
ZEBULON UNITED METHODIST CHURCH



SCALE: NOT TO SCALE

COVERED PAVILION ADDITION CONSTRUCTION DRAWINGS

114 W. SYCAMORE STREET ZEBULON, NC

JUNE 7, 2024 SEPTEMBER 30, 2024	
JANUARY 17, 2025	

OWNER/DEVELOPER

ZEBULON UNITED METHODIST CHURCH (RANDY SINK - TRUSTEE) 121 WEST GANNON AVENUE ZEBULON, NC 27597

ENCINEED	DEVELOPER
ENGINEER	DEVELOPER
THE NAU COMPANY	ZEBULON UNITED METHODIST CHURCH
P.O. BOX 810	121 WEST GANNON AVENUE
ROLESVILLE, NC 27571	ZEBULON, NC 27597
CONTACT: JEREMY J. BECKETT, PE	CONTACT: RANDY SINK
PHONE: (919) 395-2775	PHONE: (336) 972-9482

EMAIL: jbeckett@thenauco.com

EXISTING SITE DATA		
PARCEL PIN(S)	2705-25-9154	
SITE ADDRESS	114 W. SYCAMORE STREET, ZEBULON, NC	
ZONING	DTP	
PROPOSED PARCEL AREA	0.61 ACRES (26,608 SF)	
EXISTING USE	CHURCH	
RIVER BASIN	NEUSE	

SHEET INDEX

PLANS PREPARED BY OTHERS

EXISTING CONDITIONS/STAGING/DEMOLITION PLAN

GRADING AND EROSION CONTROL PLAN

LANDSCAPE PLAN

PAVILION ELEVATIONS


PRO	POSED SITE DATA
ZONING	DTP
PROPOSED NET SITE AREA	0.61 ACRES (26,608 SF)
PROPOSED USE	CHURCH PAVILION
BUILDING FOOTPRINT AREA:	
EXISTING (PRIMARY)	14,898 SF
PROPOSED (DETACHED)	3,200 SF
RATIO (35% MAX.)	3,200/14,898 = 21.48%
BUILDING HEIGHT:	
EXISTING CHURCH (PRIMARY)	56 FT)
PROPOSED PAVILION (DETACHED)	24 FT \(\int \)
PARKING SPACES REQUIRED	N/A (EXISTING CHURCH PARKING)
PARKING SPACES PROVIDED	N/A (EXISTING CHURCH PARKING)
BUILDING SETBACKS:	
FRONT	0'
SIDE	5'
REAR	15'
EXISTING IMPERVIOUS AREA	7,398 SF
PROPOSED IMPERVIOUS AREA	10,598 SF
DISTURBED AREA	7,500 SF (0.17 AC)

EROSION AND SEDIMENT CONTROL NOTE

PER WAKE COUNTY UDO 10-13-1(A), LAND DISTURBANCES LESS THAN ONE ACRE THAT ARE NOT PART OF A LARGER COMMON PLAN OF DEVELOPMENT ARE EXEMPT FROM REQUIRING AN EROSION AND SEDIMENTATION CONTROL PLAN OR PERMIT. THEREFORE, THIS PROJECT IS EXEMPT FROM OBTAINING AN EROSION AND SEDIMENTATION CONTROL PERMIT FROM WAKE COUNTY.

STORMWATER MANAGEMENT NOTE

PER TOWN OF ZEBULON LDO 1.2.1(E), DEVELOPMENT THAT CUMULATIVELY DISTURBS LESS THAN 20,000 SQUARE FEET AND IS NOT PART OF A LARGER COMMON PLAN OF DEVELOPMENT OR SALE IS EXEMPT FROM THE PROVISIONS OF THE STORMWATER ORDINANCE. THEREFORE, THIS PROJECT IS EXEMPT FROM PROVIDING ANY STORMWATER MANAGEMENT DEVICES OR OBTAINING A STORMWATER PERMIT FROM WAKE COUNTY.






ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH TOWN OF ZEBULON STANDARDS AND SPECIFICATIONS.



PO Box 810 Rolesville, NC 27571 919-435-6395 NCBELS License P-0751

PRELIMARY DRAWING - NOT RELEASED FOR CONSTRUCTION



EXISTING CONDITIONS NOTES

- 1. EXISTING CONDITIONS TAKEN FROM AN ALTA SURVEY
- PREPARED BY: WILLIAMS-PEARCE AND ASSOC., PROFESSIONAL LAND SURVEYORS, P.A.
- 2. TOPOGRAPHY FOR SITE TAKEN FROM ELECTRONIC CAD FILE PROVIDED BY: WILLIAMS-PEARCE AND ASSOC., PROFESSIONAL LAND SURVEYORS, P.A.
- 3. THE SURVEYOR DID NOT EXAMINE OR CONSIDER SUBSURFACE OR ENVIRONMENTAL CONDITIONS FOR THIS SURVEY. ALL BUILDINGS, SURFACE AND SUBSURFACE IMPROVEMENTS ON AND ADJACENT TO THE SITE ARE NOT NECESSARILY SHOWN.
- 4. THE LOCATION OF UNDERGROUND UTILITIES AS SHOWN ARE BASED ON VISIBLE EVIDENCE AND DRAWINGS PROVIDED TO THE SURVEYOR. THE LOCATION OF UNDERGROUND UTILITIES AND STRUCTURES MAY VARY FROM THE LOCATIONS SHOWN AND ADDITIONAL BURIED UTILITIES MAY EXIST.
- 5. SURVEY PERFORMED WITHOUT BENEFIT OF TITLE EXAMINATION BY A LICENSED ATTORNEY. THE PROPERTY IS SUBJECT TO ALL EASEMENTS AND RESTRICTIONS OF RECORD. NO TITLE EXAMINATION HAS BEEN PERFORMED BY THE SURVEYOR OR THE NAU COMPANY, PLLC.

DEMOLITION KEYNOTES

(1) ITEM TO REMAIN

2 REMOVE EXISTING ITEM, COORDINATE DEMOLITION WORK WITH RESPECTIVE JURISDICTIONAL AUTHORITY AND/OR UTILITY COMPANY.

3 RELOCATE EXISTING ITEM, COORDINATE RELOCATION WORK WITH RESPECTIVE JURISDICTIONAL AUTHORITY AND/OR UTILITY COMPANY.



STAGING AND DEMOLITION NOTES

- ALL TREES LABELED TO REMAIN SHALL BE ENCOMPASSED WITHIN TREE PROTECTION FENCING.
 THERE ARE NO STOCKPILES REQUIRED FOR THIS PROJECT.
- 3. CONSTRUCTION AND EMERGENCY ACCESS WILL BE FROM WEST
- SYCAMORE STREET. 4. TRAFFIC MANAGEMENT IS NOT NECESSARY FOR THE PROPOSED
- DEVELOPMENT 5. NO EXISTING SIDEWALK CLOSURES WILL BE NECESSARY FOR THIS

EXISTING CONDITIONS LEGEND EXISTING PROPERTY BOUNDARY EXISTING RIGHT-OF-WAY EXISTING PROPERTY LINE EXISTING EASEMENT EXISTING SETBACK EXISTING PROPERTY BUFFER EXISTING ROAD CENTERLINE EXISTING CURB & GUTTER **EXISTING SIDEWALK** EXISTING MAJOR (5') CONTOUR EXISTING MINOR (1') CONTOUR EX. SANITARY SEWER PIPE EXISTING WATER PIPE **EXISTING STORM SEWER PIPE** OVERHEAD UTILITIES — он — он — он — UNDERGROUND ELECTRIC ___ UE ____ UE ____ UE ___ UNDERGROUND TELEPHONE GAS LINE FENCE LINE SANITARY SEWER MANHOLE SANITARY SEWER CLEANOUT WATER VALVE WATER METER FIRE HYDRANT STORM DRAINAGE MANHOLE YARD INLET TELEPHONE PEDESTAL TELEPHONE MANHOLE ELECTRIC BOX LIGHT POLE POWER POLE

EXISTING IRON PIPE


ALL WORK IN THE PUBLIC RIGHT OF WAY SHALL BE PER CURRENT NCDOT STANDARDS AND SPECIFICATIONS. SCALE: 1"=30' PRELIMINARY DRAWING - NOT RELEASED FOR CONSTRUCTION The Nau Consulting Civi


ZEBULON UNITED METHODIST CHURCH COVERED PAVILION ADDITION


DESIGN BY:

2024-04-25

C1.0







THE NCG01 CONSTRUCTION GENERAL PERMIT lementing the details and specifications on this plan sheet will result in the construct activity being considered compliant with the Ground Stabilization and Materials Handling

ctions of the NCG01 Construction General Permit (Sections E and F, respectively). Th ermittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet nay not apply depending on site conditions and the delegated authority having jurisdiction

Si	Re te Area Description	equired Ground Stabil Stabilize within this many calendar days after ceasing	ization Timeframes Timeframe variations
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	land disturbance	None
(b)	High Quality Water (HQW) Zones	7	None
(c)	Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d)	Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e)	Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zor -10 days for Falls Lake Watershed unles there is zero slope

activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved

GROUND STABILIZATION SPECIFICATION

tabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the chniques in the table below:

- Temporary Stabilization Temporary grass seed covered with straw or
 Permanent grass seed covered with straw or other mulches and tackifiers Hydroseeding Rolled erosion control products with or
- other mulches and tackifiers Geotextile fabrics such as permanent soil without temporary grass seed Hydroseeding Appropriately applied straw or other mulch
 Shrubs or other permanent plantings covered with mulch . Uniform and evenly distributed ground cover
- sufficient to restrain erosion
- Rolled erosion control products with grass seed

retaining walls

. Structural methods such as concrete, asphalt or

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculant. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions Provide ponding area for containment of treated Stormwater before discharging
- Store flocculants in leak-proof containers that are kept under storm-resistant cover

Maintain vehicles and equipment to prevent discharge of fluids. Provide drip pans under any stored equipment.

- Identify leaks and repair as soon as feasible, or remove leaking equipment from th Collect all spent fluids, store in separate containers and properly dispose as
- hazardous waste (recycle when possible). Remove leaking vehicles and construction equipment from service until the probl
- has been corrected. Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum produ to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

EQUIPMENT AND VEHICLE MAINTENANCE

- Never bury or burn waste. Place litter and debris in approved waste containers Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available. Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland
- Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers. Anchor all lightweight items in waste containers during times of high winds.

Empty waste containers as needed to prevent overflow. Clean up immediately if

Dispose waste off-site at an approved disposal facility. On business days, clean up and dispose of waste in designated waste containers

PAINT AND OTHER LIQUID WASTE


- Do not dump paint and other liquid waste into storm drains, streams or wetlands. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available. Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from

ORTABLE TOILETS

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or pla on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and repla with properly operating unit.

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile. Provide stable stone access point when feasible.
- Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.





- Do not discharge concrete or cement slurry from the site. Dispose of, or recycle settled, hardened concrete residue in accordance with local
- and state solid waste regulations and at an approved facility. Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within
- lot perimeter silt fence. Install temporary concrete washouts per local requirements, where applicable. If alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project. Locate washouts at least 50 feet from storm drain inlets and surface waters unless it
- can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow. Locate washouts in an easily accessible area, on level ground and install a stone
- entrance pad in front of the washout. Additional controls may be required by the
- Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location. Remove leavings from the washout when at approximately 75% capacity to limit
- overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions. . At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance

IERBICIDES, PESTICIDES AND RODENTICIDES

caused by removal of washout.

- Store and apply herbicides, pesticides and rodenticides in accordance with label
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of

SELF-INSPECTION, RECORDKEEPING AND REPORTING

They are less than 25 gallons but cannot be cleaned up within 24 hours,

 Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA

(e) Noncompliance with the conditions of this permit that may endanger health or the

After a permittee becomes aware of an occurrence that must be reported, he shall contact

other requirements listed below. Occurrences outside normal business hours may also be

Reporting Timeframes (After Discovery) and Other Requirements

with the federal or state impaired-waters conditions.

Within 24 hours, an oral or electronic notificatio

Within 24 hours, an oral or electronic notification

sediment and actions taken to address the cause of the deposition.

Division staff may waive the requirement for a written report on a If the stream is named on the NC 303(d) list as impaired for sediment.

related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff

Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and

A report at least ten days before the date of the bypass, if possible.

The report shall include an evaluation of the anticipated quality and

Within 7 calendar days, a report that includes an evaluation of the

 Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not

been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and

prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6).

determine that additional requirements are needed to assure compliance

eported to the Department's Environmental Emergency Center personnel at (800)

deposition in a
• Within 7 calendar days, a report that contains a description of the

(a) Visible sediment • Within 24 hours, an oral or electronic notification.

location of the spill or release.

quality and effect of the bypass.

effect of the bypass.

· They cause sheen on surface waters (regardless of volume), or

They are within 100 feet of surface waters (regardless of volume).

accidental poisoning. Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.

SECTION C: REPORTING

(b) Oil spills if:

858-0368.

(b) Oil spills and

1(b)-(c) above

ypasses [40 CFR

22.41(m)(3)]

(d) Unanticipated

bypasses [40 CFR

with the conditions

of this permit that

CFR 122.41(I)(7)]

health or the

122.41(m)(3)]

hazardous

I. Occurrences that Must be Reported

They are 25 gallons or more,

Permittees shall report the following occurrences

(Ref: 40 CFR 302.4) or G.S. 143-215.85.

2. Reporting Timeframes and Other Requirements

(d) Anticipated bypasses and unanticipated bypasses.

(a) Visible sediment deposition in a stream or wetland.

Do not stockpile these materials onsite.

- ZARDOUS AND TOXIC WASTE Create designated hazardous waste collection areas on-site.
- Place hazardous waste containers under cover or in secondary containment. Do not store hazardous chemicals, drums or bagged materials directly on the ground.



EFFECTIVE: 04/01/19

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

SECTION B: RECORDKEEPING

SECTION A: SELF-INSPECTION below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or

SELF-INSPECTION, RECORDKEEPING AND REPORTING

Inspect	(during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those unattended days (anc this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	I. Identification of the measures inspected, Date and time of the inspection, Name of the person performing the inspection, Indication of whether the measures were operating properly, Description of maintenance needs for the measure, Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDCs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	Identification of the discharge outfalls inspected, Date and time of the inspection, Name of the person performing the inspection, Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, Indication of visible sediment leaving the site, Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.
(6) Ground stabilization measures	After each phase of grading	The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover).

NOTE: The rain inspection resets the required 7 calendar day inspection requiremen

timeframe or an assurance that they will be provided as

SELF-INSPECTION, RECORDKEEPING AND REPORTING

1. E&SC Plan Documentatio The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for

inspection at all times during normal business hours.			
Item to Document	Documentation Requirements		
(a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan.	Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC		

shown on the approved E&SC plan.	E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC plan.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved

- ground cover specifications. omplete, date and sign an inspection report. requirements for all E&SC measures (e) Corrective actions have been taken Initial and date a copy of the approved E&SC
- plan or complete, date and sign an inspection report to indicate the completion of the 2. Additional Documentation to be Kept on Site In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the
- Division provides a site-specific exemption based on unique site conditions that make this requirement not practical: (a) This General Permit as well as the Certificate of Coverage, after it is received.
- (b) Records of inspections made during the previous twelve months. The permittee shall ecord the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if
- 3. Documentation to be Retained for Three Years All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

shown to provide equal access and utility as the hard-copy records.

- shall not commence until the E&SC plan authority has approved these items,
- b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit,
- (c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include
- d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above, e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and f) Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States

DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

ediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). lon-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- (a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal
- properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems,

Division staff may waive the requirement for a written report on a case-by-case basis.

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

NORTH CAROLINA

Environmental Quality

NPDES Stormwater Discharge Permit for Construction Activities (NCGO1) NCDENR/Division of Water Quality

NEW STABILIZATION TIMEFRAMES (Effective Aug. 3, 2011) SITE AREA STABILIZATION TIMEFRAME EXCEPTIONS DESCRIPTION Perimeter dikes, 7 days swales, ditches, slopes High Quality Water 7 days (HQW) Zones Slopes steeper than 7 days If slopes are 10' or less in length and are not steeper than 2:1, 14 days are Slopes 3:1 or flatter 14 days 7 days for slopes greater than 50' in llenath.

Seedbed Preparation:

slopes flatter than 4:1

All other areas with 14 days

1. Chisel compacted areas and spread topsoil three inches deep over adverse soil

Zones.

None, except for perimeters and HQW

conditions, if available Rip the entire area to six inches deep.

after permanent cover is established.

- 3. Remove all loose rock, roots and other obstructions, leaving surface reasonably
- smooth and uniform. 4. Apply agricultural lime, fertilizer and superphosphate uniformly and mix with soil
- (see mixture below). 5. Continue tillage until a well-pulverized, firm, reasonably uniform seedbed is
- prepared four to six inches deep 6. Seed on a freshly prepared seedbed and cover seed lightly with seeding equipment
- or cultipack after seeding. 7. Mulch immediately after seeding and anchor mulch. 8. Inspect all seeded areas and make necessary repairs or reseedings within the
- planting season, if possible. If stand should be more than 60% damaged, reestablish following the original lime, fertilizer and seeding rates. 9. Consult S&EC Environmental Engineers on maintenance treatment and fertilization

Mixture

Agricultural Limestone	2 tons/acre (3 tons/acre in clay soils)
Fertilizer	1,000 lbs/acre – 10-10-10
Superphosphate	500 lbs/acre – 20% analysis
Mulch	2 tons/acre – small grain straw
Anchor	Asphalt emulsion at 300 gals/acre

SOIL STABILIZATION SHALL BE ACHIEVED ON ANY AREA OF A SITE WHERE AND-DISTURBING ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED ACCORDING TO THE FOLLOWING SCHEDULE:

- ALL PERIMETER DIKES, SWALES, DITCHES, PERIMETER SLOPES AND ALL SLOPES STEEPER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1) SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN 7 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY.
- ALL OTHER DISTURBED AREAS SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN 14 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY.

Seding Schedule

For Shoulders, Side Ditches, Slopes (Max 3:1

Date	Туре	Planting Rate
Aug 15– Nov 1	Tall Fescue	300 lbs/acre
Nov 1– Mar 1	Tall Fescue & Abruzzi Rye	300 lbs/acre
Mar 1–Apr 15	Tall Fescue	300 lbs/acre
Apr 15– Jun 30	Hulled Common Bermudagrass	25 lbs/acre
Jul 1– Aug 15	Tall Fescue AND Browntop Millet or Sorghum-Sudan Hybrids***	125 lbs/acre (Tall Fescue); 35 lbs/acre (Browntop Millet); 30 lbs/acre (Sorghum-Sudan Hybrids)

For Shoulders, Side Ditches, Slopes (3:1 to 2:1):

Date	Туре	Planting Rate
Mar 1– Jun 1	Sericea Lespedeza (scarified) and use the following combinations:	50 lbs/acre (Sericea Lespedeza);
Mar 1– Apr 15	Add Tall Fescue	120 lbs/acre
Mar 1– Jun 30	Or add Weeping Love grass	10 lbs/acre
Mar 1– Jun 30	Or add Hulled Common Bermudagrass	25 lbs/acre
Jun 1– Sept 1	Tall Fescue AND Browntop Mullet or Sorghum-Sudan Hybrids***	120 lbs/acre (Tall Fescue); 35 lbs/acre (Browntop Mullet); 30 lbs/acre (Sorghum-Sudan Hybrids)
Sept 1– Mar 1	Sericea Lespedeza (unhulled – unscarified) AND Tall Fescue	70 lbs/acre (Sericea Lespedeza); 120 lbs/acre (Tall Fescue)
Nov 1– Mar 1	AND Abruzzi Rye	25 lbs/acre

SEEDING SCHEDULE

NOTE: LOCAL AND TENANT STANDARDS AND DETAILS SHALL SUPERCEDE THE DETAILS SHOWN ON THIS SHEET. CONTRACTOR SHALL CORRDINATE ALL WORK WITH LOCAL GOVERNING JURISDICTION AND THE ARCHITECTURAL PLANS FOR THIS PROJECT AND VERIFY ALL LOCAL REQUIREMENTS PRIOR TO ANY CONSTRUCTION.

Nau Iting Civ The Consu

Company vil Engineers

 $\frac{1}{2}$ UNITED METHODIST CI

ZEBULON U N

PROJECT NO:

DESIGN BY:


SCALE:

DRAWN BY: JJB

> NTS 2024-04-25

JJB

PRELIMINARY DRAWING - NOT RELEASED FOR CONSTRUCTION



THIS TREE PROTECTION FENCE DETAIL IS REQUIRED

FOR PROTECTION OF TREE CONSERVATION AREAS (UDO ARTICLE 9.1. TREE CONSERVATION) AND FOR CREDIT OF EXISTING TREES (UDO SECTION 7.2.7.E.)

NOTES:

1. WARNING SIGNS TO BE MADE OF DURABLE, WEATHERPROOF MATERIAL.

2. LETTERS TO BE SY HIGH MINIMUM, CLEARLY LEGIBLE AND SPACED AS DETAILED.

3. PLACEA SIGN AT EACH DOF LINEAR THEE PROTECTION AND SO ON CENTER THEREAFTER.

4. FOR TREE PROTECTION AREAS LESS THAN 200 IN PERIMETER, PROVIDE NO LESS THAN ONE SIGN PER PROTECTION AREA.

5. ATTACH SIGNS SECURELY TO FENCE POSTS AND FABRIC.

6. MAINTAIN TREE PROTECTION FENCE THROUGHOUT DURATION OF PROJECT.

7. ADDITIONAL SIGNS MAY BE REQUIRED BY CITY OF RALEIGH BASED ON ACTUAL FIELD CONDITIONS.


TREE PROTECTION FENCING SHALL NOT EXCEED FOUR FEET

IN HEIGHT. SEE DETAIL FOR SPECIFICATIONS.

TREE PROTECTION AREA

DO NOT ENTER


WARNING SIGN DETAIL



D2.0


Company vil Engineers

Nau Ilting Civ



Building Elevation

1/4 = 1-0



Building Elevation

1/4 = 1-0

H

SO3 EAST FRANKLIN STREE

RALEIGH, NORTH CAROLIN

ZEBULON UNITED METHODIST CHURCH

RAWING DISTRIBUTION

JULY 2024 FOR REVIEW ONLY

NOT FOR CONSTRUCTION

HEET NO.