



COOK OUT 15 LAURA LANE, SUITE 300 THOMASVILLE, NORTH CAROLINA 27360 TELEPHONE: (336) 215-7025 FAX: (336) 474-1849

SITE ADDRESS: 1200 NORTH ARENDELL AVENUE ZEBULON, NORTH CAROLINA CSD PROJECT NUMBER: OUT-1502

TOWN OF ZEBULON PROJECT NUMBER: 856796

CONTACT INFORMATION WATER: CITY OF RALEIGH PUBLIC UTILITIES 222 W. HARGETT STREET RALEIGH, NC 27601 CONTACT: CESAR SANCHEZ PHONE: 919-996-2673 **EROSION & SEDIMENT CONTROL** WAKE COUNTY GOVERNMENT AND STORMWATER ENVIRONMENTAL SERVICE / WATER QUALITY DIVISION CONTACT: KARYN PAGEAU karyn.pageau@wake.gov PHONE: 919-796-8769 STORM DRAINAGE. WAKE COUNTY STORMWATER DIVISION OF WATER QUALITY 336 FAYETTEVILLE STREET CONTACT: DEBORAH L. RYALS PHONE: 919-856-7400 SANITARY SEWER: CITY OF RALEIGH PUBLIC UTILITIES 222 W. HARGETT STREET RALEIGH, NC 27601 CONTACT: CESAR SANCHEZ PHONE: 919-996-2673 GAS: PSNC ENERGY CONTACT: BUSINESS SERVICES PHONE: 919-452-2177 DUKE ENERGY PROGRESS ELECTRIC: CONTACT: BUSINESS SERVICES PHONE: 800-452-2777 TELEPHONE: CONTACT: BUSINESS SERVICES PHONE: 800-221-0000 PLANNING / ZONING: TOWN OF ZEBULON PLANNING DEPT. 1003 N. ARENDELL AVENUE ZEBULON, NC 27597 CONTACT: SENIOR PLANNER PHONE: 919-823-1809

24 HOUR CONTACT BRODIE KEY **CONSTRUCTION MANAGER** TELEPHONE: (336) 250-2110

ATTENTION CONTRACTORS

ENVIRONMENTAL CONSULTANT SIGNATURE

EROSION CONTROL, STORMWATER

AND FLOODPLAIN MANAGEMENT

EROSION CONTROL \square S-

FLOOD STUDY

S-

STORMWATER MGMT. ☐ S-

APPROVED

DATE

The Contractor responsible for the extension of water, sewer, and/or reuse, as approved in these plans, is responsible for contacting the Infrastructure Inspections Division and schedule a Pre-construction meeting on the Development Portal prior to beginning any construction. Raleigh Water must be contacted at (919) 996-4540 at least twenty-four hours prior to beginning any work activity around critical water and sewer infrastructure.

Failure to notify City Departments in advance of beginning construction, will result in the issuance of monetary fines, and require reinstallation of any water or sewer facilities not inspected as a result of this notification failure.

Failure to call for Inspection, install a downstream plug, have permitted plans on the jobsite, or any other violation of City of Raleigh Standards will result in a fine and possible exclusion from future work in the City of Raleigh.

SHEET INDEX

C-1	EXISTING CONDITIONS / DEMOLITION PLAN
C-2	SITE PLAN

GRADING PLAN EROSION CONTROL PLAN - PHASE I

EROSION CONTROL PLAN - PHASE 2 **EROSION CONTROL PLAN - PHASE 3**

NPDES STABILIZATION PLAN

NPDES STABILIZATION DETAILS HWY 96 TURN LANE PLAN

UTILITY PLAN

DETAILS DETAILS

DETAILS C-6 **DETAILS** C-6a

CITY OF RALEIGH DETAILS

CITY OF RALEIGH DETAILS SCM DETAILS

SCM DETAILS **DETAILS** C-10

TOWN OF ZEBULON DETAILS C-11

TOWN OF ZEBULON DETAILS C-13 LANDSCAPE PLAN

LANDSCAPE DETAILS AND NOTES LIGHTING PLAN C-15

JONES STREET PLAN AND PROFILE **BUILDING ELEVATIONS**

BUILDING ELEVATIONS


Phase Number(s)	PHASE 1	PHASE 2	PHASE 3
Number of Lot (s)	1	N/A	N/A
Lot Number (s) by Phase	N/A	N/A	N/A
Number of Units	1	N/A	N/A
Livable Buildings	1 COMMERCIAL	N/A	N/A
Open Space?	34,243 SF	N/A	N/A
Number of Open Space Lots	N/A	N/A	N/A
Public Water (LF)	223 LF	N/A	N/A
Private Water* (LF)	N/A	N/A	N/A
Public Sewer (LF)	N/A	N/A	N/A
Public Force Main (LF)	N/A	N/A	N/A
Private Sewer** (LF)	N/A	N/A	N/A
Public Street (LF) - FULL	227 LF- JONES ST.	N/A	N/A
Public Street (LF) - PARTIAL	280 LF- 2 TURN LANES	N/A	N/A
Public Sidewalk (LF) - FULL	761 LF	N/A	N/A
Public Sidewalk (LF) – PARTIAL	N/A	N/A	N/A
Multi-Use Path*** (LF)	N/A	N/A	N/A
Public Stormdrain (LF)	181 LF	N/A	N/A
Street Signs (LF)	2 (JONES ST)	N/A	N/A
Water Service Stubs	1	N/A	N/A
Sewer Service Stubs	1	N/A	N/A
Average Daily Flow per phase****		N/A	N/A

* Water mains 4" and larger

Sewer mains and manholes as part of a collection system * 10 or 12 ft wide path in lieu of sidewalk or a Multi-Use path as part of a development amenity ****Entire Project Flow. Based on 75gpd per bedroom for residential (Apartments, single Family dwelling, townhouse, condos), or based on 15A NCAC 02T .0114 Wastewater Design Flow Rates for Commercial and Industrial.

SITE ADDRESS:	1200 NORTH ARENDELL AVENUE
PARCEL IDENTIFICATION NUMBER:	2706008182
OWNER / DEVELOPER:	COOK OUT 15 LAURA LANE, SUITE 300 THOMASVILLE, NORTH CAROLINA 27360 PHONE: (336) 215-7025 FAX: (336) 474-1849
DESIGNER:	COMMERCIAL SITE DESIGN, PLLC 8312 CREEDMOOR ROAD RALEIGH, NORTH CAROLINA 27613 PHONE: (919) 848-6121 FAX: (919) 848-3741
ZONING:	HC (HEAVY COMMERCIAL)
EXISTING USE:	VACANT LOT
PROPOSED USE:	RESTAURANT WITH DRIVE-THRU
BUILDING SETBACKS: RIGHT OF WAY SIDE REAR	30 FEET 0 FEET 25 FEET
PARKING REQUIREMENTS:	1 SPACE PER 4 SEATS 160 SEATS / 4 = 40 SPACES
PARKING PROVIDED:	48 REGULAR SPACES 2 ACCESSIBLE SPACES 50 TOTAL SPACES
SITE AREA: DISTURBED AREA: EXISTING IMPERVIOUS AREA: PROPOSED IMPERVIOUS AREA:	83,368 SF OR 1.91 ACRES 105,763 SF OR 2.42 ACRES 0 SF 52,846 SF OR 1.21 ACRES
BUILDING AREA:	4,909 SF
BITUMINOUS AREA:	37,232 SF
CONCRETE AREA:	10,705 SF
NUMBER OF RESTAURANT SEATS:	60 MAIN DINING ROOM & 100 SEATS PARTY ROOM
WATER:	CITY OF RALEIGH PUBLIC UTILITIES
SEWER:	CITY OF RALEIGH PUBLIC UTILITIES
OPEN SPACE:	REQUIRED: 3% OF LOT AREA =2,501 SF PROVIDED: 34,243 SF

SITE INFORMATION














A	2023-06-08	REVISED PER TOWN	KL
2	2023-11-06	TRC AND WAKE COUNTY COMMENTS	DDH
3	2024-09-26	REV. ENTRANCE DRIVES/ADD TURN LANES	DDH
<u>A</u>	2025-04-02	REVISE BUILDING FOOTPRINT	DDH
<u>\$</u>	2025-06-24	REVISE BUILDING FOOTPRINT	DDH
<u> </u>	2025-08-28	REVISED PER TOWN COMMENTS	DDH
\triangle	2025-10-16	REVISED PER TOWN COMMENTS	JMW
NO.	DATE	DESCRIPTION	BY

















GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH

mplementing the details and specifications on this plan sheet will result in the constructior activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction

	Re	equired Ground Stabil	ization Timeframes
Si	te Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b)	High Quality Water (HQW) Zones	7	None
(c)	Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d)	Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e)	Areas with slopes flatter than 4:1	14	 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope

ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. U	Jse one of the
techniques in the table below:	

•
Temporary Stabilization
• Temporary grass seed covered with straw
other mulches and tackifiers

- other mulches and tackifiers Hydroseeding Rolled erosion control products with or
- without temporary grass seed Appropriately applied straw or other mulch
- Plastic sheeting
- - Hydroseeding • Shrubs or other permanent plantings covered with mulch
 - Uniform and evenly distributed ground cover sufficient to restrain erosion • Structural methods such as concrete, asphalt or

Permanent Stabilization

• Permanent grass seed covered with straw or

Geotextile fabrics such as permanent soil

other mulches and tackifiers

retaining walls Rolled erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- Apply flocculants at the concentrations specified in the NC DWR List of Approved *PAMS/Flocculants* and in accordance with the manufacturer's instructions.
- Provide ponding area for containment of treated Stormwater before discharging Store flocculants in leak-proof containers that are kept under storm-resistant cover
- or surrounded by secondary containment structures.

QUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- Provide drip pans under any stored equipment. Identify leaks and repair as soon as feasible, or remove leaking equipment from the
- Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- Remove leaking vehicles and construction equipment from service until the problem has been corrected Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

to a recycling or disposal center that handles these materials

- Never bury or burn waste. Place litter and debris in approved waste containers. Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
- . Locate waste containers at least 50 feet away from storm drain inlets and surface
- waters unless no other alternatives are reasonably available. Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland
- Cover waste containers at the end of each workday and before storm events or
- provide secondary containment. Repair or replace damaged waste containers. Anchor all lightweight items in waste containers during times of high winds. Empty waste containers as needed to prevent overflow. Clean up immediately if

9. On business days, clean up and dispose of waste in designated waste containers.

containers overflow. B. Dispose waste off-site at an approved disposal facility.

PAINT AND OTHER LIQUID WASTE

- Do not dump paint and other liquid waste into storm drains, streams or wetlands. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- 4. Containment must be labeled, sized and placed appropriately for the needs of site. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place
- on a gravel pad and surround with sand bags. Provide staking or anchoring of portable toilets during periods of high winds or in high

Contain liquid wastes in a controlled area.

foot traffic areas. Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.
- Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.

- Do not discharge concrete or cement slurry from the site. Dispose of, or recycle settled, hardened concrete residue in accordance with local
- and state solid waste regulations and at an approved facility. . Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- . Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
- Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the
- approving authority. Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
- Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
- 10. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

HERBICIDES, PESTICIDES AND RODENTICIDES

- Store and apply herbicides, pesticides and rodenticides in accordance with label
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- . Do not stockpile these materials onsite.

- Create designated hazardous waste collection areas on-site.
- Place hazardous waste containers under cover or in secondary containment. Do not store hazardous chemicals, drums or bagged materials directly on the ground.

EFFECTIVE: 04/01/19

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend of holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those un attended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded a "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	 Identification of the measures inspected, Date and time of the inspection, Name of the person performing the inspection, Indication of whether the measures were operating properly, Description of maintenance needs for the measure, Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	 Identification of the discharge outfalls inspected, Date and time of the inspection, Name of the person performing the inspection, Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, Indication of visible sediment leaving the site, Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	 If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.
(6) Ground stabilization measures	After each phase of grading	1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization

soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

measures have been provided within the required

timeframe or an assurance that they will be provided as

SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION B: RECORDKEEPING **E&SC Plan Documentation**

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

Documentation Requirements
Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.
Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.
Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
Complete, date and sign an inspection report.
Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

2. Additional Documentation to be Kept on Site

In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- (a) This General Permit as well as the Certificate of Coverage, after it is received.
- (b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

3. Documentation to be Retained for Three Years

All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

PART II, SECTION G, ITEM (4) DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- (a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items, (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit,
- (c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems,
- (d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above, (e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
- (f) Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

SELF-INSPECTION, RECORDKEEPING AND REPORTING **SECTION C: REPORTING**

- 1. Occurrences that Must be Reported Permittees shall report the following occurrences:
- (a) Visible sediment deposition in a stream or wetland.
- (b) Oil spills if:
- They are 25 gallons or more,
- They are less than 25 gallons but cannot be cleaned up within 24 hours,
- They cause sheen on surface waters (regardless of volume), or
- They are within 100 feet of surface waters (regardless of volume).
- Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.
- (d) Anticipated bypasses and unanticipated bypasses.
- (e) Noncompliance with the conditions of this permit that may endanger health or the environment.

2. Reporting Timeframes and Other Requirements

of this permit that

may endanger

environment[40

CFR 122.41(I)(7)]

health or the

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.

Occurrence	Re	eporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment	•	Within 24 hours, an oral or electronic notification.
deposition in a stream or wetland	•	Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliant with the federal or state impaired-waters conditions.
(b) Oil spills and release of hazardous substances per Item 1(b)-(c) above	•	Within 24 hours , an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.
(c) Anticipated	•	A report at least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and

The report shall include an evaluation of the anticipated quality and 122.41(m)(3)] effect of the bypass. Within 24 hours, an oral or electronic notification.

(d) Unanticipated bypasses [40 CFR • Within 7 calendar days, a report that includes an evaluation of the 122.41(m)(3)] quality and effect of the bypass. (e) Noncompliance Within 24 hours, an oral or electronic notification with the conditions | • Within 7 calendar days, a report that contains a description of the

> including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6). Division staff may waive the requirement for a written report on a case-by-case basis

noncompliance, and its causes; the period of noncompliance,

I. ACTUAL LOCATION DETERMINED IN BELOW GRADE WASHOUT STRUCTURE

ONSITE CONCRETE WASHOUT

STRUCTURE WITH LINER

TEL 919 856 7400 Environmental Sedimentation & Erosion Control Services 336 Fayetteville St. • P.O. Box 550 • Raleigh, NC 27602

Effective September 1, 2008 Soil stockpiles shall be located on the approved plan and shall adhere to the following requirements:

Design Criteria


- a. A 25-foot temporary maintenance and access easement shall be shown around all proposed stockpiles (erosion control measures surrounding the stockpile shall be shown at the outer limit of this easement).
- b. Stockpile footprints shall be setback a minimum of 25' from adjacent property lines.
- c. A note shall be provided on the approved plan that stockpile height shall not exceed 35 feet.
- d. Stockpile slopes shall be 2:1 or flatter.
- e. Approved BMPs shall be shown on a plan to control any potential sediment loss from a stockpile.
- f. Stockpiling materials adjacent to a ditch, drainageway, watercourse, wetland, stream buffer, or other body of water shall be avoided unless an alternative location is demonstrated to be unavailable.
- g. Any concentrated flow likely to affect the stockpile shall be diverted to an approved BMP.
- h. Off-site spoil or borrow areas must be in compliance with Wake County UDO and State Regulations. All spoil areas over an acre are required to have an approved sediment control plan. Developer/Contractor shall notify Wake County of any offsite disposal of soil, prior to disposal. Fill of FEMA Floodways and Non-encroachment Areas are prohibited except as otherwise provided by subsection 14-19-2 of the Wake County Unified Development Ordinance (certifications and permits required).

Maintenance Requirements to be Noted on the Plan

- . Seeding or covering stockpiles with tarps or mulch is required and will reduce erosion problems. Tarps should be keyed in at the top of the slope to keep water from running underneath the plastic.
- . If a stockpile is to remain for future use after the project is complete (builders, etc.), the financial responsible party must notify Wake County of a new responsible party for that stockpile.

k. The approved plan shall provide for the use of staged seeding and

mulching on a continual basis while the stockpile is in use. 1. Establish and maintain a vegetative buffer at the toe of the slope (where practical).










OUT-1502 OUT1502-NPDES STH N.T.S.


06-24-2025


C-3e


NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING


EFFECTIVE: 04/01/19
























PROJECT NO. OUT-1502

PLENAME: OUT1502-DTL2

PRAWN BY: STH

SCALE: N.T.S.


PATE: 06-24-2025


CHEET NO.


C-6


200

ambate












STANDARD CLEAN WATER DIVERSION

EFFECTIVE: 01/31/08














ROJECT NO.	OUT-1502
ILENAME:	OUT1502-DTL2a
RAWN BY:	STH
CALE:	N.T.S.
ATE:	06-24-2025
HEET NO.	C-6a


200











DRUM ROLLER TO ACHIEVE A SMOOTH, LEVEL PATCH.





















SHEET 1 OF 2


CITY OF RALEIGH

STANDARD DETAIL

ASPHALT PAVEMENT PATCH AND RCP PIPE BACKFILL

T-10.05.1









DESCRIPTION	DATE	NO.
REVISED PER TOWN COMMENTS	2025-10-16	2
REVISED PER TOWN COMMENTS	2025-08-28	9
REVISE BUILDING FOOTPRINT	2025-06-24	9
REVISE BUILDING FOOTPRINT	2025-04-02	4
REV. ENTRANCE DRIVES/TURN LANES	2024-09-26	ε
2023-10-17 TRC & WAKE COUNTY COMMENTS	2023-10-17	2




COOK OUT 15 LAURA LANE, SUITE 300 THOMASVILLE, NC 27360 TELEPHONE: (336) 215-7025 FAX: (336) 474-1849


H HAMBURGERS
TH ARENDELL AVENUE
ON, NORTH CAROLINA

FRESH 1200 NORTH ZEBULON, CITY OF R.

ROJECT NO.	OUT-1502			
LENAME:	OUT1502-DTL3			
RAWN BY:	STH			
CALE:	N.T.S.			
ATE:	06-24-2025			
HEET NO.	$\overline{}$			

U-/





REINFORCING REQUIREMENTS							
I.D. PIPE	REBAR SIZE	"X" BAR LENGTH	"X" BAR WEIGHT	"Y" BAR LENGTH	"Y" BAR WEIGHT	NO. REQUIRED	
6" - 36"	#5	2'-2"+ O.D. PIPE	1.043 LBS/FT	1'-1"	1.1 LBS. EACH	X-24, Y-12	
48" & greater	#6	3'-0"+ O.D. PIPE	1.502 LBS/FT	1'-3"	1.9 LBS. EACH	X-24, Y-12	

THRUST COLLAR, AND THRUST SCHEDULE					
I.D. PIPE	"A"	"B"	"C"	"D"	
6" - 16"	1'-4"	1'-7"	2"	3/8"	
20" - 24"	1'-4"	1'-7"	3"	1/2"	
30" - 36"	1'-4"	1'-7"	4"	5/8"	
48" & greater	1'-8"	1'-9"	6"	7/8"	

- 1. SEE STANDARD DETAIL W-9 FOR THRUST BLOCK LOCATIONS. 2. CONCRETE SHALL BE 3000 PSI AND TRANSIT MIXED.
- 3. REINFORCING BARS SHALL BE DEFORMED AND TIED TOGETHER. 4. TRENCH BOTTOM WIDTH IN VICINITY OF THRUST BLOCK INSTALLATION SHALL BE THE
- MINIMUM WIDTH AS SHOWN ON STANDARD DETAIL W-3.
- 5. BACKFILL TAMPED IN 6" LIFTS PER STANDARD DETAIL W-3. 6. THRUST COLLAR MUST BE FACTORY WELDED ON BOTH SIDES ALONG BOTH EDGES OF COLLAR AROUND CIRCUMFERENCE.

				ALL AREAS	GIVEN IN S	QUARE FEET	Г.			
SERMO		N. S.					008 WAY 108 WEST	80x 100 May, 2.7.		777 OQ 7000
6"										,
11 1/4°	1,108	1	1	1	1	1	1	2	1	
22 1/2°	2,207	1	2	2	1	1	1	3	1	
45°	4,328	2	3	3	1	1	2	5	1	
90°	7,996	2	4	5	1	1	2	8	1	
PLUG	5,655	2	3	4	1	1	2	6	1	
8"										
11 1/4°	1,970	1	1	2	1	1	1	2	1	
22 1/2°	3,922	1	2	3	1	1	1	4	1	
45°	7,694	2	4	5	1	1	2	8	1	
90°	14,215	4	8	9	2	2	4	15	2	
PLUG	10,053	3	5	6	2	2	3	10	1	
12"										
11 1/4°	4,433	2	3	3	1	1	2	5	1	
22 1/2°	8,826	3	5	6	2	2	3	9	1	
45°	17,312	5	9	11	3	3	5	18	2	
90°	31,983	8	16	19	4	4	8	32	4	
PLUG	22,619	6	12	14	3	3	6	23	3	
16"										
11 1/4°	7,881	2	4	5	1	1	2	8	1	
22 1/2°	15,691	4	8	10	2	2	4	16	2	
45°	30,779	8	16	19	4	4	8	31	4	
90°	56,861	15	29	35	8	8	15	57	6	
PLUG	40,213	10	21	25	5	5	10	41	5	

REACTION BEARING AREAS FOR HORIZONTAL

BASED ON TEST PRESSURE OF 200 P.S.I.

WATER PIPE BENDS


REACTION BEARING AREAS ARE IN SQUARE FEET MEASURED IN A VERTICAL PLANE IN THE TRENCH SIDE AT AN ANGLE OF 90° TO THE THRUST VECTOR. USE 6" - 90 BEND VALUE FOR HYDRANTS FOR ADDITIONAL SAFETY FACTOR.

CITY OF RALEIGH


DEPARTMENT OF PUBLIC UTILITIES

THRUST BLOCKING DESIGN

QUANTITY TABLE



DVVG. NO.	1001010	DATE 11-3-99	REVISIONS	DATE 1-20-05		
DWG. NO.	WATER METER BOX DETAIL REVISIONS DATE REVISIONS DATE					
	DEPARTMENT OF PUBLIC UTILITIES					
	CITY OF RALEIGH					



CITY OF RALEIGH

DEPARTMENT OF PUBLIC UTILITIES

3-31-00 J.P.S.

90° BEND

2-15-05

10-29-10


TRENCH BOTTOM DIMENSIONS & BACKFILLING

REQUIREMENTS FOR DUCTILE IRON

NOTES:

- 1. CONCRETE SHALL BE 3000 PSI 2. CONCRETE SHALL NOT CONTACT BOLTS OR ENDS OF MECHANICAL
- 3. TRENCHES SHALL CONFORM TO STANDARD DETAIL W-3. 4. SEE STANDARD THRUST BLOCK TABLES, W-10 THRU W-11, FOR AREA
- OF CONCRETE REQUIRED. 5. ALL BENDS AND INTERSECTIONS SHALL HAVE CONCRETE THRUST

	CITY OF RALEIGH					
	DEPARTMENT OF PUBLIC UTILITIES					
	STANDARD THRUST BLOCKING VIEWS					
DWG. NO.	REVISIONS	DATE	REVISIONS	DATE		
W-9	D.W.C.	3-1-87	RRH	3-31-00		
VV- <i>J</i>		9-7-99	D.H.L.	6-18-08		



R	ROD REQUIREMENTS				
SIZE OF 45 BEND	STATIC THRUST IN POUNDS	NO. OF RODS REQUIRED			
6"	4,328	2			
8"	7,694	4			
12"	17,312	4			
16"	30,779	8			
24"	69,252	8			

GENERAL NOTES:

1. STEEL RODS AND BOLTS SHALL BE 3/4" HOT DIPPED GALVANIZED.

2. CONCRETE SHALL NOT CONTACT BOLTS OR ENDS OF MECHANICAL

5. 3' MINIMUM COVER MUST BE MAINTAINED ON ALL WATER MAINS

JOINT BENDS. 3. RESTRAINED MECHANICAL GLANDS TO BE USED AT ALL FITTINGS.
4. MUST USE DUCTILE IRON EYE BOLTS WHERE NECESSARY.

CITY OF RALEIGH

DEPARTMENT OF PUBLIC UTILITIES


THRUST BLOCKING DESIGN DATA

FOR WATER MAINS

1-21-00

6-18-08

		CITY OF RALEIGH				
	DEPARTMENT OF PUBLIC UTILITIES					
	STANDARD VERTICAL BEND					
DWG. NO.	REVISIONS	DATE	REVISIONS	DATE		
W-12	ABB	4-6-04	J.P.S.	11-1-10		
VV-12	D.H.L.	6-18-08				



1. ALL ABOVE GROUND ENCLOSURES MUST HAVE ADEQUATE DRAINAGE (TWICE THE DIAMETER OF THE SUPPLY PIPE)


2. REDUCED PRESSURE BACKFLOW PRESENTERS MAY BE LOCATED IN A BUILDING PROVIDED THERE ARE NO OTHER UNPROTECTED TAPS BETWEEN THE MAIN AND THE BUILDING. DRAINAGE IN A BUILDING MUST BE TWICE THE DIAMETER OF THE SUPPY PIPE. 3. ABOVE GROUND INSULATED VAULTS MUST BE ASSE 1060 APPROVED ABOVE GROUND ENCLOSURES. SEE CROSS

CONNECTION MANUAL FOR ENCLOSURE FREEZE PROTECTION AND CERTIFICATION REQUIREMENTS.

4. RESIDENTIAL LAWN IRRIGATION R.P. ASSEMBLIES THAT ARE REMOVED TO PREVENT FREEZING IN THE WINTER MONTHS MUST BE CAPPED OFF. ALL ABOVE GROUND ASSEMBLIES, EXCEPT RESIDENTIAL LAWN IRRIGATION ASSEMBLIES, MUST BE PROTECTED FROM FROST. 6. FOR ENCLOSURE DIMENSIONS SEE DETAIL W-34.

7. STEEL RODS AND BOLTS SHALL BE 3/4" HOT DIPPED GALVANIZED. 8. ALL ASSEMBLIES MUST BE ON THE CURRENT APPROVAL LIST.

	CITY OF RALEIGH					
	DEPARTMENT OF PUBLIC UTILITIES					
	TYPICAL REDUCED PRESSURE ZONE BACKFLOW PREVENTER ASSEMBLY					
DWG. NO.	REVISIONS	DATE	REVISIONS	DATE		
W-36	Y.C.A.	12-31-91	A.B.B.	7-10-04		
W-36	D.W.C.	11-8-99	D.H.L.	6/18/08		




Know what's below.

Call before you dig. nc811.org or 1-800-632-4949

PROJECT NO.	OUT-1502
FILENAME:	OUT1502-DTL3a
DRAWN BY:	STH
SCALE:	N.T.S.
DATE:	06-24-2025
SHEET NO.	C-8

200



ROUND OPTION PLAN VIEW

CAST-IN-PLACE MANHOLE CAP DETAIL

NOT TO SCALE

PROVIDE ADDITIONAL REINFORCING AROUND OPENINGS EQUAL TO THE BARS INTERRUPTED, HALF EACH SIDE. ADDITIONAL BARS TO BE IN THE SAME PLANE.

PROTECTION SLAB AND ALL MATERIALS TO BE PROVIDED AND INSTALLED BY CONTRACTOR.

DETAIL DESIGN BY DELTA ENGINEERS, ARCHITECTS AND LAND SURVEYORS, ENDWELL, NY.

The Stormwater Management StormFilter


48"Ø UNDERGROUND DETENTION SYSTEM - 761691-15

2. DESIGN LOAD HS25.


3. EARTH COVER = 1' MAX.


4. CONCRETE STRENGTH = 4,000 psi


5. REINFORCING STEEL = ASTM A615, GRADE 60.




48"Ø UNDERGROUND DETENTION SYSTEM - 761691-15









These results are submitted to you as a guideline only, without liability on the part of CONTECH Construction Products Inc. for accuracy or suitability to any particular application, and are subject to your verification.

		La Company	w.			
37	37	10.39	1.21	3.36	10373	333.23
38	38	10.67	1.22	3.25	10648	333.32
39	39	10.94	1.22	3.12	10913	333.40
40	40	11.19	1.22	2.98	11167	333.48
41	41	11.43	1.21	2.82	11409	333.57
42	42	11.66	1.21	2.65	11636	333.65
43	43	11.87	1.19	2.44	11848	333.73
44	44	12.07	1.18	2.21	12042	333.82
45	45	12.24	1.16	1.94	12215	333.90
46	46	12.39	1.13	1.60	12362	333.98
47	47	12.50	1.10	1.14	12478	334.07
48	48	12.57	1.00	0.00	12541	334.15





During the worst-case scenario, there is 5.85 feet of head available on the orifice.

Flow Rate per Cartridge:		
Flow, Q (cfs)	0.0127	$O = cA\sqrt{2Gh}$
Flow, Q (gpm)	5.69	

0.0011

0.017

CNTECH

Discharge flow rate from StormFilter:

Restrictor Disc Diameter (ft)

Restrictor Disk Calibration:

Area of Restrictor Disc (sf)

Number of cartridges

Cook Out - Zebulon Specific Data:

10 cartridges are suitable for this site.

Max. Head, h, on Cartridges (ft) 5.85

for all cartridge sizes

Orifice Coefficient

Head, h (ft)

Flow, Q (cfs) Flow, Q (gpm)

Restrictor Disc Diameter (in) 0.443

Zebulon, NC

Project Name: Contech No:

Input Calculated

Volume StormFilter Outflow & Orifice Calculation

Cook Out - Zebulon

761,691

With 5.85 of head available, each cartridge will discharge 5.69 gpm, or 0.0127 cfs. Since 5.69 gpm is less than the 1 GPM/sf flow rate of 7.5 GPM for the 18-inch cartridge, the mass loading calculations are preserved and

The Volume StormFilter restrictor disc is calibrated to flow at 7.5 gpm at 10 feet of head, or 1 gpm/sf or less

 $Q = cA\sqrt{2Gh}$

Q = 0.017cfs = 7.5GPM

0.0127	
0.127	(Q = No. Cartridges x Flow per Cartridge)


With 10 cartridges, the total StormFilter discharge outflow rate is 0.127 cfs during the worst-case scenario.

Equivalent Orifice Diameter:


The following equations back-calculate from the total worst-case StormFilter flow rate and head to determine an equivalent orifice diameter that can be used to represent the StormFilter when designed on a volume/mass basis.

Total Outflow (cfs)	0.127	$Q = cA\sqrt{2Gh}$
Orifice Coefficent	0.61	g - c.1 v 2 c/n
Max. Head on cartridges (ft)	5.85	$Q = (0.61) \left(\frac{D^2}{10.000} \pi \right) \sqrt{2(32)}$
Equivalent Diameter, D (ft)	0.117	$Q = (0.01) \left(\frac{\pi}{4} \right) \sqrt{2(32)}$
Equivalent Diamter, D (in)	1.402	
	350	40


This equivalent orifice, however, it not a physical orifice. It is simply a method for accounting for the flow through the Volume StormFilter in routing calculations when required.







Sambatek.com www.sambatek.com



- 6" CMP OUTLET TO STORMFILTER

INV. = 330.10' (TOP OF CARTRIDGES)

- OUTLET CONTROL STRUCTURE

(SEE DETAIL 1)

ACCESS RISER

(8) 123 LF 48" CMP @ 0.25% WITH MANIFOLD

DETENTION STRUCTURE

(SEE CONTECH DETAILS)

STORMFILTER

WATER QUALITY DEVICE -

STORMFILTER -CARTRIDGE (typ.)

UNDERGROUND DETENTION AND TREATMENT SYSTEM SECTION VIEW

12" CMP OUTLET TO OCS — INV = 328.30 18" LOW DROP

STRUCTURE

ACCESS RISER


STRUCTURE


▼ 100 YEAR ELEV. = 334.07


▼ 10 YEAR ELEV. = 333.21


▼ 1 YEAR ELEV. = 331.87 ▼ WQv, ELEV. = 331.23

-INV = 330.30'









PROJECT NO. OUT-1502

FILENAME: OUT1502-DTL4a

DRAWN BY: STH

SCALE: N.T.S.

DATE: 06-24-2025

SHEET NO.

SITE PLAN GENERAL NOTES

- 1. THE INFORMATION SHOWN HEREIN WAS TAKEN FROM A TOPOGRAPHIC SURVEY PREPARED BY: COMMERCIAL SITE DESIGN 8312 CREEDMOOR ROAD RALEIGH, NORTH CAROLINA PHONE 919-848-6121; FAX 919-848-3745
- 2. THE LOCATIONS OF ALL UTILITIES SHOWN ON THESE PLANS ARE BASED ON THE AVAILABLE INFORMATION. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UTILITIES WITH THE UTILITY OWNERS PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- 3. ALL HANDICAP SITE FEATURES SHALL BE CONSTRUCTED TO MEET ALL FEDERAL, STATE AND LOCAL CODES.
- 4. ANY DISCREPANCY IN THIS PLAN AND ACTUAL FIELD CONDITIONS SHALL BE REPORTED TO THE OWNER PRIOR TO START OF CONSTRUCTION. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF ALL SETBACKS, EASEMENTS, AND DIMENSIONS SHOWN HEREON BEFORE BEGINNING CONSTRUCTION.
- 5. PRIOR TO STARTING CONSTRUCTION, THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OR FABRICATION OF ANY ITEM SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED ALL PLANS AND ANY OTHER DOCUMENTATION FROM ALL OF THE PERMITTING AND ANY OTHER REGULATORY AUTHORITIES. FAILURE OF THE CONTRACTOR TO FOLLOW THIS PROCEDURE SHALL CAUSE THE CONTRACTOR TO ASSUME FULL RESPONSIBILITY FOR ANY SUBSEQUENT MODIFICATION OF THE WORK MANDATED BY ANY REGULATORY AUTHORITY. ALL CONSTRUCTION TO BE IN ACCORDANCE WITH PERMITS ISSUED AND APPLICABLE STATE, COUNTY AND LOCAL CODES.
- 6. THE GENERAL CONTRACTOR SHALL CONTACT ALL OWNERS OF EASEMENTS, UTILITIES AND RIGHT-OF-WAYS, PUBLIC OR PRIVATE, PRIOR TO WORKING IN THESE AREAS.
- 7. CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY, AND ADJOINING PROPERTY PROTECTED FROM DAMAGE.
- 8. ACCESS TO UTILITIES, FIRE HYDRANTS, STREET LIGHTING, ETC., SHALL REMAIN UNDISTURBED, UNLESS COORDINATED WITH RESPECTIVE UTILITY.
- 9. CONTRACTOR IS RESPONSIBLE FOR DAMAGE TO ANY EXISTING ITEM AND/OR MATERIAL INSIDE OR OUTSIDE CONTRACT LIMITS DUE TO CONSTRUCTION OPERATIONS.
- 10. ALL DIMENSIONS ARE TO THE FACE OF CURB, UNLESS OTHERWISE NOTED.
- 11. DO NOT SCALE THIS DRAWING AS IT IS A REPRODUCTION AND SUBJECT TO DISTORTION.
- 12. THE GENERAL CONTRACTOR SHALL REMOVE ALL TRASH AND DEBRIS FROM THE SITE UPON COMPLETION OF THE PROJECT AND AT LEAST ONCE A WEEK DURING CONSTRUCTION.
- 13. THE GENERAL CONTRACTOR SHALL KEEP THE AREA OUTSIDE THE "CONSTRUCTION LIMITS" BROOM CLEAN AT ALL TIMES.
- 14. GENERAL CONTRACTOR WILL ERECT AND ILLUMINATE A SITE IDENTIFICATION SIGN, PER OWNER'S SPECIFICATION. COORDINATE LOCATION WITH OWNER'S REPRESENTATIVE
- 15. FINISH CURB AND WALK ELEVATIONS SHALL BE 6" ABOVE FINISH PAVEMENT GRADE UNLESS NOTED DIFFERENT ON PLAN.
- 16. CONTRACTOR SHALL ENSURE THAT ADEQUATE SITE LIGHTING IS PROVIDED PER OWNER'S SPECIFICATIONS.
- 17. ALL RADII DIMENSIONS ARE TO FACE OF CURB.
- 18. ALL UTILITIES TO SERVICE BUILDING SHALL BE UNDERGROUND ON SITE, UNLESS OTHERWISE INDICATED.
- 19. ALL STREET SURFACES, DRIVEWAYS, CULVERTS, CURB AND GUTTERS, ROADSIDE DRAINAGE DITCHES AND OTHER STRUCTURES THAT ARE DISTURBED OR DAMAGED IN ANY MANNER AS A RESULT OF CONSTRUCTION SHALL BE REPLACED OR REPAIRED IN ACCORDANCE WITH THE SPECIFICATIONS.
- 20. ALL DISTURBED AREAS SHALL HAVE TEMPORARY SEEDING AND MULCHING. ALL AREAS THAT ARE PLANNED TO BE BARE FOR MORE THAN 45 DAYS SHALL BE SEEDED AND MULCHED WITHIN SEVEN (7) DAYS.
- 21. THE CONTRACTOR SHALL VERIFY LOCATION AND ELEVATION OF ALL UNDERGROUND UTILITIES. THE LOCATION OF ALL EXISTING UTILITIES ARE NOT NECESSARILY SHOWN ON THE PLANS AND WHERE SHOWN ARE ONLY APPROXIMATE. THE CONTRACTOR SHALL ON HIS INITIATIVE AND AT NO EXTRA COSTS HAVE LOCATED ALL UNDERGROUND LINES AND STRUCTURES AS NECESSARY. NO CLAIMS FOR DAMAGES OR EXTRA COMPENSATION SHALL ACCRUE TO THE CONTRACTOR FROM THE PRESENCE OF SUCH PIPE, OTHER OBSTRUCTIONS OR FROM ANY DELAY DUE TO REMOVAL OR REARRANGEMENT OF THE SAME. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO UNDERGROUND STRUCTURES. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING ALL NON-SUBSCRIBING UTILITIES. THE CONTRACTOR(S) SHALL CONTACT NORTH CAROLINA "ONE CALL" AT 800-632-4949 FOR ASSISTANCE IN LOCATING EXISTING UTILITIES. CALL AT LEAST 48 HOURS PRIOR TO ANY DIGGING.

- 22. ALL LOT STRIPING AND DIRECTIONAL ARROWS TO BE WHITE REFLECTIVE MARKINGS AND SHALL CONFORM TO LOCAL REGULATIONS.
- 23. COMPACTION AND MAINTENANCE OF PROPER MOISTURE CONTENT OF THE SOIL UNDER BUILDINGS AND PAVED AREAS SHALL BE ACCOMPLISHED TO ACHIEVE 98% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY OR AS RECOMMENDED IN THE SOIL REPORT.
- 24. THE CONTRACTOR SHALL MAINTAIN AN "AS-BUILT" SET OF DRAWINGS TO RECORD THE EXACT LOCATION OF ALL PIPING PRIOR TO CONCEALMENT. DRAWINGS SHALL BE GIVEN TO THE OWNER UPON COMPLETION OF THE PROJECT WITH A COPY OF THE TRANSMITTAL LETTER TO THE ENGINEER.
- 25. BEFORE COMMENCEMENT OF WORK, THE CONTRACTOR SHALL REVIEW ALL PLANS AND SPECIFICATIONS AND THE JOB SITE. THE CONTRACTOR SHALL NOTIFY THE OWNER AND THE ENGINEER WHO PREPARED THE PLANS OF ANY DISCREPANCIES THAT MAY REQUIRE MODIFICATIONS TO THESE PLANS OR OF ANY FIELD CONFLICTS.
- 26. ALL PERMITS RELATIVE TO THE PROJECT MUST BE OBTAINED, PRIOR TO CONSTRUCTION. ALL CONSTRUCTION TO BE IN ACCORDANCE WITH PERMITS ISSUED AND APPLICABLE STATE, COUNTY AND LOCAL CODES.
- 27. THE CONTRACTOR SHALL REFER TO THE ARCHITECTURAL DRAWINGS FOR ALL BUILDING DIMENSIONS.
- 28. ALL PARKING LOT DIMENSIONS ARE TO FACE OF CURB UNLESS OTHERWISE NOTED.
- 29. CONTRACTOR SHALL COORDINATE EXACT SIZE OF HVAC CONCRETE PADS WITH MECHANICAL CONTRACTOR. REFER TO MECHANICAL PLANS FOR DETAILS.
- 30. ALL SEEDING, TEMPORARY AND PERMANENT, TO BE INSTALLED TO LOCAL REGULATIONS AND STANDARD PRACTICES.
- 31. ALL ROAD WORK SHALL BE PERFORMED IN ACCORDANCE WITH "THE CURRENT EDITION OF THE STATE DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIALS SPECIFICATIONS".
- 32. ANY AND ALL QUANTITIES SHOWN OR IMPLIED ON THESE PLANS ARE FOR ESTIMATION PURPOSES ONLY.
- 33. IT IS THE GENERAL CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH THE IRRIGATION CONTRACTOR, FOR IRRIGATION SLEEVE SIZE FOR IRRIGATION SYSTEM.
- 34. CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY. THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY, AND HOLD THE OWNER AND DESIGN PROFESSIONAL HARMLESS OF ANY AND ALL LIABILITY, REAL OR ALLEGED IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, ACCEPTING LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR DESIGN PROFESSIONAL.

UTILITY PLAN GENERAL NOTES

- 1. UTILITY INFORMATION SHOWN HEREON WAS OBTAINED FROM THE BEST AVAILABLE SOURCE AND MAY OR MAY NOT BE EITHER ACCURATE OR COMPLETE. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR VERIFYING EXACT LOCATIONS OF EXISTING UTILITIES AND IS RESPONSIBLE FOR ANY DAMAGE TO ANY UTILITIES, EITHER PUBLIC OR PRIVATE, SHOWN HEREON OR NOT SHOWN HEREON. ANY REPAIRS SHALL BE DONE TO THE SATISFACTION OF THE APPROPRIATE UTILITY COMPANY.
- 2. THE GENERAL CONTRACTOR SHALL CONFIRM ALL NEW UTILITY TAP LOCATIONS WITH THE UTILITY OWNERS. ALL FEES SHALL BE THE RESPONSIBILITY OF DEVELOPER.
- 3. IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO VERIFY THE ACTUAL LOCATION AND AVAILABILITY OF ALL EXISTING AND PROPOSED UTILITIES IN THE FIELD PRIOR TO GROUND BREAKING.
- 4. NEW LOT LIGHT FOUNDATION BASES, CONDUIT AND WIRING ARE BY THE GENERAL CONTRACTOR. POLES, FIXTURES, ANCHOR BOLTS & HARDWARE SHALL BE COORDINATED WITH THE OWNER AND INSTALLED BY THE ELECTRICAL CONTRACTOR.
- 5. ALL NEW LOT LIGHTS AND THE MAIN IDENTIFICATION SIGN SHALL HAVE A MINIMUM 10 FEET CLEARANCE FROM ALL OVERHEAD UTILITIES.
- 6. GENERAL CONTRACTOR IS RESPONSIBLE FOR PERMITS AND/OR APPROVALS NECESSARY FOR ANY WORK IN ROADWAY OR RIGHT-OF-WAY.
- 7. ALL TRENCH EXCAVATION AND BACKFILL SHALL BE IN ACCORDANCE WITH


TRENCH BACKFILL DETAIL SHOWN ON THESE PLANS.

- 8. MINIMUM COVER FOR CONDUITS SHALL BE 36" UNLESS OTHERWISE SHOWN OR NOTED ON THESE PLANS. 9. ALL MANHOLES, VALVES, AND MONUMENT FRAMES SHALL BE SET TO FINISH
- GRADE AFTER PAVING. 10. THE CONTRACTOR SHALL COMPLY WITH THE RULES AND REGULATIONS OF THE STATE CONSTRUCTION SAFETY ORDERS. TRENCHES SHALL BE SHORED
- IN ACCORDANCE WITH OSHA. 11. THE MINIMUM SLOPE FOR SANITARY SEWER LINES SHALL BE AS FOLLOWS: 1) 1/4"/FT FOR 4" LINES AND 2) 1/8"/FT FOR 6" LINES. CLEANOUTS SHALL BE PLACED AT 75' INTERVALS.
- 12. ALL WATER LINES SHALL HAVE A FINAL COVER DEPTH OF 3'-0" IN NON-TRAFFIC AREAS AND 4'-0" MINIMUM IN TRAFFIC AREAS UNLESS SPECIFICALLY NOTED OTHERWISE.
- 13. ALL SEWER LINES SHALL HAVE A FINAL COVER DEPTH 4'-0" IN NON-TRAFFIC AREAS AND 5'-0" MINIMUM IN TRAFFIC AREAS UNLESS SPECIFICALLY NOTED OTHERWISE ON THE PLANS.
- 14. SANITARY SEWER SERVICES SHALL BE PVC SDR 35 TO R/W, THEN PVC SCH. 40 TO BUILDING. WATER SERVICE SHALL BE TYPE "K" COPPER.
- 15. CABLE TV SERVICE ROUTING IS NOT PART OF THIS PLAN, CONTRACTOR TO COORDINATE WITH CABLE COMPANY.
- 16. EXISTING MANHOLES SHOULD BE FIELD VERIFIED FOR RIMS AND INVERTS. 17. ALL WORK SHALL BE GOVERNED BY THE LATEST EDITIONS OF THE STATE
- MECHANICAL, PLUMBING, ELECTRICAL, FIRE PROTECTION, BUILDING CODE, ENERGY CONSERVATION, HANDICAP ACCESSIBILITY, NATIONAL ELECTRICAL CODES AND NATIONAL FIRE PROTECTION ASSOCIATION CODES AND AS ADOPTED BY THE AUTHORITIES HAVING JURISDICTION.
- 18. THE CONTRACTOR SHALL OBTAIN AND PAY FOR ALL INSPECTIONS. CERTIFICATIONS, EQUIPMENT, ETC., THAT MAY BE REQUIRED.
- 19. THE ENGINEER AND/OR OWNER DISCLAIM ANY ROLE IN THE CONSTRUCTION MEANS/METHODS ASSOCIATED WITH THE PROJECT AS SET FORTH IN THESE PLANS.
- 20. OCCUPATIONAL HEALTH AND SAFETY ADMINISTRATION (OSHA) STANDARDS FOR EXCAVATIONS; FINAL RULE 29CFR PART 1926, SUBPART "P" APPLIES TO ALL EXCAVATIONS EXCEEDING 5 FEET IN DEPTH.
- 21. EXCAVATION EXCEEDING TWENTY (20) FEET IN DEPTH REQUIRES THE DESIGN OF A TRENCH SAFETY SYSTEM BY A REGISTERED PROFESSIONAL ENGINEER.
- 22. EQUIPMENT AND PRODUCTS OTHER THAN THOSE SPECIFIED MAY BE USED PROVIDED PRIOR APPROVAL HAS BEEN OBTAINED FROM THE OWNER IN WRITING PRIOR TO ORDERING OR INSTALLATION. THE CONTRACTOR SHALL WAIVE ANY CLAIM FOR ADDITIONAL COST RELATED TO THE SUBSTITUTION OF ALTERNATE EQUIPMENT.
- 23. CONTRACTOR SHALL MAINTAIN AN "AS-BUILT" SET OF DRAWINGS TO RECORD THE EXACT LOCATION OF ALL PIPING PRIOR TO CONCEALMENT. DRAWINGS SHALL BE GIVEN TO THE OWNER UPON COMPLETION OF THE PROJECT WITH A COPY OF THE TRANSMITTAL LETTER TO THE ENGINEER.
- 24. ONLY SEWAGE NOT CONTAINING GREASE IS ALLOWED TO BYPASS THE
- 25. ALL SANITARY SEWER SERVICES AND STORM DRAIN PIPING 8" IN DIAMETER OR SMALLER SHALL BE SCH. 40 PVC WITH ADHESIVE "WELDED JOINTS, UNLESS SPECIFIED OTHERWISE OR REQUIRED BY LOCAL GOVERNING MUNICIPALITY, MINIMUM SLOPES ON SANITARY SEWER SERVICES: 4" - 1/4"/FT.
- 26. BELOW GRADE WATER SERVICE PIPING SHALL BE TYPE "K" HARD DRAWN COPPER TUBING WITH SILVER SOLDER JOINTS. SOLDERS CONTAINING LEAD SHALL NOT BE USED FOR ANY PURPOSE ON THIS PROJECT, WHERE PIPING IS REQUIRED TO RUN BELOW BUILDING SLAB, IT SHALL BE INSTALLED WITHOUT JOINTS BELOW SLAB.
- 27. WATER PIPING SHALL BE CONNECTED TO BUILDING STUBS, VERIFY LOCATIONS PRIOR TO BEGINNING WATER PIPE INSTALLATION.
- 28. WASTE PIPING SHALL BE CONNECTED TO BUILDING STUBS, VERIFY LOCATIONS AND INVERTS PRIOR TO BEGINNING ANY WASTE PIPE INSTALLATION.
- 29. CONTRACTOR SHALL NOTIFY THE LOCAL LOCATE SERVICE BY CALLING 811 AT LEAST 12 FULL WORKING DAYS PRIOR TO BEGINNING CONSTRUCTION OR EXCAVATION TO HAVE UTILITIES LOCATED. CONTRACTOR SHALL CONTACT ANY LOCAL UTILITIES THAT PROVIDE THEIR OWN LOCATOR SERVICES INDEPENDENTLY.
- 30. ALL UTILITY CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE TOWN OF ____ PUBLIC UTILITIES AND CROSS CONNECTION CONTROL REGULATIONS AND STANDARDS.
- 31. SITE UTILITY CONTRACTOR TO PROVIDE WATER, SANITARY SEWER, AND ROOF DRAIN LEADERS TO WITHIN 5 FEET OF THE BUILDING. CONTRACTOR SHALL COORDINATE SITE PLAN CONNECTIONS WITH THE ARCHITECTURAL BUILDING PLANS.
- 32. SITE UTILITY CONTRACTOR TO PROVIDE WATER, SANITARY SEWER, AND ROOF DRAIN LEADERS TO WITHIN 5 FEET OF THE BUILDING. CONTRACTOR SHALL COORDINATE SITE PLAN CONNECTIONS WITH THE ARCHITECTURAL
- 33. SANITARY CLEANOUTS SHALL BE PLACED NO MORE THAN 75 FEET APART. CLEAN OUTS LOCATED IN PAVEMENT AREAS SHALL HAVE HEAVY DUTY TRAFFIC RATED CONSTRUCTION.
- 34. CONNECTION OF SANITARY SEWER SERVICE TO AN EXISTING MANHOLE SHALL COMPLY WITH THE TOWN OF _____ STANDARDS, INCLUDING: CORE DRILL FOR OPENING INTO MANHOLE AND INSTALL WITH FLEXIBLE BOOT. IF PAVEMENT CUT IS REQUIRED, CONTRACTOR SHALL PATCH PAVEMENT WITH A SECTION TO MATCH EXISTING PAVEMENT: 3" I-2, 8" ABC OR BETTER.

- 35. RELATION OF WATER MAINS TO SEWERS:
 - A. LATERAL SEPARATION OF SEWER AND WATER MAINS: WATER MAINS SHALL BE LAID AT LEAST 10 FEET LATERALLY FROM EXISTING OR PROPOSED SEWERS UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT A 10 FOOT LATERAL SEPARATION, IN WHICH CASE: 1). THE WATER MAIN IS LAID IN A SEPARATE TRENCH, WITH THE ELEVATION OF THE BOTTOM OF THE WATER MAIN AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER, OR 2). THE WATER MAIN IS LAID IN THE SAME TRENCH AS THE SEWER LINE WITH THE WATER MAIN LOCATED AT ONE SIDE ON A BENCH OF UNDISTURBED EARTH, AND ABOVE THE TOP OF THE SEWER.
- B. CROSSING A WATER MAIN OVER A SEWER MAIN: WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS OVER A SEWER THE WATER MAIN SHALL BE LAID AT SUCH AN ELEVATION THAT THE BOTTOM OF THE WATER MAIN IS AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER MAIN, UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT AN 18 INCH VERTICAL SEPARATION - IN WHICH CASE BOTH THE WATER MAIN AND SEWER MAIN SHALL BE CONSTRUCTED OF FERROUS MATERIALS AND WITH JOINTS THAT ARE EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING.
- C. CROSSING A WATER MAIN UNDER A SEWER MAIN: WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS UNDER A SEWER MAIN BOTH THE WATER MAIN AND SEWER MAIN SHALL BE CONSTRUCTED OF FERROUS MATERIALS AND WITH JOINTS EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING.
- D. CROSSING A SEWER LINE OVER OR UNDER A STORM DRAIN: WHENEVER IT IS NECESSARY FOR A SEWER LINE TO CROSS A STORM DRAIN PIPE, THE SEWER LINES SHALL BE LAID AT SUCH AN ELEVATION THAT THE OUTSIDE OF THE SEWER LINE NEAREST TO THE OUTSIDE OF THE STORM DRAIN PIPE SHALL MAINTAIN A 12 INCH CLEAR SEPARATION DISTANCES, OR ENCASED IN EITHER CONCRETE OR DUCTILE IRON PIPE FOR AT LEAST 5 FEET ON EITHER SIDE OF THE CROSSING.
- 36. UNDERGROUND CONDUITS TO SIGNS, LOT LIGHTS, ETC., SHALL BE PLACED IN GRASS OR LANDSCAPE AREAS WHENEVER POSSIBLE. THE LOCATION OF THE CONDUIT AS SHOWN ON THESE PLANS SHALL BE CONSIDERED TO BE SCHEMATIC WITH ACTUAL LOCATION TO BE VERIFIED BY THE GENERAL CONTRACTOR, PVC SCH. 40 SLEEVES SHALL BE INSTALLED FOR ALL CONDUIT CROSSING UNDER PAVED AREAS.
- 37. SEE ELECTRICAL SHEETS FOR SIZE OF CONDUIT AND WIRE ON ALL ELECTRICAL SERVICES.
- TRANSFORMER BY ELECTRIC COMPANY, GENERAL CONTRACTOR TO PROVIDE PAD. REFER TO ELECTRIC COMPANY SPECIFICATIONS FOR PAD CONSTRUCTION.
- 38. TRANSFORMER BY ELECTRIC COMPANY, GENERAL CONTRACTOR TO PROVIDE PAD, REFER TO ELECTRIC COMPANY SPECIFICATIONS FOR PAD CONSTRUCTION.

DRAINAGE STRUCTURE NOTES

- 1. BOXES SHALL COMPLY WITH LOCAL JURISDICTIONAL STANDARDS AND SPECIFICATIONS.
- 2. ANY NONSTANDARD BOX IS TO BE DESIGNED BY A PROFESSIONAL ENGINEER.
- 3. THE MAXIMUM HEIGHT OF AN UN-REINFORCED MASONRY DRAINAGE STRUCTURE WITH 8" WALLS SHALL BE LIMITED TO 8'-0" FROM INVERT OF THE OUTLET PIPE TO THE TOP OF THE CASTING. DEPTHS GREATER THAN 8'-0" SHALL HAVE WALLS 12" THICK. BASINS OVER 12' IN TOTAL DEPTH SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER. FOUR INCH WALLS ARE NOT ALLOWED ON DRAINAGE STRUCTURES. BOTTOM SLAB ON STRUCTURES SHALL BE REINFORCED WHEN BOX DEPTHS EXCEEDS 8 FT.
- 4. STEPS ARE TO BE PROVIDED ON ALL BASINS DEEPER THAN 42".
- 5. STEPS ARE TO BE PS1-PF AS MANUFACTURED BY M.A. INDUSTRIES OR AN APPROVED EQUAL. LOCATE ON NON-PIPE WALLS.
- 6. MORTAR IN MASONRY BOXES IS TO BE TYPE M.
- 7. CLAY BRICK STRUCTURES ARE NOT ALLOWED.
- 8. CONCRETE PIPE IS TO BE MINIMUM CLASS III.
- 9. CONCRETE BUILDING BRICK IS TO MEET ASTM C-55, GRADE N, TYPE 1.
- 10. BASINS LOCATED IN WET AREAS, OR AS OTHERWISE REQUIRED BY THE TOWN ENGINEER, SHALL HAVE WEEP HOLES AS SHOWN ON DETAILS.
- 11. ALL CAST-IN-PLACE PRECAST CONCRETE DRAINAGE STRUCTURES LOCATED IN PAVED AREAS ACCESSIBLE TO TRUCK LOADINGS TO BE DESIGNED TO MEET AASHTO HS 20-44 LOADING. SEE MANUFACTURERS DETAILS FOR WALL, TOP AND BOTTOM THICKNESS.






OUT-1502


STH


N.T.S.

06-24-2025

OUT1502-DTL C-10







3. WHEN THE PROJECT HAS BEEN COMPLETED FOR A PERIOD OF ONE YEAR, UPON WRITTEN REQUEST BY THE ENCROACHER/CONTACTOR TO THE DIRECTOR OF PUBLIC WORKS OR CONSTRUCTION INSPECTOR, A FINAL INSPECTION AND REVIEW WILL BE CONDUCTED BY TOWN OF ZEBULON PUBLIC WORKS


4. ANY PERSONNEL OR EQUIPMENT WORKING WITHIN FIVE FEET OF A TRAVEL LANE SHALL REQUIRE A FULL LANE CLOSURE. NO ROADWAY OF TRAFFIC SHALL BE CLOSED OR RESTRICTED BETWEEN THE HOURS OF 6:00 AM TO 8:30 AM AND 4:00 PM TO 6:00 PM MONDAY THROUGH FRIDAY. TRAFFIC SHALL BE MAINTAINED AT ALL TIMES.

5. ALL MATERIALS AND CONSTRUCTION ON DOGWOOD LANE AND JONES STREET SHALL BE IN ACCORDANCE TOWN OF ZEBULON STANDARDS AND SPECIFICATIONS.

6. ANY EXISTING DRIVEWAYS, PAVEMENT, SIDEWALK, CURB AND GUTTER OR DRAINAGE STRUCTURES THAT ARE DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED TO THEIR ORIGINAL CONDITION.


7. CONTRACTOR SHALL NOT PLACE EXCAVATED MATERIAL ON THE ROADWAY AT ANY TIME.

8. TOWN OF ZEBULON RESERVES THE RIGHT TO REVISE, RESTRICT, SUSPEND AND/OR VOID RIGHT TO COMPLETE WORK ON TOWN ROW IF THE EXECUTION AND/OR OPERATION OF SAID PERMIT IS FOUND TO BE A HAZARD TO THE TRAVELING PUBLIC.














OUT-1502 OUT1502-DTL6 STH N.T.S.


06-24-2025



RIPRAP APRON







PERMANENT SEEDING IN NORTH CAROLINA (TABLE 6.11s)

33 BU/ACRE (SPRIGS)

TREE PIT DEPTH AND WIDTH.

PRUNE TO GROWERS SPECIFICATIONS.

TREE PLANTING DETAIL

2. ALL TREES SHALL COMPLY WITH THE AMERICAN

STANDARDS FOR NURSERY STOCK - INCLUDING

SEEDING MIXTURE

RATE (lb/acre) SPECIES CENTIPEDE GRASS 10-20 LB/ACRE (SEED) OR

SEEDING DATES: MAR. - JUNE

(SPRIGGING CAN BE DONE THROUGH JULY WHERE WATER IS AVAILABLE FOR IRRIGATION.)

SOIL AMENDMENTS
ALLP LIME AND FERTILIZER ACCORDING TO SOIL TESTS, OR APPLY 300 LB/ACRE 10-10-10.

SPRIGGING
PLANT SPRIGS IN FURROWS WITH A TRACTOR-DRAWN TRANSPLANTER

OR BROADCAST BY HAND. FURROWS SHOULD BE 4-6 INCHES DEEP AND 2 FT APART. PLACE SPRIGS ABOUT 2 FT

APART IN THE ROW WITH ONE END AT OR ABOVE GROUND LEVEL. BROADCAST AT RATES SHOWN ABOVE, AND PRESS SPRIGS INTO THE TOP 1/2 - 2

INCHES OF SOIL WITH A DISK SET STRAIGHT SO THAT SPRIGS ARE NOT BROUGHT BACK TOWARD THE SURFACE.

MULCH DO NOT MULCH.

FERTILIZE VERY SPARINGLY - 20 LB/ACRE NITROGEN IN SPRING WITH NO PHOSPHORUS. CENTIPEDEGRASS CANNOT TOLERATE HIGH PH OR EXCESS FERTILIZER.

ALL STREET TREES AND PARKING LOT TREES WILL REQUIRE THE USE OF STRUCTURED SOILS PER UDO SECTION 5.6.9.B.7.

TURF NOTES:

- 1. CHISEL COMPACTED AREAS AND SPREAD TOPSOIL 3 INCHES DEEP OVER ADVERSE SOIL CONDITIONS, IF AVAILABLE.
- 2. RIP ENTIRE AREA TO 6 INCHES IN DEPTH.
- 3. REMOVE ALL LOOSE ROCK, ROOTS, AND OTHER OBSTRUCTIONS LEAVING
- SURFACE REASONABLY SMOOTH AND UNIFORM. 4. APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPERPHOSPHATE
- UNIFORMLY AND MIX WITH SOIL (SEE BELOW*). 5. CONTINUE TILLAGE UNTIL A WELL-PULVERIZED, FIRM, REASONABLY
- UNIFORM SEEDBED IS PREPARED 4 TO 6 INCHES DEEP. 6. SEED ON A FRESHLY PREPARED SEEDBED AND COVER SEED LIGHTLY WITH SEEDING EQUIPMENT OR CULTIPACK AFTER SEEDING.
- MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH.
- . INSPECT ALL SEEDED AREAS AND MAKE NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND SHOULD BE OVER 60% DAMAGED, RE-ESTABLISH FOLLOWING ORIGINAL LIME, FERTILIZER AND SEEDING RATES.
- 9. CONSULT CONSERVATION INSPECTOR ON MAINTENANCE TREATMENT AND FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED.
- *APPLY: AGRICULTURAL LIMESTONE 2 TONS/ACRE (3 TONS/ACRE IN CLAY SOILS) FERTILIZER - 1,000 LBS/ACRE - 10-10-10 SUPERPHOSPHATE -500 LBS/ACRE 20% ANALYSIS MULCH - 2 TONS/ACRE - SMALL GRAIN STRAW ANCHOR - ASPHALT EMULSION @, 300 GALS/ACRE

FOLLOW PREPARATION AS DIRECTED FOR STEPS 1-5 ABOVE. IMMEDIATELY WATER SOD UPON INSTALLATION AND CONTINUE UNTIL ROOTS ARE

- 10. CONTRACTOR SHALL WATER AND MAINTAIN ALL LAWN AREAS UNTIL AN ACCEPTABLE STAND OF GRASS HAS BEEN ESTABLISHED.
- 11. ONCE AN ACCEPTABLE STAND OF GRASS HAS BEEN ESTABLISHED. THE CONTRACTOR SHALL REPAIR ALL DAMAGED AREAS AND MONITOR THE LAWN AREAS UNTIL THE GRASS REACHES A HEIGHT OF 4 INCHES TALL.
- 12. AT THE TIME THE GRASS REACHES A HEIGHT OF 4 INCHES TALL, THE CONTRACTOR SHALL MOW THE GRASS TO THE HEIGHT OF 3 INCHES AND TURN OVER THE LAWN MAINTENANCE TO THE OWNER.
- 13. AN ACCEPTABLE STAND OF GRASS SHALL BE 92% COVERAGE OR BETTER.

LANDSCAPE NOTES:

ESTABLISHED.

- . THE GENERAL CONTRACTOR SHALL LEAVE THIS SITE AT FINISHED GRADE. THE LANDSCAPE CONTRACTOR SHALL REVISE GRADES AT A MINIMUM TO ENSURE SMOOTH TRANSITIONS BETWEEN PLANTING BEDS AND LAWN AREAS.
- PLANT GUARANTEE: ALL PLANTS SHALL BE GUARANTEED TO LIVE FOR TWELVE MONTHS. THE GUARANTEE SHALL COMMENCE UPON FINAL ACCEPTANCE OF THE PROJECT. IF ANY PLANTS ARE DEAD OR IN AN UNHEALTHY CONDITION BEFORE FINAL ACCEPTANCE, THE LANDSCAPE CONTRACTOR SHALL REPLACE THEM AT HIS EXPENSE. THIS REPLACEMENT SHALL NOT BE CONSIDERED A GUARANTEED
- ALL PLANTING SHALL BE PLACED WITHIN A MULCHED PLANTING BED. ALL STRAPPING AND THE TOP 2/3 OF WIRE BASKETS MUST BE CUT AWAY AND REMOVED FROM ROOT BALLS PRIOR TO BACKFILLING PLANTING PIT. REMOVE TOP 1/3 OF BURLAP FROM ROOT BALL.
- 4. ALL LANDSCAPE WORK SHALL BE IN ACCORDANCE WITH CURRENT CITY STANDARD DETAILS AND SPECIFICATIONS.
- 5. ALL AREAS NOT MULCHED SHALL BE SEEDED OR SODDED IN ACCORDANCE WITH THE AREA SPECIFIED ON PLANS WITH "REBEL II" HYBRID TALL FESCUE OR EQUIVALENT AS PRESCRIBED IN THE SEEDING SCHEDULE AS SHOWN ON THIS
- 6. SITE LIGHTING SHALL NOT BE PLACED IN CONFLICT WITH PLANTED TREES.
- 7. TREE PROTECTION FENCING TO BE PROVIDED AROUND TREE PRESERVATION AREAS IN ACCORDANCE WITH CITY STANDARDS.
- 8. COORDINATE ALL WORK WITH SITE LAYOUT AND SITE GRADING, DRAINAGE &
- 9. VERIFY LOCATION OF UTILITIES BEFORE PLANTING.
- 10. MULCH ALL AREAS, THAT ARE NOT SEEDED OR SODDED, WITH SHREDDED
- HARDWOOD MULCH TO A DEPTH OF 3" 4".
- 11. THE SELECTION AND INSTALLATION OF PLANTS AND PLANTING METHODS SHALL CONFORM WITH THE STANDARDS OF THE AMERICAN ASSOCIATION OF NURSERYMEN OR THE CITY STANDARD DETAILS AND SPECIFICATIONS, WHICHEVER IS STRICTER.
- 12. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL QUANTITIES. DRAWINGS SHALL RULE OVER PLANT LISTS.
- 13. SUBSTITUTIONS SHALL BE SUBMITTED TO LANDSCAPE ARCHITECT FOR APPROVAL, PRIOR TO INSTALLATION, SUBSTITUTIONS MAY REQUIRE ADDITIONAL APPROVAL BY THE GOVERNING JURISDICTION.
- 14. ALL LANDSCAPING SOIL AND FILL SHALL BE FREE FROM WEEDS, REFUSE, AND DEBRIS AT ALL TIMES.
- 15. TREES AND LARGE SHRUBS SHALL BE ADEQUATELY SUPPORTED, AS NECESSARY, USING STAKES AND GUYS. SUCH SUPPORTS SHALL BE DESIGNED SO AS TO PROTECT TREES AND SHRUBS FROM INJURY. TREES AND SHRUBS SHALL BE FASTENED TO THE SUPPORT WITH AN ACCEPTABLE COMMERCIAL TREE TIE OF PLASTIC OR HOSE COVERED WIRE.
- 16. THE MAXIMUM GROWTH HEIGHT OF ANY LANDSCAPING WITHIN THE SIGHT TRIANGLE SHALL BE THREE (3) FEET IN HEIGHT.
- 17. PLANTING SOIL TO BE USED SHALL HAVE THE FOLLOWING CHARACTERISTICS: FERTILE, FRIABLE, NATURAL TOPSOIL OF LOAMY CHARACTER, WITHOUT ADMIXTURE OF SUBSOIL MATERIAL, OBTAINED FROM WELL-DRAINED ARABLE SITE, REASONABLY FREE FROM CLAY, LUMPS, COARSE SANDS, STONES 1 INCH AND LARGER, PLANTS, GRASS, WEEDS, ROOTS, STICKS, AND OTHER FOREIGN MATERIALS, TOPSOIL SHALL CONFORM TO ASTM D5268 WITH A PH RANGE OF 5.5 TO 7, AND A MIN. 4 PERCENT ORGANIC MATERIAL.

Seeding Specifications

NPDES Stormwater Discharge Permit for Construction Activities (NCGO1 - 4/1/19) NCDEQ/Division of Energy, Mineral and Land Resources

SECTION E: GF	ROUND STABII	LIZATION
Require	ed Ground Stat	oilization Timeframes
Site Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b) High Quality Water (HQW) Zones	7	None
(c) Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d) Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e) Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slopes
Note: After the permaner	nt cessation of constru	ction activities, any areas with temporary

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the

techniques in the table below:		
Temporary Stabilization	Permanent Stabilization	
-Temporary grass seed covered with straw or other mulches and tackifiers	-Permanent grass seed covered with straw or other mulches and tackifiers	
-Hydroseeding	-Geotextile fabrics such as permanent soil reinforcement matting	
-Rolled erosion control products with or without temporary grass seed	-Hydroseeding	
-Appropriately applied straw or other mulch	-Shrubs or other permanent plantings covered with mulch	
-Plastic sheeting	-Uniform and evenly distributed ground cover sufficient to restrain erosion	
	-Structural methods such as concrete, asphalt or retaining walls	
	-Rolled erosion control products with grass seed	

Seedbed Preparation:

- 1. Chisel compacted areas and spread topsoil three inches deep over adverse
- soil conditions, if available.
- 2. Rip the entire area to six inches deep. 3. Remove all loose rock, roots and other obstructions, leaving surface
- reasonably smooth and uniform.
- 4. Apply agricultural lime, fertilizer and superphosphate uniformly and mix with soil (see mixture below).
- 5. Continue tillage until a well-pulverized, firm, reasonably uniform seedbed is prepared four to six inches deep.
- 6. Seed on a freshly prepared seedbed and cover seed lightly with seeding equipment or cultipack after seeding.
- 7. Mulch immediately after seeding and anchor mulch.

8. Inspect all seeded areas and make necessary repairs or reseedings within the planting season, if possible. If stand should be more than 60% damaged, reestablish following the original lime, fertilizer and seeding rates.

9. Consult Wake County Soil & Water or NC State Cooperative Extension on maintenance treatment and fertilization after permanent cover is established.

Mixture

2 tons/acre (3 tons/acre in clay soils) Agricultural Limestone 1,000 lbs/acre - 10-10-10 Fertilizer 500 lbs/acre - 20% analysis Superphosphate 2 tons/acre – small grain straw

Asphalt emulsion at 400 gals/acre Anchor

Seeding Schedule

For Shoulders, Side Ditches, Slopes (Max 3:1):

Date	Туре	Planting Rate
Aug 15- Nov 1	Tall Fescue	300 lbs/acre
Nov 1– Mar 1	Tall Fescue & Abruzzi Rye	300 lbs/acre
Mar 1– Apr 15	Tall Fescue	300 lbs/acre
-	- Hulled Common Bermudagrass	25 lbs/acre

Jul 1- Tall Fescue AND Browntop 125 lbs/acre (Tall Fescue); 35

Ibs/acre (Browntop Millet); 30 lbs/acre

(Sorghum-Sudan Hybrids)

Aug 15 Millet or Sorghum-Sudan

For Shoulders, Side Ditches, Slopes (3:1 to 2:1):

Mullet or Sorghum-Sudan

Date	Туре	Planting Rate
Mar 1– Jun 1	Sericea Lespedeza (scarified) and use the following combinations:	50 lbs/acre (Sericea Lespedeza);
Mar 1– Apr 15	Add Tall Fescue	120 lbs/acre
Mar 1– Jun 30	Or add Weeping Love grass	10 lbs/acre

Mar 1— Or add Hulled Common 25 lbs/acre Jun 30 Bermudagrass 120 lbs/acre (Tall Fescue); 35 lbs/acre Tall Fescue AND Browntop (Browntop Mullet); 30 lbs/acre

Hvbrids*** (Sorghum-Sudan Hybrids) Sericea Lespedeza (unhulled 70 lbs/acre (Sericea Lespedeza); 120 unscarified) AND Tall lbs/acre (Tall Fescue)

25 lbs/acre AND Abruzzi Rye


Consult Wake County Soil & Water Conservation District or NC State Cooperative Extension for additional information concerning other alternatives for vegetation of denuded areas. The above vegetation rates are those that do well under local conditions; other seeding rate combinations are possible.


*** **TEMPORARY**: Reseed according to optimum season for desired permanent vegetation. Do not allow temporary cover to grow more than 12" in height before mowing; otherwise, fescue may be shaded out.






nc811.org or 1-800-632-4949










OUT-1502 OUT1502-LS2 06-24-2025









ALL STREET AND STORM CONSTRUCTION SHALL COMPLY WITH TOWN OF ZEBULON STANDARDS AND SPECIFICATIONS.

ALL WATER CONSTRUCTION SHALL COMPLY WITH CITY OF RALEIGH STANDARDS AND SPECIFICATIONS.

ALL SIDEWALKS SHALL BE ADA COMPLIANT.





KL	
DDH	
	Engineering Su

BY

REVISIONS

REVISED PER TOWN AND WAKE EC

TRC & WAKE COUNTY COMMENTS

DESCRIPTION

1 2023-06-08

2 | 2023-10-17

DATE

HORIZONTAL SCALE: 1" = 20' VERTICAL SCALE: 1" = 2'

Sanbatek
www.sambatek.com
Engineering | Surveying | Planning | Environmental

COOK OUT
1200 ARENDELL AVENUE
ZEBULON, NORTH CAROLINA

PLAN AND PROFILE - JONES STREET
STATION 0+00.00 THRU 2+45.08

CLIENT:		
COOK OUT 15 LAURA LANE, SUITE 300		
THOMASVILLE, N.C. 27360		
PHONE: (336) 215-7025		

FAX: (336) 474-1849

PROJECT NO.	OUT-1502
FILENAME:	OUT1502-PP1
DRAWN BY:	RCN
DESIGNED BY:	WBB
HORIZONTAL SCAL	.E: 1" = 20'
VERTICAL SCALE:	1" = 2'
DATE:	10-07-15


P-1

SHEET NO.



ZEBULON WAKE COUNTY

1200 NORTH ARENDELL AVE. ZEBULON, NC



1 FRAMING PLAN
A2.0 SCALE: 3/16" = 1'-0"

ISSUE DATE: 06-13-2025

SHEET TITLE OVERALL FLOOR PLAN

A2.0



EXTERIOR PERSPECTIVE

SIDE (STREET) ELEVATION

1,660 sq ft

758 sq ft

45.6%

1,902 sq ft

490 sq ft

25.7%

SCALE: 1/8" = 1'-0"

FIRST STORY SURFACE AREA:

FIRST STORY TRANSPARENCY:

PERCENTAGE OF TRANSPARENCY:

SECOND STORY SURFACE AREA:

SECOND STORY TRANSPARENCY:


SCALE: 1/8" = 1'-0"

PERCENTAGE OF TRANSPARENCY:

COMPLIES WITH MINIMUM 40% TRANSPARENCY

COMPLIES WITH MINIMUM 25% TRANSPARENCY

NOT TO SCALE





ZEBULON WAKE COUNTY

1200 NORTH ARENDELL AVE ZEBULON, NC

REVISIONS:

— PAINTED (WHITE)

(NOT NEON) STRIP


HARDIE TRIM WITH LED


_ SLOPED BRICK


UDO 5.3.9.C.iv

ALUMINUM

UDO 5.3.9.C.i OR ii







PERCENTAGE OF TRANSPARENCY:

SECOND STORY SURFACE AREA:

SECOND STORY TRANSPARENCY:

PERCENTAGE OF TRANSPARENCY:

COMPLIES WITH MINIMUM 40% TRANSPARENCY

COMPLIES WITH MINIMUM 25% TRANSPARENCY

EXTERIOR MATERIAL LEGEND

INTERIOR SPACE

INDICATES RIBBED METAL PANEL WITH CONCEALED

DROP PAINTED NEUTRAL BLACK TO IMITATE A DARK

INDICATES TRANSPARENT GLAZING WITH SHEATHING BACK


INDICATES TRANSPARENT GLAZING INTO INTERIOR SPACE


INDICATES WOOD ARCHITECTURAL PANEL; SEE FINISH

INDICATES BRICK VENEER; SEE FINISH SPECIFICATIONS

SPECIFICATIONS DELETED FROM SCOPE

FASTENERS; SEE FINISH SPECIFICATIONS





40.4%

522 sq ft

148 sq ft

28.3%



ISSUE DATE: 08-29-2025

SHEET TITLE **EXTERIOR ELEVATIONS**