

TOWN OF ZEBULON

ZEBULON NORTH CAROLINA

ZEBULON MAINTENANCE YARD EXPANSION

OWNER INFORMATION

TOWN OF ZEBULON
1003 N. ARENDELL AVE.
ZEBULON, NC 27597-2309

SITE INFORMATION

450 E. HORTON ST. ZEBULON, NC 27597
PIN: 2705558698

ZONING: HI - HEAVY INDUSTRIAL
EXISTING USE: PUBLIC WORKS

ACREAGE: 7.8 ACRES

BUILDING SETBACKS

FRONT - 25'
REAR - 25'
SIDE - 20'

PARKING

EXISTING: 23

IMPERVIOUS COVER (TOTAL)

EXISTING CONDITIONS: 93,356 SF, 27.5%
PROPOSED CONDITIONS: 137,577 SF, 40.5%
FUTURE: 32,788 SF, 9.7%

OPEN SPACE

REQUIRED: 3.12 ACRES (40%)
PROVIDED: 3.29 ACRES (42%)

FLOODPLAIN

FLOODPLAIN ZONE X, AREA OUTSIDE
THE 0.2% ANNUAL CHANCE FLOOD,
MAP #3720270500K, DATED JULY 19, 2022

WATERSHED

NEUSE, MOCCASIN CREEK, C, NSW


CURRENT LAND USE: IH

FUTURE LAND USE: IH



SHEET INDEX

C-0.01	COVER SHEET
C-0.02	GENERAL NOTES - LEGENDS
C-1.00	OVERALL EXISTING CONDITIONS PLAN
C-1.01	EXISTING CONDITIONS PLAN
C-1.02	DEMOLITION PLAN
C-2.00	SITE & LANDSCAPE PLAN
C-2.01	RIGHT-OF-WAY LAYOUT PLAN
C-2.02	SIGHT DISTANCE CALCULATIONS
C-3.00	GRADING & DRAINAGE PLAN
C-3.01	STORMWATER MANAGEMENT PLAN
C-3.02	SCM PLANTING PLAN
C-5.00	EROSION & SEDIMENT POLLUTION CONTROL PLAN-PH I
C-5.01	EROSION & SEDIMENT POLLUTION CONTROL PLAN-PH II
C-5.02	EROSION & SEDIMENT POLLUTION CONTROL PLAN-DETAIL
C-6.00	DETAILS
C-6.01	DETAILS
C-6.02	DETAILS
C-6.03	DETAILS



VICINITY MAP
NOT TO SCALE



PROJECT AREA MAP
NOT TO SCALE



120 North Boylan Avenue • Raleigh, NC 27603-1423
(919) 828-0531 • thewootencompany.com
License Number : F-0115
awadsworth@thewootencompany.com

REVISIONS



NORTH CAROLINA

TOWN OF ZEBULON

ZEBULON

ZEBULON MAINTENANCE YARD EXPANSION



ISSUED FOR:

PERMITTING

DATE: 1/26/2024

DESIGNED BY: AMW

DRAWN BY: THR

CHECKED BY: AMW

PROJECT NO.: 2922-S

C-0.01

GENERAL NOTES

- The Contractor Shall have a Complete Set of Contract Documents as well as All Permit Approvals and Easements on the Job Site at All Times.
- Construction and Material Specifications Shall Conform to The State of North Carolina and the Contract Documents.
- All Shop Drawings must be Reviewed and Approved by Engineer before any Equipment is Ordered.
- Contractor Shall make every Effort to Preserve Property Irons, Monuments, Other Permanent Points and Lines of Reference, and Construction Stakes. A Registered Land Surveyor, at the Contractor's Expense, Shall Replace Property Irons, Monuments, and Other Permanent Points of Reference Disturbed Reference by the Contractor.
- Coordinates are based on GNSS Observations Processed in Conjunction with the NC RTN. Horizontal Datum is North Carolina State Plane NAD 83 (2011) and the Vertical Datum is NAVD 88.
- Utilities (i.e., Power Poles, Light Poles, Telephone, and Cable Pedestals, etc.) Located within Project Limits to Remain unless shown Otherwise.
- All Individual Trees to Remain unless noted otherwise on Plan or as Directed by the Engineer and Approved by Owner.
- Land Disturbance for the Project is Greater than 1 (One) Acre. Erosion Control Plan Approval is Required. It is the Contractor's Responsibility to Comply with the Erosion Control Requirements, Devices, Maintenance, etc. as Indicated on the Plans.
- It is the Contractor's Responsibility to Accurately Locate both Horizontally and Vertically All Existing Utilities Prior to Start of Construction (One Call Center 1-800-632-4949). All Costs Associated with Any Damage to Known or Unknown Existing Utilities Resulting from the Contractor's Failure to Adequately Protect the Existing Utilities during Construction Shall be Borne Solely by the Contractor.
- The Engineer and the Owner Shall be Notified 24 hours prior to any Service Interruptions or Connections being Made. Any Service Interrupted by the Contractor Shall be Returned to Service before the End of the Working Day.
- Support Existing Poles, Fences, Culverts, Pavement, Utilities, Curbing, and Other Structures during Construction. Repair Damaged Items to their Original Condition at No Additional Cost to Owner.
- Temporarily Remove Minor Items as Required for Construction. Minor Items shall Include, but are NOT Limited to: Existing Signs, Fences, Mailboxes, etc. Reinstall Items to their Original Condition at a Location as Close to the Original Location as Practicable.
- Where Indicated, Remove and Replace Existing Curb & Gutter (Match Existing Elevation and Location Unless Otherwise Shown). Remove to Nearest Joint if within 5' of Full Height Curb; otherwise Provide New Joint in Curb & Gutter.
- Where Practicable Sidewalk Transitions Shall Not Exceed 12:1 Slope per ADA and Sidewalk Cross-Slope shall be 2% Maximum. See Spot Elevations and Cross-Sections.
- Sidewalks to Join Flush with Existing or Proposed Concrete Drives and Existing Curb & Gutter to Remain.
- Driveway Impacts are anticipated with this Project and Access during Construction Shall be Coordinated with each Owner.
- Contractor will Adjust Manholes, Water Valves, and Meter Boxes as necessary to Coordinate with Sidewalk or Grade Changes.
- All Proposed Concrete Driveways shall be 6-inches Thick (3,000 PSI) Unless Otherwise Noted. All Proposed Concrete Sidewalk shall be 4-inches Thick (3,000 PSI) Unless Otherwise Noted.
- If any Lane Closure is Necessary, Streets shall Remain Open (at least One Lane) to Local Traffic during Construction. Contractor shall Submit Traffic Control Plan, highlighting Key Milestones, to Engineer for Approval prior to Beginning Construction. No Lane of Traffic shall be Closed or Restricted Monday through Friday between the Hours of 6 AM to 9 AM or between 4 PM to 7 PM. Comply with All NCDOT Provisions in the Approved Encroachment Agreement including Posting of any Required Bonds.

LEGEND

Font Style Indicates Existing Features

FONT STYLE INDICATES DESIGN FEATURES

SURVEY

CODE	Existing	PROPOSED
BENCHMARK	BM	
CONTROL POINT	CP	
IRON PIPE FOUND	IPF	
IRON PIPE SET	IPS	
IRON ROD FOUND	IRF	
IRON ROD SET	IRS	
NAIL FOUND	NLF	
NAIL SET	NLS	
PK NAIL FOUND	PKF	
PK NAIL SET	PKS	
PROPERTY LINE		
TEMPORARY BENCHMARK	TBM	

EASEMENTS

CODE	Existing	PROPOSED
ACCESS EASEMENT	AE	
DRAINAGE EASEMENT	SDE	
PUBLIC UTILITY EASEMENT	UE/PUE	
RIGHT-OF-WAY	RW	
RIGHT-OF-WAY (RAILROAD)	RRW	
SEWER EASEMENT	SSE	
TEMPORARY CONSTRUCTION EASEMENT	TCE	
WATER EASEMENT	WLE	

EROSION CONTROL

CODE	Existing	PROPOSED
CHECK DAM	RCHK	
INLET PROTECTION		
RIP-RAP	RPRP	
LIMITS OF DISTURBANCE		
RIPARIAN BUFFER - ZONE 1	RBZ1	
RIPARIAN BUFFER - ZONE 2	RBZ2	
SILT FENCE	SF	
SILT FENCE OUTLET	SFOLT	
SILT FENCE / TREE PROTECTION FENCE	SF/TPF	
SUPER SILT FENCE	SSF	
TREE PROTECTION FENCE	TPF	
WATTLE	WTTL	
WATTLE BARRIER	WB	

ROADWAY

CODE	Existing	PROPOSED
ASPHALT DRIVEWAY		
ASPHALT OVERLAY		
BRICK DRIVEWAY		
EDGE OF PAVEMENT	EP	
GRAVEL DRIVEWAY / PATH		
SOIL DRIVEWAY / PATH		

SITE

CODE	Existing	PROPOSED
AREA LIGHT / LIGHT POLE	LP	
BOLLARD	BOLL	
FENCE	FNC	
FIRE HOSE	HOSE	
FIRE WATER LINE	FWL	
SIGN	SN	

STORM DRAINAGE

CODE	Existing	PROPOSED
CATCH BASIN / COMBINATION INLET	CB	
CURB INLET	CI	
DROP INLET	DI	
FLARED END SECTION	FES	
JUNCTION BOX	JB	
DRAINAGE MANHOLE	SDMH	
STORM DRAINAGE PIPE		

SEWER

CODE	Existing	PROPOSED
CLEAN OUT	SSCO	
GRAVITY SEWER LINE	SS	
SEWER MANHOLE	SSMH	

UTILITIES

CODE	Existing	PROPOSED
CABLE TV CABLE	CTV	
UNDERGROUND ELECTRICAL CABLE	UGE	
OVERHEAD ELECTRICAL WIRE	OHE	
ELECTRICAL HAND HOLE	EHH	
ELECTRICAL METER	EM	
ELECTRICAL PEDESTAL	EPED	
FIBER OPTIC CABLE	FOC	
FIBER OPTIC HAND HOLE	FOHH	
GAS LINE	GL	
GAS METER	GM	
GAS VALVE	GV	
GUY / ANCHOR WIRE	GUY	
LIGHT POLE / AREA LIGHT	LP	
POWER POLE	PP	
TELECOMMUNICATIONS CABLE	COM	
TELEPHONE CABLE	COM	
TELEPHONE HAND HOLE	THH	
TELEPHONE PEDESTAL	TPED	
TRAFFIC SIGNAL BOX	TFCB	
TRAFFIC SIGNAL POLE	TFCP	
TRANSFORMER	TRNS	
UTILITY POLE	UP	

VEGETATION

CODE	Existing	PROPOSED
CONIFEROUS TREE	CTREE	
DECIDUOUS TREE	DTREE	
HEDGE / SHRUB ROW	HED	
LANDSCAPING	LSCP	
SHRUB	SHB	
STUMP		
TREELINE / WOODS		

WATER

CODE	Existing	PROPOSED
FIRE HYDRANT	FH	
FIRE HYDRANT VALVE	FHV	
REDUCER / INCREASER	RDCR	
WATER LINE	WL	
WATER METER	WM	
WATER VALVE	WV	
YARD HYDRANT	YH	

REVISIONS

Wooten

120 North Boylan Avenue • Raleigh, NC 27603-1423
(919) 828-0531 • thewootencompany.com
License Number: F-0115

NORTH CAROLINA

ZEBULON MAINTENANCE YARD EXPANSION

TOWN OF ZEBULON

GENERAL NOTES - LEGENDS

FINAL DRAWING NOT RELEASED FOR CONSTRUCTION



ISSUED FOR:

PERMITTING

DATE: 1/26/2024

DESIGNED BY: **AMW**


DRAWN BY: **THR**

CHECKED BY: **AMW**


PROJECT NO.: **2922-S**

C-0.02

T:\Standards\CADD\Civil3D\01_Templates\TWC-CIVL_Titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM



LINE	BEARING	DISTANCE
L1	S81°56'58"E	28.15'
L2	N87°54'06"E	99.96'
L3	N79°38'32"E	99.97'
L4	N77°04'51"E	99.97'
L5	N76°18'05"E	99.97'
L6	N77°12'59"E	99.99'
L7	N79°25'36"E	100.01'
L8	N82°35'26"E	99.99'
L9	N29°04'30"W	83.03'




NO.	DATE	DESCRIPTION

Wooten
 120 North Boylan Avenue • Raleigh, NC 27603-1423
 (919) 828-0531 • thewootencompany.com
 License Number: F-0115

TOWN OF ZEBULON
 NORTH CAROLINA
 ZEBULON MAINTENANCE YARD EXPANSION
 OVERALL EXISTING CONDITIONS PLAN


FINAL DRAWING
 NOT RELEASED FOR CONSTRUCTION



ISSUED FOR:
PERMITTING
 DATE: 1/26/2024
 DESIGNED BY: AMW
 DRAWN BY: THR
 CHECKED BY: AMW
 PROJECT NO.: 2922-S

C-1.00

T:\Standards\CADD\Civil3D\01_Templates\TWC-CIVL_Titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM



NAOMI ST.
50' R/W

(NC 2345) EAST HORTON STREET
(60' Right-of-Way)


CP-17: CP-02
N: 755807.39
E: 2205527.01
ELEV.: 318.40

2705-55-4601
N/F NANCY R. HOLDER
DB: 5437, PG: 874
Zoning: DTP

2705-55-4323
N/F JERRY L. REED
& CONNIE J. REED
DB: 4322, PG: 443
PB: 1971, PG: 412
Zoning: DTP

2705-55-8698
TOWN OF ZEBULON
DB: 4090, PG: 243 PB: 1987, PG: 1442

NORFOLK SOUTHERN R/R
Railroad Tracks



REVISIONS

Wooten
 120 North Boylan Avenue • Raleigh, NC 27603-1423
 (919) 828-0531 • thewootencompany.com
 License Number: F-0115

NORTH CAROLINA
 TOWN OF ZEBULON
 ZEBULON MAINTENANCE YARD EXPANSION
 EXISTING CONDITIONS

FINAL DRAWING
 NOT RELEASED FOR CONSTRUCTION


PROFESSIONAL ENGINEER
 SEAL 042389
 ASHLEY M. WADSWORTH

ISSUED FOR: PERMITTING

DATE: 1/26/2024
 DESIGNED BY: AMW
 DRAWN BY: THR
 CHECKED BY: AMW
 PROJECT NO.: 2922-S

C-1.01




T:\Standards\CADD\Civil3D\01_Templates\TWC-CIVIL_titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM




2705-55-4601
N/F NANCY R. HOLDER
DB: 5437, PG: 874
Zoning: DTP

2705-55-4323
N/F JERRY L. REED
& CONNIE J. REED
DB: 4322, PG: 443
PB: 1971, PG: 412
Zoning: DTP

CP-17: CP-02
N: 755807.39
E: 2205527.01
ELEV.: 318.40

-  TREE CLEARING AREA
-  GRAVEL DRIVE TO BE REMOVED
-  ASPHALT DRIVE TO BE REMOVED

NOTE:
ITEMS SHOWN IN RED TO BE REMOVED / RELOCATED.




REVISIONS

Wooten
120 North Boylan Avenue • Raleigh, NC 27603-1423
(919) 828-0531 • thewootencompany.com
License Number: F-0115

TOWN OF ZEBULON
ZEBULON MAINTENANCE YARD EXPANSION
DEMOLITION PLAN

FINAL DRAWING
NOT RELEASED FOR CONSTRUCTION




ISSUED FOR:

PERMITTING



DATE:	1/26/2024
DESIGNED BY:	AMW
DRAWN BY:	THR
CHECKED BY:	AMW
PROJECT NO.:	2922-S

C-1.02




- LANDSCAPE SCREENING NOTES:**
1. 15' MIN. WIDTH.
 2. MIN. 4 SHADE TREES PER 100 FEET.
 3. MIN. 15 SHRUBS PER 100'.
 4. SHRUBS MIN. 5' HEIGHT.
 5. SHRUBS & GRASSES IN DUKE ENERGY R.O.W. 7' MAX. HEIGHT.
 6. TREES IN DUKE ENERGY R.O.W. 15' MAX. HEIGHT.
 7. ALL VEGETATION IN DUKE ENERGY R.O.W. MUST BE APPROVED BY DUKE ENERGY.

CP-17: CP-02
N: 755807.39
E: 2205527.01
ELEV.: 318.40



SITE KEYNOTES

- (A) 200 AMP, 3 PHASE PANEL (BY OTHERS) FOR GATE, POWER SOURCE
 - (B) 33' ALUMINUM AUTOMATED GATE (OWNER TO PROVIDE)
 - (C) TREE CLEARING LIMIT LINE
 - (D) 6' SECURITY FENCE, TOPPED WITH BARBED WIRE
 - (E) 20' SCM ACCESS GATE
 - (F) CONCRETE APRON
 - (G) 2' WIDE STOP BAR, WHITE PAINT
 - (H) STOP SIGN, (R1-1)
 - (J) LANDSCAPE BUFFER
 - (K) 8"-12" DIP CASING, CAPPED AT ENDS
 - (L) 6' SECURITY FENCE, WITHOUT BARBED WIRE
- HEAVY DUTY PAVEMENT; 3" S9.5C/8" CABC
 8" CABC GRAVEL LOT



REVISIONS

Wooten
120 North Boylan Avenue • Raleigh, NC 27603-1423
(919) 828-0531 • thewootencompany.com
License Number: F-0115

NORTH CAROLINA
TOWN OF ZEBULON
ZEBULON MAINTENANCE YARD EXPANSION
SITE & LANDSCAPE PLAN

FINAL DRAWING
NOT RELEASED FOR CONSTRUCTION




ISSUED FOR:

PERMITTING



DATE: 1/26/2024
DESIGNED BY: AMW
DRAWN BY: THR
CHECKED BY: AMW
PROJECT NO.: 2922-S

C-2.00



CONCRETE PAVING SECTION



NOTE:
1: NC 2345 EXISTING SPEED LIMIT IS 35 MPH.



ROW IMPROVEMENT ALIGNMENT



REVISIONS

Wooten
120 North Boylan Avenue • Raleigh, NC 27603-1423
(919) 828-0531 • thewootencompany.com
License Number: F-0115

NORTH CAROLINA
TOWN OF ZEBULON
ZEBULON MAINTENANCE YARD EXPANSION
RIGHT-OF-WAY LAYOUT PLAN

FINAL DRAWING
NOT RELEASED FOR CONSTRUCTION




ISSUED FOR:

PERMITTING

DATE: 1/26/2024
DESIGNED BY: AMW
DRAWN BY: THR
CHECKED BY: AMW
PROJECT NO.: 2922-S

C-2.01






SIGHT DISTANCE CALCULATIONS

POSTED SPEED LIMIT : 35 MPH
 DESIGN SPEED LIMIT: 40 MPH

CASE B1- LEFT TURN FROM MINOR ROAD
 ISD = 1.47 * 40MPH * 9.5
 ISD = 559 LF

CASE B2- RIGHT TURN FROM MINOR ROAD
 ISD = 1.47 * 40MPH * 8.5
 ISD = 500 LF



T:\Standards\CADD\Civil3D\01_Templates\TWC-CIVL_Titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM

REVISIONS

Wooten
 120 North Boylan Avenue • Raleigh, NC 27603-1423
 (919) 828-0531 • thewootencompany.com
 License Number: F-0115

TOWN OF ZEBULON
 NORTH CAROLINA
 ZEBULON MAINTENANCE YARD EXPANSION

SIGHT DISTANCE CALCULATIONS

FINAL DRAWING
 NOT RELEASED FOR CONSTRUCTION




ISSUED FOR:

PERMITTING

DATE: 1/26/2024
 DESIGNED BY: AMW
 DRAWN BY: THR
 CHECKED BY: AMW
 PROJECT NO.: 2922-S

C-2.02

T:\Standards\CADD\Civil3D\01_Templates\TWC-CIVL_Titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM



REVISIONS

Wooten
 120 North Boylan Avenue • Raleigh, NC 27603-1423
 (919) 828-0531 • thewootencompany.com
 License Number: F-0115

TOWN OF ZEBULON
 NORTH CAROLINA
 ZEBULON MAINTENANCE YARD EXPANSION

GRADING & DRAINAGE PLAN



FINAL DRAWING
 NOT RELEASED FOR CONSTRUCTION



ISSUED FOR:
PERMITTING

DATE: 1/26/2024
 DESIGNED BY: AMW
 DRAWN BY: THR
 CHECKED BY: AMW
 PROJECT NO.: 2922-S


C-3.00



46 LF- 18" RCP @ 1.0%
 INV: 302.00
 4' x 6' CLASS A RIP RAP DISSIPATER PAD WITH GEOTEXTILE UNDERLINER

- STORMWATER WETLAND MAINTENANCE NOTES:**
1. CONDUCT BI-WEEKLY INSPECTIONS AND WATER WETLAND PLANTS BI-WEEKLY UNTIL VEGETATION BECOMES ESTABLISHED.
 2. BEFORE AND IMMEDIATELY AFTER PLANT INSTALLATION, MONITOR WATER LEVEL AND ADJUST TO ENSURE THAT PLANTS ARE NOT COMPLETELY INUNDATED.
 3. NO PORTION OF WETLAND SHALL BE FERTILIZED AFTER THE INITIAL FERTILIZATION THAT IS REQUIRED TO ESTABLISH THE WETLAND PLANTS.
 4. STABLE GROUND COVER SHALL BE MAINTAINED IN THE DRAINAGE AREA TO REDUCE SEDIMENT LOAD TO WETLAND.
 5. AT LEAST ONCE ANNUALLY, INSPECT THE EMBANKMENT. ANY PROBLEMS THAT ARE FOUND WILL BE REPAIRED IMMEDIATELY.
 6. AFTER WETLAND IS ESTABLISHED, IT SHALL BE INSPECTED MONTHLY WITHIN 24 HOURS AFTER EVERY STORM EVENT GREATER THAN 1 INCH.
 7. RECORDS OF OPERATION AND MAINTENANCE SHALL BE KEPT IN A KNOWN SET LOCATION AND SHALL BE AVAILABLE UPON REQUEST.
 4. SEE SCM MAINTENANCE PLAN FOR SPECIFIC INSPECTION ACTIVITIES.

PERIMETER OF WETLANDS SHALL BE STABILIZED WITH SOD, ESPECIALLY DURING THE CONVERSION OF SEDIMENT TRAPS



STORMWATER WETLAND
 NOT TO SCALE

T:\Standards\CADD\Civil3D\01_Templates\TWC-CIVIL_Titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM

REVISIONS

Wooten
 120 North Boylan Avenue • Raleigh, NC 27603-1423
 (919) 828-0531 • thewootencompany.com
 License Number: F-0115

NORTH CAROLINA
 ZEBULON MAINTENANCE YARD EXPANSION
 TOWN OF ZEBULON
 STORMWATER MANAGEMENT PLAN

FINAL DRAWING
 NOT RELEASED FOR CONSTRUCTION

ISSUED FOR:



PERMITTING

DATE: 1/26/2024

DESIGNED BY:	AMW
DRAWN BY:	THR
CHECKED BY:	AMW
PROJECT NO.:	2922-S

C-3.01

T:\Standards\CADD\Civil3D\01_Templates\TWC-CIVL_Titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM



SHALLOW WATER ZONE REQ.
 50 HERBACEOUS PLANTS/200 SF (2' OC)
 6 SPECIES

SHALLOW WATER ZONE CALCULATIONS
 SHALLOW WATER ZONE #1: 657 SF
 $\frac{657}{200} \times 50 = 164$ PLANTS REQUIRED

SHALLOW WATER ZONE #2: 1,547 SF
 $\frac{1547}{200} \times 50 = 387$ PLANTS REQUIRED

TOTAL PLANTS REQUIRED: 551
TOTAL PLANTS PROVIDED: 551

TEMPORARY INUNDATION ZONE REQ. OPTIONS:

- 50 HERBACEOUS PLANTS/200 SF (2' OC)
- 8 SHRUBS PER 200 SF (5' OC)
- ONE TREE AND 40 GRASS-LIKE HERBACEOUS PLANT/100 SF

TEMPORARY INUNDATION ZONE CALCULATIONS
 TEMPORARY INUNDATION ZONE: 2,913 SF
 $\frac{2193}{200} \times 50 = 548$ PLANTS REQUIRED

-OR-

$\frac{2193}{200} \times 8 = 88$ SHRUBS REQUIRED

-OR-

$\frac{2193}{100} \times 40 = 22$ TREES AND 877 PLANTS

TOTAL SHRUBS PROVIDED: 88

PLANTS LIST- WETLAND AREA PLANTINGS ONLY

QTY	SYM	BOTANICAL NAMME	COMMON NAME	MIN. SIZE	REMARKS
HERBACEOUS PLANTS (SHALLOW WATER ZONE PLANTINGS)- 6 VARIETIES					
51	CF	CANNA FLACCIDA	YELLOW CANNA	1 QT	24" O.C
37	IV	IRIS VIRGINIANA	VIRGINIA IRIS	1 QT	24" O.C
101	NO	NYMPHAEA ODORATA	AMERICAN WHITE WATERLILY	1 QT	24" O.C
230	PC	POTEDERIA CORDATA	PICKERELWEED	1 QT	24" O.C
80	PV	PELTANDRA VIRGINICA	ARROW ARUM	1 QT	24" O.C
52	ST	SCHOENOPECTUS TABERNWONTANI	SOFTSTEM BULRUSH	1 QT	24" O.C
SHRUBS (TEMPORARY INUNDATION ZONE PLANTINGS)- OPTION 2					
29	AA	ARONIA ARBUTIFOLIA	RED CHOKEBERRY	3 GAL	5' O.C
42	CA	CORNUS AMOMUM	SILKY DOGWOOD	3 GAL	5' O.C
17	SS	SALIX SERICA	SILKY WILLOW	3 GAL	5' O.C

REVISIONS

Wooten
 120 North Boylan Avenue • Raleigh, NC 27603-1423
 (919) 628-0531 • thewootencompany.com
 License Number: F-0115

NORTH CAROLINA
 TOWN OF ZEBULON
 ZEBULON MAINTENANCE YARD EXPANSION
 SCM PLANTING PLAN


FINAL DRAWING
 NOT RELEASED FOR CONSTRUCTION

ISSUED FOR:
PERMITTING

DATE: 1/26/2024
 DESIGNED BY: AMW
 DRAWN BY: THR
 CHECKED BY: AMW
 PROJECT NO.: 2922-S

C-3.02

T:\Standards\CADD\Civil3D\01_Templates\TWC-CIVL_Titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM




EROSION CONTROL NOTES/LEGEND:

- 1. LIMITS OF DISTURBANCE = 2.09 AC
- 2. SEE SHEET C-6.03 FOR EROSION CONTROL SEQUENCE

- NA GREEN S75BN MATTING OR APPROVED EQUAL
- WATTLE
- LOD
- SILT FENCE
- COMBINATION SILT AND TREE PROTECTION FENCE
- SILT FENCE OUTLET
- INLET PROTECTION

EXISTING STORMWATER CONTROL FEATURE MUST BE LEFT IN OPERATION UNTIL REMAINDER OF SITE HAS BEEN STABILIZED. THEN DIVERSION DITCH CAN BE INSTALLED.



REVISIONS

wooten
 120 North Boylan Avenue • Raleigh, NC 27603-1423
 (919) 828-0531 • thewootencompany.com
 License Number: F-0115

TOWN OF ZEBULON
 NORTH CAROLINA
 ZEBULON MAINTENANCE YARD EXPANSION
 EROSION & SEDIMENT POLLUTION CONTROL PLAN - PHASE 1

FINAL DRAWING
 NOT RELEASED FOR CONSTRUCTION

ISSUED FOR:


PERMITTING

DATE: 1/26/2024

DESIGNED BY: AMW
 DRAWN BY: THR
 CHECKED BY: AMW
 PROJECT NO.: 2922-S

C-5.00

T:\Standards\CADD\Civil3D\01_Templates\TWC-CIVL_Titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM




2705-55-4601
N/T NANCY R. HOLDER
DB: 5437, PG: 874
Zoning: DTP


2705-55-4323
N/T JERRY L. REED
& CONNIE J. REED
DB: 4322, PG: 443
PB: 1971, PG: 412
Zoning: DTP

EROSION CONTROL NOTES/LEGEND:

1. LIMITS OF DISTURBANCE = 2.09 AC
2. SEE SHEET C-6.03 FOR EROSION CONTROL SEQUENCE






EXISTING STORMWATER CONTROL FEATURE MUST BE LEFT IN OPERATION UNTIL REMAINDER OF SITE HAS BEEN STABILIZED. THEN DIVERSION DITCH CAN BE INSTALLED.




<p>REVISIONS</p>	
	120 North Boylan Avenue • Raleigh, NC 27603-1423 (919) 828-0531 • thewootencompany.com License Number: F-0115
NORTH CAROLINA TOWN OF ZEBULON	ZEBULON MAINTENANCE YARD EXPANSION EROSION & SEDIMENT POLLUTION CONTROL PLAN - PHASE 2
<p>FINAL DRAWING NOT RELEASED FOR CONSTRUCTION</p>	
ISSUED FOR: <p>PERMITTING</p>	
DATE: 1/26/2024 DESIGNED BY: AMW DRAWN BY: THR CHECKED BY: AMW PROJECT NO.: 2922-S	
C-5.01	

T:\Standards\CADD\Civil3D\01_Templates\TWC-CIVL_Titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM




NOTES
 1. SEED AND PLACE MATTING FOR EROSION CONTROL ON INTERIOR AND EXTERIOR SIDESLOPES, TO TOP OF BANK
 2. INSTALL A MINIMUM OF 3 COIR FIBER BAFFLES IN ACCORDANCE WITH PRACTICE STANDARD 6.65.
 3. INSTALL SKIMMER AND COUPLING TO RISER STRUCTURE OR DIRECTLY INTO EMBANKMENT 1 FT. FROM BOTTOM OF BASIN.
 4. THE ARM PIPE SHALL HAVE A MINIMUM LENGTH OF 6 FT. BETWEEN THE SKIMMER AND COUPLING.

TEMPORARY SEDIMENT BASIN WITH SKIMMER
 NOT TO SCALE




SKIMMER BASIN	
DISTURBED AREA (AC)	1.43
PEAK RUNOFF (10 YR STORM) (CFS)	17.45
REQUIRED VOLUME (CF)	2,574
PROVIDED VOLUME (CF)	3,248
REQUIRED SURFACE AREA (SF)	7,603
PROVIDED SURFACE AREA (SF)	8,952
SKIMMER SIZE (IN)	2.00
HEAD ON SKIMMER (FT)	0.17
ORIFICE SIZE (IN)	1.00
DEWATERING TIME (DAYS)	2.73

NOTES:
 1. SKIMMER IS TO BE A SURFACE DEWATERING DEVICE SUCH AS BMP SKIMMER OR APPROVED DEVICE.
 2. SKIMMER SHOULD RISE TO LEVEL OF WEIR HEIGHT IN TEMPORARY BASIN OR TO RISER INLET.
 3. ROPE ATTACHED TO SKIMMER TO HELP KEEP CLEAN.



EXISTING STORMWATER CONTROL FEATURE MUST BE LEFT IN OPERATION UNTIL REMAINDER OF SITE HAS BEEN STABILIZED. THEN DIVERSION DITCH CAN BE INSTALLED.



REVISIONS

Wooten
 120 North Boylan Avenue • Raleigh, NC 27603-1423
 (919) 828-0531 • thewootencompany.com
 License Number: F-0115

NORTH CAROLINA
 TOWN OF ZEBULON
 ZEBULON MAINTENANCE YARD EXPANSION
 EROSION & SEDIMENT POLLUTION CONTROL PLAN - SKIMMER DETAIL

FINAL DRAWING
 NOT RELEASED FOR CONSTRUCTION




ISSUED FOR:
PERMITTING

DATE: 1/26/2024
 DESIGNED BY: AMW
 DRAWN BY: THR
 CHECKED BY: AMW
 PROJECT NO.: 2922-S

C-5.02


T:\Standards\CADD\Civil3D\01_Templates\TWC-CIVL_Titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM



STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR DRIVEWAY TURNOUT DRIVEWAY GRADES





SHEET 2 OF 2
848.03



STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR DRIVEWAY TURNOUT DRIVEWAY CURB TYPE

SHEET 1 OF 2
848.03



REVISIONS

NORTH CAROLINA

TOWN OF ZEBULON

ZEBULON MAINTENANCE YARD EXPANSION

DETAILS

FINAL DRAWING NOT RELEASED FOR CONSTRUCTION

ISSUED FOR:

PERMITTING

DATE: 1/26/2024

DESIGNED BY: AMW

DRAWN BY: THR

CHECKED BY: AMW


PROJECT NO.: 2922-S

C-6.00


Wooten

120 North Boylan Avenue • Raleigh, NC 27603-1423
 (919) 828-0531 • thewootencompany.com
 License Number: F-0115






DIVERSION DITCH
NOT TO SCALE




- NOTE:**
- ENTRANCE APPLICABLE AT ALL POINTS OF INGRESS AND EGRESS UNTIL SITE IS STABILIZED.
 - CONSTRUCTION ENTRANCE SHALL BE PLACED FOR MAXIMUM UTILITY BY ALL CONSTRUCTION VEHICLES.
 - PERIODIC TOP DRESSING AND ROUTINE MAINTENANCE SHALL BE PROVIDED ON ENTRANCE AS REQUIRED. CONTRACTOR SHALL STOCKPILE FRESH STONE ON SITE.
 - ANY MATERIAL THAT MAKES IT TO EXISTING PUBLIC ROADWAY SHALL BE REMOVED AND CLEANED IMMEDIATELY.
- MAINTENANCE REQUIREMENTS:**
- MAINTAIN ENTRANCE IN A CONDITION WHICH PREVENTS TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 2 INCHES OF STONE, AS CONDITIONS REQUIRE, AT NO ADDITIONAL COST TO THE OWNER.

TEMPORARY CONSTRUCTION ENTRANCE
NOT TO SCALE





- NOTES:**
- POSTS SET AT DEPTHS OF 4' FOR EARTH BACKFILL. ANCHOR DITCH IS 9" x 9" AND FILL IS TO BE COMPACTED.
 - PROVIDE ADEQUATE EXCAVATION AHEAD OF SILT FENCE TO ACT AS A VELOCITY BREAK AND SILT TRAP.
 - CONTRACTOR MAY USE ALTERNATE MATERIAL OR METHOD UPON APPROVAL FROM ENGINEER.

SILT FENCE
NOT TO SCALE




- INSTALLATION OF LINER:**
- APPLY LIME, FERTILIZER, AND SEED BEFORE LAYING LINER.
 - LAY LINER FROM TOP OF DITCH OR CHANNEL AND UNROLL IT DOWNGRADE. DO NOT STRETCH OR LEAVE WRINKLES.
 - BURY THE UPSLOPE END IN A SLOT 6" DEEP. PROVIDE STAPLES AND OVERLAP AS SHOWN ABOVE.
- MAINTENANCE:**
- INSPECT AFTER RAINSTORMS FOR EROSION OR FAILURE. REPAIR ALL WASHED OUT AREAS BY REGRADING, RESEEDING, AND REINSTALLING MULCH.



EROSION CONTROL BLANKET
NOT TO SCALE



SILT FENCE OUTLET DETAIL
NOT TO SCALE



ENERGY DISSIPATION PAD/RIPRAP APRON
NOT TO SCALE



Wooten
120 North Boylan Avenue • Raleigh, NC 27603-1423
(919) 828-0531 • thewootencompany.com
License Number: F-0115

TOWN OF ZEBULON
NORTH CAROLINA
ZEBULON MAINTENANCE YARD EXPANSION
DETAILS

FINAL DRAWING
NOT RELEASED FOR CONSTRUCTION

PROFESSIONAL ENGINEER
SEAL 042389
M. WADSWORTH

ISSUED FOR:
PERMITTING

DATE: 1/26/2024
DESIGNED BY: AMW
DRAWN BY: THR
CHECKED BY: AMW
PROJECT NO.: 2922-S

C-6.01

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT
 Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION		
Required Ground Stabilization Timeframes		
Site Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b) High Quality Water (HQW) Zones	7	None
(c) Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d) Slopes 3:1 to 4:1	14	- 7 days for slopes greater than 50' in length and with slopes steeper than 4:1 - 7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones - 10 days for Falls Lake Watershed
(e) Areas with slopes flatter than 4:1	14	- 7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones - 10 days for Falls Lake Watershed unless there is zero slope

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION
 Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Temporary Stabilization	Permanent Stabilization
<ul style="list-style-type: none"> Temporary grass seed covered with straw or other mulches and tackifiers Hydroseeding Roll erosion control products with or without temporary grass seed Appropriately applied straw or other mulch Plastic sheeting 	<ul style="list-style-type: none"> Permanent grass seed covered with straw or other mulches and tackifiers Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Stakes or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or retaining walls Roll erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants.
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions.
- Provide ponding area for containment of treated Stormwater before discharging offsite.
- Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- Provide drip pans under any stored equipment.
- Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
- Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- Remove leaking vehicles and construction equipment from service until the problem has been corrected.
- Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers.
- Provide a sufficient number and size of waste containers (e.g. dumpster, trash receptacle) on site to contain construction and domestic wastes.
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
- Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
- Dispose waste off-site at an approved disposal facility.
- On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE


- Do not dump paint and other liquid waste into storm drains, streams or wetlands.
- Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site.
- Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

PORTABLE TOILETS

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. 150 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.
- Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.



CONCRETE WASHOUTS

- Do not discharge concrete or cement slurry from the site.
- Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
- Manage washout from rotar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
- Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
- Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
- Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
- At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

HERBICIDES, PESTICIDES AND RODENTICIDES

- Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE

- Create designated hazardous waste collection areas on-site.
- Place hazardous waste containers under cover or secondary containment.
- Do not store hazardous chemicals, drums or bagged materials directly on the ground.

TEMPORARY SEEDING (BY SEASON)

FALL		LATE WINTER AND EARLY SPRING	
SEEDING MIXTURE	RATE (lb/acre)	SEEDING MIXTURE	RATE (lb/acre)
Rye (grain)	120	Rye (grain)	120
Mountains - Aug 15 thru Dec 15		Annual Lespedeza (kobe in piedmont and coastal plain, Korean in mountains)	50
Coastal plain and piedmont - Aug 15 thru Dec 30			

SEEDING DATES
 Mountains - Aug 15 thru Dec 15
 Coastal plain and piedmont - Aug 15 thru Dec 30

SOIL AMENDMENTS
 Follow recommendation of soil tester or apply 2,000 lb/acre (4,000 lbs/acre in clay soils) Ground Agricultural Limestone, 1000 lb/acre 10-10-10 fertilizer, and 400 gallons/acre asphalt emulsion tack rate.

MULCH
 Apply 4,000 lb/acre straw. Anchor straw by tacking with asphalt, netting

MAINTENANCE
 Repair and fertilize damaged areas immediately. Topdress with 50 lb/acre of nitrogen in March. If necessary to extend temporary cover beyond June 15, overseed with 50 lb/acre Kobe (Piedmont and Coastal plain) Lespedeza in late February or early March.

SUMMER

SEEDING MIXTURE	RATE (lb/acre)
German Millet	40

In the piedmont and mountains, a small stemmed Sundgrass may be substituted at a rate of 50 lb/acre.

SEEDING DATES
 Mountains - May 15 thru Aug 15
 Piedmont - May 1 thru Aug 15
 Coastal plain - Apr 15 thru Aug 15

SOIL AMENDMENTS
 Follow recommendation of soil tester or apply 2,000 lb/acre (4,000 lbs/acre in clay soils) Ground Agricultural Limestone, 1000 lb/acre 10-10-10 fertilizer, and 400 gallons/acre asphalt emulsion tack rate.

MULCH
 Apply 4,000 lb/acre straw. Anchor straw by tacking with asphalt, netting

MAINTENANCE
 Refertilize if growth is not fully adequate. Reseed, refertilize and mulch immediately following erosion or other damage.

PERMANENT SEEDING

Planting Dates	Grass Type	Pounds/Acre
Aug. 15-Nov. 1	Tall Fescue	300
Nov. 1-Mar. 1	Tall Fescue & Abruzzi Rye	300
Mar. 1-April 15	Tall Fescue	25
April 15 - June 30	Hulled Common Bermuda Grass	25
July 1-Aug. 15	Tall Fescue	120
&	Browntop Millet	35
&	Sorghum-Sundan Hybrids	30
Lime Fertilizer	10-10-10	4,000
Mulch	Straw	1,000
		4,000

STABILIZATION NOTES

- STABILIZATION FOR THIS PROJECT SHALL COMPLY WITH THE TIMEFRAME GUIDELINES AS SPECIFIED BY THE NCG-01 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 2, 2011 ISSUED BY NCDQW. TEMPORARY OR PERMANENT GROUND COVER STABILIZATION SHALL OCCUR WITHIN 7 CALENDAR DAYS FROM LAST LAND-DISTURBING ACTIVITIES, WITH THE FOLLOWING EXCEPTIONS IN WHICH TEMPORARY OR PERMANENT GROUND COVER SHALL BE PROVIDED IN 14 CALENDAR DAYS FROM LAST LAND DISTURBING ACTIVITIES.
 - SLOPES BETWEEN 2:1 AND 3:1, WITH A SLOPE LENGTH OF 10 FEET OR LESS
 - SLOPES 3:1 OR FLATTER, WITH A SLOPE LENGTH OF 50 FEET OR LESS.
 - SLOPES 4:1 OR FLATTER

EROSION CONTROL MAINTENANCE

THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING EROSION CONTROL DEVICES THROUGH THE PROJECT DURATION.

- THE SEDIMENTATION POLLUTION CONTROL ACT WAS AMENDED IN 2006 TO REQUIRE THAT PERSONS RESPONSIBLE FOR LAND-DISTURBING ACTIVITIES INSPECT A PROJECT AFTER EACH PHASE OF THE PROJECT TO MAKE SURE THAT THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN IS BEING FOLLOWED. RULES DETAILING THE DOCUMENTATION OF THESE INSPECTIONS BECAME EFFECTIVE OCTOBER 1, 2010. TO SIMPLIFY DOCUMENTATION OF SELF-INSPECTION REPORTS AND NPDES SELF-MONITORING REPORTS, A COMBINED FORM IS NOW AVAILABLE. THE NEW FORM WAS DEVELOPED TO SATISFY THE REQUIREMENTS OF THE SEDIMENTATION POLLUTION CONTROL ACT AND THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES, NCG 010000. BEGINNING AUGUST 1, 2013, THE DIVISION OF ENERGY, MINERAL, AND LAND RESOURCES IS RESPONSIBLE FOR ADMINISTERING BOTH THE SPCA AND THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES, NCG 010000. THE COMBINED FORM SHOULD MAKE IT EASIER TO COMPLY WITH SELF-INSPECTION REQUIREMENTS. THE COMBINED SELF-MONITORING FORM IS AVAILABLE AS A PDF AND WORD DOCUMENT FROM THE LAND QUALITY WEB SITE: <https://deq.nc.gov/about/divisions/energy-mineral-land-resources/erosion-sediment-control/forms>
- ALL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL (≥1.0 IN.) BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS WILL BE MADE IMMEDIATELY TO MAINTAIN ALL PRACTICES AS DESIGNED.
- SEDIMENT WILL BE REMOVED FROM THE BEHIND ANY EROSION CONTROL DEVICES WHEN STORAGE CAPACITY HAS BEEN APPROXIMATELY 50% FILLED. GRAVEL WILL BE CLEANED OR REPLACED WHEN THE SEDIMENT POOL NO LONGER DRAINS PROPERLY.
- SEDIMENT WILL BE REMOVED FROM BEHIND THE SEDIMENT FENCE WHEN IT BECOMES 6 INCHES DEEP AT THE FENCE. THE SEDIMENT FENCE WILL BE REPAIRED AS NECESSARY TO MAINTAIN A BARRIER.
- SEDIMENTS WILL BE REMOVED FROM THE GRAVEL INLET PROTECTION AND ALL INLET PROTECTIONS AFTER EACH SIGNIFICANT RAINFALL EVENT.
- ANY DEWATERING OF SEDIMENT CONTAINMENT DEVICES FOR MAINTENANCE, REMOVAL OR CONVERSION PURPOSES IS TO BE DONE THROUGH A SILT BAG.
- ALL SEEDED AREAS WILL BE FERTILIZED, RESEDED AS NECESSARY AND MULCHED ACCORDING TO SPECIFICATIONS IN THE VEGETATIVE PLAN TO MAINTAIN A VIGOROUS, DENSE VEGETATIVE COVER.
- SEE NCDQW SEDIMENTATION AND EROSION CONTROL PLANNING AND DESIGN MANUAL FOR FURTHER INSTALLATION/MAINTENANCE INSTRUCTIONS.

PERMITTING OF LAND DISTURBING ACTIVITY

IF THE SAME PERSON CONDUCTS THE LAND DISTURBING ACTIVITY & ANY RELATED BORROW OR WASTE ACTIVITY, THE RELATED BORROW OR WASTE ACTIVITY SHALL CONSTITUTE PART OF THE LAND-DISTURBING ACTIVITY UNLESS THE BORROW OR WASTE ACTIVITY IS REGULATED UNDER THE MINING ACT OF 1971, OR IS A LANDFILL REGULATED BY THE DIVISION OF WASTE MANAGEMENT. IF THE LAND-DISTURBING ACTIVITY AND ANY RELATED BORROW OR WASTE ACTIVITY ARE NOT CONDUCTED BY THE SAME PERSON, THEY SHALL BE CONSIDERED SEPARATE LAND-DISTURBING ACTIVITIES AND MUST BE PERMITTED EITHER THROUGH THE SEDIMENTATION POLLUTION CONTROL ACT AS A ONE-USE BORROW SITE OR THROUGH THE MINING ACT.

SELF-INSPECTION REQUIREMENTS

THE SEDIMENTATION POLLUTION CONTROL ACT WAS AMENDED IN 2006 TO REQUIRE THAT PERSONS RESPONSIBLE FOR LAND-DISTURBING ACTIVITIES INSPECT A PROJECT AFTER EACH PHASE OF THE PROJECT TO MAKE SURE THAT THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN IS BEING FOLLOWED. RULES DETAILING THE DOCUMENTATION OF THESE INSPECTIONS BECAME EFFECTIVE OCTOBER 1, 2010. TO SIMPLIFY DOCUMENTATION OF SELF-INSPECTION REPORTS AND NPDES SELF-MONITORING REPORTS, A COMBINED FORM IS NOW AVAILABLE. THE NEW FORM WAS DEVELOPED TO SATISFY THE REQUIREMENTS OF THE SEDIMENTATION POLLUTION CONTROL ACT AND THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES, NCG 010000.

BEGINNING AUGUST 1, 2013, THE DIVISION OF ENERGY, MINERAL, AND LAND RESOURCES IS RESPONSIBLE FOR ADMINISTERING BOTH THE SPCA AND THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES, NCG 010000. THE COMBINED FORM SHOULD MAKE IT EASIER TO COMPLY WITH SELF-INSPECTION REQUIREMENTS.

THE COMBINED SELF-MONITORING FORM IS AVAILABLE AS A PDF AND WORD DOCUMENT FROM THE LAND QUALITY WEBSITE: [HTTPS://DEQ.NC.GOV/ABOUT/DIVISIONS/ENERGY-MINERAL-LAND-RESOURCES/EROSION-SEDIMENT-CONTROL/FORMS](https://deq.nc.gov/about/divisions/energy-mineral-land-resources/erosion-sediment-control/forms)

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

EFFECTIVE: 04/01/19

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SELF-INSPECTION
 Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In the event of equal or greater rain of 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&S Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, and 6. Date and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indicators of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Visible sedimentation found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Record of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.
(6) Ground stabilization measures	After each phase of grading	1. The phase of grading (installation of perimeter E&S measures, clearing and grubbing, installation of storm drainage facilities, completion of all land disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION B: RECORDKEEPING
1. E&S Plan Documentation
 The approved E&S plan as well as any approved deviation shall be kept on the site. The approved E&S plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&S plan shall be kept on site and available for inspection at all times during normal business hours.

Item to Document	Documentation Requirements
(a) Each E&S measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&S plan.	Initial and date each E&S measure on a copy of the approved E&S plan or complete, date and sign an inspection report that lists each E&S measure shown on the approved E&S plan. This documentation is required upon the initial installation of the E&S measures or if the E&S measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&S plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&S plan.	Initial and date a copy of the approved E&S plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&S measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&S measures.	Initial and date a copy of the approved E&S plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

2. Additional Documentation to be Kept on Site
 In addition to the E&S plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- This General Permit as well as the Certificate of Coverage, after it is received.
- Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

3. Documentation to be Retained for Three Years
 All data used to complete the e-NOTI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION C: REPORTING

1. Occurrences that Must be Reported
 Permittees shall report the following occurrences:

- Visible sediment deposition in a stream or wetland.
- Oil spills is:
 - They are 25 gallons or more,
 - They are less than 25 gallons but cannot be cleaned up within 24 hours,
 - They are shown on surface waters (regardless of volume), or
 - They are within 100 feet of surface waters (regardless of volume).
- Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 113.0 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.
- Anticipated bypasses and unanticipated bypasses.
- Noncompliance with the conditions of this permit that may endanger health or the environment.

2. Reporting Timeframes and Other Requirements
 After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.

Occurrence	Reporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment deposition in a stream or wetland	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions.
(b) Oil spills and release of hazardous substances per Item 1(b)-(c) above	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.
(c) Anticipated bypasses [40 CFR 122.41(m)(3)]	<ul style="list-style-type: none"> A report at least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and effect of the bypass.
(d) Unanticipated bypasses [40 CFR 122.41(m)(3)]	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass.
(e) Noncompliance with the conditions of this permit that may endanger health or the environment [40 CFR 122.41(l)(7)]	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that contains a description of the noncompliance, and its causes, the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue, and steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance. [40 CFR 122.41(l)(6)]. Division staff may waive the requirement for a written report on a case-by-case basis.

PART II, SECTION G, ITEM (4) DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- The E&S plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&S plan authority has approved these items.
- The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit.
- Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems.
- Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above.
- Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
- Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

REVISIONS
 TOWN OF ZEBULON
 NORTH CAROLINA
 ZEBULON MAINTENANCE YARD EXPANSION
 DETAILS
 Wooten
 120 North Boylan Avenue • Raleigh, NC 27603-1423
 (919) 628-0531 • thewootencompany.com
 License Number: F-0115
 ISSUED FOR:
 PERMITTING
 DATE: 1/26/2024
 DESIGNED BY: AMW
 DRAWN BY: THR
 CHECKED BY: AMW
 PROJECT NO.: 2922-5
 C-6.02

PHASED EROSION CONTROL SEQUENCE

1. POST SEDIMENTATION & EROSION CONTROL APPROVAL AT A CONSPICUOUS LOCATION AT THE PROJECT SITE.
2. CALL DEMLR AT THE FAYETTEVILLE REGIONAL OFFICE AT 910-433-3300 TO SCHEDULE A PRE-CONSTRUCTION MEETING AT LEAST 48 HOURS PRIOR TO PROJECT ACTIVATION.
3. CONSTRUCTION ACTIVITIES THAT HAVE AN E&SC PLAN APPROVED ON OR AFTER APRIL 1, 2019 ARE REQUIRED TO FILL OUT AND SUBMIT AN ELECTRONIC NOTICE OF INTENT (E-NOT) FORM. ALL CONSTRUCTION ACTIVITIES ARE REQUIRED TO FOLLOW THE NEW NCGO1 PERMIT REGARDLESS OF WHEN THEY ARE APPROVED.
4. EROSION AND SEDIMENT CONTROL (E&SC) PERMIT AND A CERTIFICATE OF COVERAGE (COC) MUST BE OBTAINED BEFORE ANY LAND DISTURBING ACTIVITIES OCCUR.
5. IN ADDITION TO THE REQUIREMENTS OF THIS PLAN AND OUTLINED IN THE PROJECT SPECIFICATIONS, THE CONTRACTOR SHALL ADHERE TO THE LATEST NCDQ SEDIMENTATION AND EROSION CONTROL MANUAL FOR GUIDANCE ON CONSTRUCTION OF MEASURES REQUIRED BY THIS PLAN. CONTRACTOR SHALL ALSO ADHERE TO THE SELF INSPECTION AND SELF REPORTING AND NPDES AS REQUIRED UNDER THE SEDIMENTATION POLLUTION CONTROL ACT AND NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES, NCG 01000. SEE PLAN SHEET.
6. A RAIN GAUGE WILL BE INSTALLED ON THE SITE, AND A WRITTEN RECORD OF DAILY RAINFALL AMOUNTS SHALL BE RETAINED AND MADE AVAILABLE TO DIVISION OF WATER QUALITY UPON REQUEST. AN APPROVED COPY OF THE E&SC PLAN WITH PLACARD & APPROVAL LETTER, AN APPROVED COPY OF NPDES PERMIT WITH A MINIMUM OF 30 DAYS OF SELF-INSPECTION REPORTS ARE TO BE KEPT ON SITE UNTIL PROJECT CLOSURE.

CONSTRUCTION PHASE 1

1. EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE INSTALLED AT ANY AREAS USED FOR CONTRACTOR EQUIPMENT STAGING, MATERIALS LAYDOWN, SPOIL, OR WASTE AREAS.
2. INSTALL ALL PERIMETER CONTROLS, SEDIMENT BASINS, DIVERSION DITCHES WITH CHECK DAMS/WATTLES AND OUTLET PROTECTION AS INDICATED ON THE DRAWINGS.
3. ONCE THE TEMPORARY MEASURES HAVE BEEN INSTALLED, CONTACT THE STATE EROSION CONTROL FIELD ENGINEER REPRESENTATIVE TO REQUEST INSPECTION OF INSTALLED MEASURES PRIOR TO CONSTRUCTION OF BUILDINGS, PARKING SPACES AND INSTALLATION OF UTILITIES.
4. AFTER THE STATE HAS CONDUCTED AN INSPECTION AND PROVIDED AN AUTHORIZATION TO PROCEED, THE REMAINING WORK MAY BEGIN.
5. GRADE DIVERSION DITCHES.

CONSTRUCTION PHASE 2

1. ANY DEWATERING FOR ESC MAINTENANCE OR UTILITY/STORM TRENCHING TO BE DONE THROUGH A SILT BAG.
2. ALL DITCHES WILL BE LINED TO THE TOP OF BANK.
3. BEGIN MASS GRADING OF SITE ENSURING DRAINAGE TO DIVERSION DITCHES AND OR SKIMMER BASIN.
4. BEGIN FINE GRADE.
5. BEGIN GRAVEL PLACEMENT.
6. MAINTAIN EROSION CONTROL DEVICES AS NECESSARY DURING CONSTRUCTION OF THE BUILDING AND INSTALLATION OF UTILITIES. INSPECT DEVICES AFTER EVERY RAINFALL EVENT AND CLEAN BEHIND THE DEVICES WHEN HALF-FULL. REPAIR OR REPLACE ANY MEASURES NOT PERFORMING AS INTENDED.
7. COMPLY WITH THE GROUND STABILIZATION REQUIREMENTS AS PER PLANS AND SPECIFICATIONS. GROUND STABILIZATION WILL BE APPLIED WITHIN 14 CALENDAR DAYS FROM LAST LAND DISTURBING ACTIVITY. FOR STEEP SLOPES, THAT AREA MUST BE STABILIZED WITHIN 7 CALENDAR DAYS. FOR CRITICAL AREAS, GROUND STABILIZATION WILL BE APPLIED AT THE END OF THE DAY.
8. PERMANENT GROUND COVER IS REQUIRED FOR ALL DISTURBED AREAS WITHIN 90 CALENDAR DAYS FOLLOWING COMPLETION OF CONSTRUCTION OR DEVELOPMENT. HOWEVER, NPDES GROUND COVER REQUIREMENTS TAKE PRECEDENCE.

CONVERSION OF SKIMMER TO WETLAND

1. REMOVE SKIMMER DEVICE AND BAFFLES, FINE GRADE BASIN TO FINAL GRADE FOR THE STORMWATER WETLAND.
2. INSTALL PLANTINGS AND STABILIZE STORMWATER WETLAND.
3. REQUEST AN INSPECTION BY THE ENGINEER AND CONTACT THE STATE EROSION CONTROL FIELD ENGINEER REPRESENTATIVE TO REQUEST FINAL INSPECTION.
4. REMOVE ALL TEMPORARY MEASURES, AND RE-ESTABLISH GRADES. SEED AND MULCH PER PLANS AND SPECIFICATIONS.
5. WHEN THE PROJECT IS COMPLETE, THE PERMITTEE SHALL CONTACT DEMLR TO CLOSE OUT, VIA INSPECTION REPORT; THE PERMITTEE SHALL VISIT DEQ.NC.GOV /NCGO1 TO SUBMIT AN ELECTRONIC NOTICE OF TERMINATION (E-NOT). A \$100 ANNUAL GENERAL PERMIT FEE WILL BE CHARGED UNTIL THE E-NOT HAS BEEN FILLED OUT.

EROSION CONTROL MAINTENANCE NOTES:

RIPRAP OUTLET PROTECTION

IN GENERAL, ONCE A RIPRAP INSTALLATION HAS BEEN PROPERLY DESIGNED AND INSTALLED IT REQUIRES VERY LITTLE MAINTENANCE. RIPRAP SHOULD BE INSPECTED PERIODICALLY FOR SCOUR OR DISLODGED STONES. CONTROL OF WEED AND BRUSH GROWTH MAY BE NEEDED IN SOME LOCATIONS.

CONSTRUCTION ENTRANCE

MAINTAIN THE GRAVEL PAD IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. THIS MAY REQUIRE PERIODIC TOPDRESSING WITH 2-INCH STONE. AFTER EACH RAINFALL, INSPECT ANY STRUCTURE USED TO TRAP SEDIMENT AND CLEAN IT OUT AS NECESSARY. IMMEDIATELY REMOVE ALL OBJECTIONABLE MATERIALS SPILLED, WASHED, OR TRACKED ONTO PUBLIC ROADWAYS.

INLET PROTECTION

INSPECT ROCK PIPE INLET PROTECTION AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (½ INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE SEDIMENT STORAGE AREA TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ONE-HALF THE DESIGN DEPTH OF THE TRAP. PLACE THE SEDIMENT THAT IS REMOVED IN THE DESIGNATED DISPOSAL AREA AND REPLACE THE CONTAMINATED PART OF THE GRAVEL FACING.

CHECK THE STRUCTURE FOR DAMAGE. ANY RIPRAP DISPLACED FROM THE STONE HORSESHOE MUST BE REPLACED IMMEDIATELY. AFTER ALL THE SEDIMENT-PRODUCING AREAS HAVE BEEN PERMANENTLY STABILIZED, REMOVE THE STRUCTURE AND ALL THE UNSTABLE SEDIMENT. SMOOTH THE AREA TO BLEND WITH THE ADJOINING AREAS AND PROVIDE PERMANENT GROUND COVER (SURFACE STABILIZATION).

WATTLE/WATTLE BARRIER/COMPOST FILTER SOCK/SILT SOCK

INSPECT COMPOST SOCKS WEEKLY AND AFTER EACH SIGNIFICANT RAINFALL EVENT (1/2 INCH OR GREATER). REMOVE ACCUMULATED SEDIMENT AND ANY DEBRIS. THE COMPOST SOCK MUST BE REPLACED IF CLOGGED OR TORN. IF PONDING BECOMES EXCESSIVE, THE SOCK MAY NEED TO BE REPLACED WITH A LARGER DIAMETER OR A DIFFERENT MEASURE. THE SOCK NEEDS TO BE REINSTALLED IF UNDERMINED OR DISLODGED. THE COMPOST SOCK SHALL BE INSPECTED UNTIL LAND DISTURBANCE IS COMPLETE AND THE AREA ABOVE THE MEASURE HAS BEEN PERMANENTLY STABILIZED.

SILT FENCE

INSPECT TEMPORARY DIVERSIONS ONCE A WEEK AND AFTER EVERY RAINFALL. IMMEDIATELY REMOVE SEDIMENT FROM THE FLOW AREA AND REPAIR THE DIVERSION RIDGE. CAREFULLY CHECK OUTLETS AND MAKE TIMELY REPAIRS AS NEEDED. WHEN THE AREA PROTECTED IS PERMANENTLY STABILIZED, REMOVE THE RIDGE AND THE CHANNEL TO BLEND WITH THE NATURAL GROUND LEVEL AND APPROPRIATELY STABILIZE IT.

ROLLED EROSION CONTROLLED PRODUCTS

1. INSPECT ROLLED EROSION CONTROL PRODUCTS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (1/2 INCH OR GREATER) RAIN FALL EVENT REPAIR IMMEDIATELY.
2. GOOD CONTACT WITH THE GROUND MUST BE MAINTAINED, AND EROSION MUST NOT OCCUR BENEATH THE RECP.
3. ANY AREAS OF THE RECP THAT ARE DAMAGED OR NOT IN CLOSE CONTACT WITH THE GROUND SHALL BE REPAIRED AND STAPLED.
4. IF EROSION OCCURS DUE TO POORLY CONTROLLED DRAINAGE, THE PROBLEM SHALL BE FIXED AND THE ERODED AREA PROTECTED.
5. MONITOR AND REPAIR THE RECP AS NECESSARY UNTIL GROUND COVER IS ESTABLISHED.


DIVERSION DITCH

INSPECT TEMPORARY DIVERSIONS ONCE A WEEK AND AFTER EVERY RAINFALL. IMMEDIATELY REMOVE SEDIMENT FROM THE FLOW AREA AND REPAIR THE DIVERSION RIDGE. CAREFULLY CHECK OUTLETS AND MAKE TIMELY REPAIRS AS NEEDED. WHEN THE AREA PROTECTED IS PERMANENTLY STABILIZED, REMOVE THE RIDGE AND THE CHANNEL TO BLEND WITH THE NATURAL GROUND LEVEL AND APPROPRIATELY STABILIZE IT.

CONTACT PERSON RESPONSIBLE FOR MAINTENANCE:

CHRIS RAY (TOWN OF ZEBULON) 919-269-5285

NA GREEN S-75BN EROSION CONTROL MATTING-OR APPROVED EQUIVALENT



Specification Sheet – BioNet® S75BN™ Erosion Control Blanket

DESCRIPTION


The short-term single net erosion control blanket shall be a machine-produced mat of 100% agricultural straw with a functional longevity of up to 12 months. (NOTE: functional longevity may vary depending upon climatic conditions, soil, geographical location, and elevation). The blanket shall be of consistent thickness with the straw evenly distributed over the entire area of the mat. The blanket shall be covered on the top side with a 100% biodegradable woven natural organic fiber net. The netting shall consist of machine directional strands formed from two intertwined yarns with across directional strands interwoven through the twisted machine strands (commonly referred to as a Leno weave) to form approximate 0.50 x 1.0 in. (1.27 x 2.54 cm) mesh. The blanket shall be sewn together on 1.50 inch (3.81 cm) centers with degradable thread. The blanket shall be manufactured with a colored thread stitched along both outer edges (approximately 2-5 inches [5-12.5 cm] from the edge) as an overlap guide for adjacent mats.

The S75BN shall meet Type 2 C specification requirements established by the Erosion Control Technology Council (ECTC) and Federal Highway Administration's (FHWA) FP-03 Section 713.17.

Index Property	Test Method	Typical
Thickness	ASTM D6525	0.29 in. (7.37 mm)
Resiliency	ECTC Guidelines	81.4%
Water Absorbency	ASTM D1117	440%
Mass/Unit Area	ASTM D6475	9.12 oz/sy (210 g/sqm)
Swell	ECTC Guidelines	15.7%
Smolder Resistance	ECTC Guidelines	Yes
Stiffness	ASTM D1388	6.92 oz-in
Light Penetration	ASTM D6567	9.1%
Tensile Strength - MD	ASTM D6818	146.4 lbs/ft (2.17 kN/m)
Elongation - MD	ASTM D6818	10.9%
Tensile Strength - TD	ASTM D6818	109.2 lbs/ft (1.62 kN/m)
Elongation - TD	ASTM D6818	14.3%
Biomass Improvement	ASTM D7322	398%

Material Content	Slope Design Data: C Factors
Matrix: 100% straw fiber (0.5 lbs/sq yd (0.27 kg/sqm))	Slope Gradients (S)
Netting: Top side only, Leno woven 100% biodegradable natural organic fiber (4.5 kg/100 sm)	Slope Length (L)
Thread: Biodegradable	≤ 3:1: 3:1 – 2:1: ≥ 2:1
	≤ 20 ft (6 m): 0.029: N/A: N/A
	20-50 ft: 0.11: N/A: N/A
	≥ 50 ft (15.2 m): 0.19: N/A: N/A
	Roughness Coefficients – Unveg.
	Flow Depth
	≤ 0.50 ft (0.15 m): 0.055
	0.50 – 2.0 ft: 0.055-0.021
	≥ 2.0 ft (0.60 m): 0.021

Standard Roll Size	Design Permissible Shear Stress
Width: 6.67 ft (2.0 m)	Unvegetated Shear Stress: 1.60 psf (76 Pa)
Length: 108 ft (32.92 m)	Unvegetated Velocity: 5.00 fps (1.52 m/s)
Weight ± 10%: 46.4 lbs (21.05 kg)	
Area: 80 sq yd (66.9 sm)	



North American Green
5401 St. Wendel-Lynthiana Road
Poseyville, Indiana 47633
na-green.com
800-772-2140

©2007 North American Green is a registered trademark. Certain products and/or applications described or illustrated herein are protected under one or more U.S. patents. Other U.S. patents are pending, and certain foreign patents and patent applications may also exist. Trademark rights also apply, as indicated herein. Final determination of the suitability of any information or material for the uses contemplated, and the manner of use, is the sole responsibility of the user. Printed in the U.S.A.

EC_RM_X_MPDS_B575BN_6-13

T:\Standards\CADD\Civil3D\01_Templates\TWC-Civil_Titleblock_24x36.dwg EMORRISON 6/21/2021 1:34 PM

REVISIONS

Wooten
120 North Boylan Avenue • Raleigh, NC 27603-1423
(919) 828-0531 • thewootencompany.com
License Number: F-0115

NORTH CAROLINA

TOWN OF ZEBULON

ZEBULON

ZEBULON MAINTENANCE YARD EXPANSION

DETAILS

FINAL DRAWING NOT RELEASED FOR CONSTRUCTION



ISSUED FOR:

PERMITTING

DATE: 1/26/2024

DESIGNED BY: **AMW**
DRAWN BY: **THR**
CHECKED BY: **AMW**
PROJECT NO.: **2922-S**

C-6.03