LITTLE RIVER PARK - PHASE I

1800 WEST GANNON AVENUE ZEBULON, NC 27597

CONSULTANTS

LANDSCAPE ARCHITECT



www.benesch.com Corp. NC License: F-1320

CIVIL ENGINEER



Alfred Benesch & Company 8000 Regency Parkway, Suite 175 Cary, NC 27518 www.benesch.com P 984.275.2490

Corp. NC License: F-1320

ATTENTION CONTRACTORS

The Contractor responsible for the extension of water, sewer, and/or reuse, as approved in these plans, is responsible for contacting the Raleigh Water Inspector at 919-996-3245 or https://cityworks.raleighnc.gov/pucontractors and schedule a Pre-construction meeting prior to beginning any construction. Raleigh Water must be contacted at (919) 996-4540 at least twenty-four hours prior to beginning any work activity around

Failure to notify City Departments in advance of beginning construction, will result in the issuance of monetary fines, and require re-installation of any water or sewer facilities not inspected

critical water and sewer infrastructure.

as a result of this notification failure.

future work in the City of Raleigh.

ELECTRICAL ENGINEER



RALEIGH WATER INSPECTIONS QU	JANTITIES (SUBDIVI	SIONS AND SITE F	PLANS) JAN2025M
Phase Number(s)	PHASE 1	PHASE 2	PHASE 3
Number of Lot(s)	N/A	_	_
Number of Units	N/A		_
Public Water (LF)	±461		
Public Sewer (LF)	±386		
Public Force Main (LF)	N/A	_	_
Private Sewer* (LF)	N/A	_	_
Water Service Stubs (Quantity)	1	_	_
Sewer Service Stubs (Quantity)	1		
Average Daily Flow per Phase**	1500 gal/day	_	_
COMMERCIAL PROJECTS WITH SING	GLE WATER AND SEV	WER SERVICE	
Fire Service (Size)	N/A		
Domestic Meter Size	1.5″	_	_
Irrigation Meter Size	N/A		
Average Daily Flow per Phase**	1500 gal/day		_

*Sewer mains and manholes as part of a collection system. **Entire Project Flow. Based on 75gpd per bedroom for residential (apartments, single family dwelling, townhouse, condos), or based on 15A NCAC 02T .0114 Wastewater Design Flow Rates for Commercial and Industrial. The meter size must match domestic service size (exemption -3/4" service tap with 5/8" meter).


Failure to call for inspection, install a downstream plug, have permitted plans on the jobsite, or any other violation of Raleigh Water Standards will result in a fine and possible exclusion from

IMPERVIOUS CALCULATIONS

EXISTING IMPERVIOUS:	12,492 SF
EXISTING IMPERVIOUS TO REMAIN:	7,438 SF
PROPOSED IMPERVIOUS:	60,804 SF
TOTAL SITE IMPERVIOUS:	68,242 SF

(REFER TO SHEETS BUA-1 AND BUA-2 FOR A MORE IN DEPTH BREAKDOWN OF EXISTING AND PROPOSED IMPERVIOUS)





VICINITY MAP

	SHEET INDEX				
SHEET NUMBER	SHEET TITLE				
	COVER SHEET				
C0.10	SURVEY				
C1.00	OVERALL EXISTING CONDITIONS DEMOLITION PLAN				
C1.01	ENLARGED EXISTING CONDITIONS DEMOLITION PLAN				
C200	OVERALL SITE PLAN				
C201	ENLARGED SITE PLAN				
C300	EROSION CONTROL NOTES AND SEQUENCE				
C301	OVERALL EROSION CONTROL PLAN				
C302	EROSION CONTROL PLAN PHASE I				
C302-I	EROSION CONTROL PLAN PHASE 2				
C303	EROSION CONTROL PLAN FINAL PHASE				
C304	OVERALL GRADING PLAN				
C305	GRADING PLAN ENLARGEMENT				
C306	DRIVEWAY PROFILE				
C400	OVERALL UTILITY PLAN				
C401	ENLARGED UTILITY PLAN				
C500	RESTROOM AND SHELTER DETAILS				
C501	SITE CONSTRUCTION DETAILS				
C502	SITE CONSTRUCTION DETAILS				
C503	SITE CONSTRUCTION DETAILS				
C504	SITE CONSTRUCTION DETAILS				
C505	SITE CONSTRUCTION DETAILS				
C600	OVERALL LANDSCAPE PLAN				
C601	LANDSCAPE PLAN				
C700	SITE LIGHTING PLAN				

ELECTRICAL LEGEND AND NOTES

ELECTRICAL FLOOR PLAN AND RISER

ELECTRICAL SITE PLAN

ELECTRICAL

EROS	SION CONTROL, STORMWATER
AND	FLOODPLAIN MANAGEMENT
APP	PROVED
ERO	SION CONTROL SEC
STO	RMWATER MGMT.□SWF
FLO	OD STUDY SWF-
DAT	E
WAKE	ENLURON MENTAL CONQUESTANT CICNATURE
NORTH CAROLINA EFFECTIVE: 08/23/17	ENVIRONMENTAL CONSULTANT SIGNATURE

Issued for Bid

DATE OF ISSUE: 11/20/2025 SET NO.:

SURVEYOR AND IS TO BE USED ONLY FOR CONVEYANCE OF THIS LOT BY THE PERSON(S) SHOWN ON THIS MAP.

WITNESS MY ORIGINAL SIGNATURE,

SURVEYOR: MICHAEL S STOKES

LICENSE # L-4996

REGISTRATION NUMBER AND SEAL THIS 30TH DAY OF SEPTEMBER, A.D. 2024.

Project No: 1725-500672.00 11.20.2025 Revisions:

Prepared for:

TOWN OF ZEBULON

STATE: NORTH CAROLINA

PIN: 1795-14-5894

PIN: 1795-25-4279

DATE: 09-30-2024

SURVEYING & MAPPING, PLLC

Firm License # P-1139


1425-105 B Rock Quarry Rd.


Raleigh, NC 27610

(919)-971-7897

www.stokes-surveying.com

SURVEY







Alfred B 2359 Perimeter Pointe



Corp. NC License: F-13

Corp. NC License: F-1320

/ER PARK

LITTLE RIVER
1800 WEST GANNON A

Project No: 1725-500672.00

Date: 11.20.2025

Revisions:

Sheet Title:

OVERALL
EXISTING
CONDITIONS
DEMOLITION
PLAN
Sheet No:

C1.00





Corp. NC License: F-1320

Project No: 1725-500672.00 11.20.2025

Sheet Title:

ENLARGED EXISTING CONDITIONS DEMOLITION PLAN





Corp. NC License: F-1320

Project No: 1725-500672.00 11.20.2025


Revisions:

Sheet Title:

OVERALL SITE PLAN

Sheet No: C200

SCALE: 1"=60'



Seals:



Corp. NC License: F-1320

Project No: 1725-500672.00 11.20.2025

Sheet Title:

ENLARGED SITE PLAN

1B. ALL OTHER DISTURBED AREAS SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN 14 CALENDAR DAYS FROM THE LAST LAND-DISTURBING

2. CONDITIONS - IN MEETING THE STABILIZATION REQUIREMENTS ABOVE. THE FOLLOWING CONDITIONS OR EXEMPTIONS

SHALL APPLY: 2A. EXTENSIONS OF TIME MAY BE APPROVED BY THE PERMITTING AUTHORITY BASED ON WEATHER OR OTHER

SITE-SPECIFIC CONDITIONS THAT MAKE COMPLIANCE IMPRACTICABLE.

2B. ALL SLOPES 50' IN LENGTH OR GREATER SHALL APPLY THE GROUND COVER WITHIN 7 DAYS EXCEPT WHEN THE SLOPE IS FLATTER THAN 4:1. SLOPES LESS THAN 50' SHALL APPLY GROUND COVER WITHIN 14 DAYS EXCEPT WHEN SLOPES ARE STEEPER THAN 3:1, THE 7 DAY REQUIREMENT APPLIES.

2C. ANY SLOPED AREA FLATTER THAN 4:1 SHALL BE EXEMPT FROM THE 7 DAY GROUND COVER REQUIREMENT.

THE SLOPE IS STEEPER THAN 2:1. 2E. FOR PORTIONS OF PROJECTS WITHIN THE SEDIMENT CONTROL COMMISSION-DEFINED HIGH QUALITY WATER ZONE

2D. SLOPES 10' OR LESS IN LENGTH SHALL BE EXEMPT FROM THE 7 DAY GROUND COVER REQUIREMENT EXCEPT WHEN

ADDITIONAL MEASURES TO CONTROL EROSION AND SEDIMENT MAY BE REQUIRED BY A REPRESENTATIVE OF NCDEQ STAFF. ANY LAND-DISTURBING ACTIVITY >1 ACRE REQUIRES COMPLIANCE WITH ALL CONDITIONS OF THE GENERAL PERMIT TO DISCHARGE STORM WATER UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (PERMIT NO.NCG010000). ANY PERMIT NONCOMPLIANCE IS A VIOLATION OF THE CLEAN WATER ACT AND MAY REQUIRE

(15A NCAC 04A, 0105), STABILIZATION WITH GROUND COVER SHALL BE ACHIEVED AS SOON AS PRACTICABLE BUT IN ANY

EVENT ON ALL AREAS OF THE SITE WITHIN 7 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACT.

4. DISTURBED AREAS DRAINING GREATER THAN ONE ACRE MUST HAVE AN EROSION CONTROL MEASURE THAT DRAINS FROM THE WATER SURFACE ELEVATION.

REQUIRED ARMY CORPS 404 PERMIT AND WATER QUALITY 401 CERTIFICATION MUST BE OBTAINED FOR STREAM **DISTURBANCES OVER 150 LINEAR FEET.**

6. ANY BORROW OR WASTE MATERIAL SHALL BE TAKEN/PLACED ON A SITE THAT HAS AN ACTIVE APPROVED GRADING PERMIT. IF THIS IS NOT OBTAINABLE, THEN CONTRACTOR MAY SUBMIT PLAN FOR APPROVAL TO NCDEQ PRIOR TO ANY OFF-SITE BORROW/WASTE AREAS BEING DENUDED AND ANY GRADING OPERATIONS STARTING ON THIS SITE.

7. ANY GRADING BEYOND THE DENUDED LIMITS SHOWN ON THE PLAN IS A VIOLATION OF THE NCDEQ EROSION CONTROL ORDINANCE AND IS SUBJECT TO A FINE. 8. GRADING MORE THAN ONE ACRE WITHOUT AN APPROVED EROSION CONTROL PLAN IS A VIOLATION OF THE NCDEQ

EROSION CONTROL ORDINANCE AND IS SUBJECT TO A FINE. 9. ANY AND ALL SITE FINES IMPOSED BY NCDEQ OR ANY OTHER GOVERNING AGENCY SHALL BE PAID BY THE GRADING

10. SLOPES SHALL BE GRADED NO STEEPER THAN 2:1. FILL SLOPES GREATER THAN 10' REQUIRE ADEQUATE TERRACING.

11. SOIL TYPES: - RgC - Rawlings-Rion complex, 10 TO 15 PERCENT SLOPES WaB - Wake-Rolesvill complex, 2 TO 6 PERCENT SLOPES, very rocky WaD - Wake-Rolesvill complex, 10 TO 15 PERCENT SLOPES, very rocky

WgB - Wedeowee-Urban land complex, 2 TO 6 PERCENT SLOPES

12. NAME OF RECEIVING WATER COURSE: LITTLE RIVER

ENFORCEMENT ACTION BY NCDEQ.

14. CLASSIFICATION OF RECEIVING WATER COURSE: CA, HQW, NSW, WS-II

15. RIVER BASIN: NEUSE

13. STREAM INDEX: <u>27-57-(7.5)</u>

DEMOLITION, CONSTRUCTION, AND OTHER WASTES. THESE AREAS ARE TO BE WITHIN THE LIMITS OF DISTURBANCE AND SHOULD BE LOCATED AT LEAST 50 FT AWAY FROM STORM DRAIN INLETS, TEMPORARY DIVERSIONS, CHANNELS, BASINS, AN SURFACE WATER BODIES. ACTIVITY LOCATIONS THAT ARE SHOWN ON THE PLANS MAY BE FIELD ADJUSTED IF THE DISTANCE

16. PROVIDE STOCKPILE / STAGING AREAS, CONCRETE WASHOUTS, EMPLOYEE PARKING, AND DEDICATED AREAS FOR

ALL DISTURBED AREAS WITH GRADED SLOPES AT 3:1 OR STEEPER SHALL RECEIVE THE FOLLOWING EROSION CONTROL BLANKET:

70% STRAW FIBER (.35 LBS/SQ YRD.) 30% COCONUT FIBER (0.15 LBS/SQ. YRD.) NETTING ON BOTH SIDES, LENO WOVEN, 100% BIODEGRADABLE ORGANIC JUTE FIBER, 9.3 LBS./1000 SQ. FT. STAPLE WITH .11 GA, 8" U STAPLES AT 2' O.C. DOWN THE SLOPE AND 1.6' O.C. ACROSS THE SLOPE.

STOCKPILE - SUPER SILT STOCKPILE **FENCE**

> 1. ENSURE STOCKPILE AREA COMPLIES WITH NCDEQ EROSION CONTROL REQUIREMENTS AND FRANKLIN COUNTY NO REQUIREMENTS 2. SOIL STOKPILE AREAS IN PLACE GREATER THAN 7 DAYS REQUIRE SEEDING OR ALTERNATIVE MEANS OF SLOPE STABILIZATION

A-A

TEMPORARY SOIL STOCKPILI

Know what's **below**. Call before you dig.

event ≥ 1.0 inch in

At least once pe

7 calendar days

hours of a rain

At least once pe

and within 24

hours of a rain

At least once per

7 calendar davs

and within 24

hours of a rain

event > 1.0 inch i

After each phase

of grading

event > 1.0 inch in

event ≥ 1.0 inch in

and within 24

discharge

outfalls (SDOs)

(4) Perimeter of

(5) Streams or

or offsite

accessible)

(6) Ground

stabilization

measures

wetlands onsite

SELF-INSPECTION, RECORDKEEPING AND REPORTING

Description of maintenance needs for the measure.

Name of the person performing the inspection.

Indication of visible sediment leaving the site,

. Date and time of the inspection.

of the following shall be made:

the site limits,

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

Description, evidence, and date of corrective actions taken.

Evidence of indicators of stormwater pollution such as oil

Description, evidence, and date of corrective actions taken

If visible sedimentation is found outside site limits, then a record

. Actions taken to clean up or stabilize the sediment that has left

Description, evidence, and date of corrective actions taken, and

3. An explanation as to the actions taken to control future

stream has visible increased turbidity from the construction

ctivity, then a record of the following shall be made:

The phase of grading (installation of perimeter E&SC

drainage facilities, completion of all land-disturbing

activity, construction or redevelopment, permanent

measures have been provided within the required

measures, clearing and grubbing, installation of storm

Documentation that the required ground stabilization

If the stream or wetland has increased visible sedimentation or a

Description, evidence and date of corrective actions taken, and

Regional Office per Part III, Section C, Item (2)(a) of this permit.

Records of the required reports to the appropriate Division

sheen, floating or suspended solids or discoloration

LEGEND

 $+XXX.\lambda$

1._____

EXISTING SIGN

RIGHT-OF-WAY

ACCESSIBLE SPACE

EXISTING TREE TO REMAIN

EXISTING FIRE HYDRANT

EXISTING WATER VALVE

EXISTING WATER METER

EXISTING SEWER MANHOLE

EXISTING STORM MANHOLE

PROPOSED STORM MANHOLE

PROPOSED FLARED END SECTION

EXISTING DRAINAGE STRUCTURE

EXISTING SPOT ELEVATION

PROPOSED SPOT ELEVATION

EXISTING CLEANOUT

EXISTING DOWNSPOUT

TEMPORARY SILT SACK

TEMPORARY INLET PROTECTION

TEMPORARY ROCK CHECK DAM

TEMPORARY FILTER BERM BASIN

TEMPORARY FILTER BAG WITH

FLOATING INTAKE TO SKIMMER

WETLANDS EXTENT

PROPOSED DRAINAGE STRUCTURE

EXISTING IRON PIN

EXISTING LIGHT POLE

EXISTING UTILITY POLE

 $\equiv \equiv \equiv \equiv \equiv \equiv$ Existing curb and gutter

PROPERTY LIN

——x——x—— EXISTING FENCE

PROPOSED CURB AND GUTTER

-----UGE------ EXISTING UNDERGROUND ELECTRIC LINE

EXISTING UNDERGROUND TELEPHONE LINE

-----OH/U----- EXISTING OVERHEAD UTILITY LINE

-----FO/C---- EXISTING FIBER OPTIC LINE

— — XXX — — EXISTING CONTOUR LINE

——XXX—— PROPOSED CONTOUR LINE

PROPOSED TREE LINE

----- STREAM CENTER LINE

——SSF——— SUPER SILT FENCE

→ ★ TEMPORARY SILT FENCE

TEMPORARY TREE PROTECTION

PROPOSED LIMIT OF DISTURBANCE

 \bowtie^{GM}

PROPOSED DRAINAGE DITCH

= == == EXISTING STORM DRAINAGE PIPE

EXISTING TREE LINE

EXISTING GAS METER

(100 YEAR FLOODPLAIN)

TEMPORARY SILT FENCE AND TREE PROTECTION

STONE OPENING IN TEMPORARY SILT FENCE

PROPOSED RIPRAP APRON

FLOOD PRONE SOIL LIMITS

(FUTURE 100 YEAR FLOODPLAIN)

PROPOSED SLOPE AND CHANNEL LINING

PROPOSED STORM DRAINAGE PIPE

PROPOSED ROOF DRAIN PIPE

-----SS----- EXISTING SANITARY SEWER LINE

SECTION B: RECORDKEEPING Self-inspections are required during normal business hours in accordance with the table 1. E&SC Plan Documentation below. When adverse weather or site conditions would cause the safety of the inspection The approved E&SC plan as well as any approved deviation shall be kept on the site. The personnel to be in jeopardy, the inspection may be delayed until the next business day on approved E&SC plan must be kept up-to-date throughout the coverage under this permit. which it is safe to perform the inspection. In addition, when a storm event of equal to or The following items pertaining to the E&SC plan shall be kept on site and available for greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be inspection at all times during normal business hours. performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record. Item to Document **Documentation Requirements** (a) Each E&SC measure has been installed Initial and date each E&SC measure on a copy Inspect Inspection records must include: and does not significantly deviate from the | of the approved E&SC plan or complete, date (during normal business hours) (1) Rain gauge shown on the approved E&SC plan. If no daily rain gauge observations are made during weekend or maintained in holiday periods, and no individual-day rainfall information is good working available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device (b) A phase of grading has been completed. approved by the Division. (2) E&SC Identification of the measures inspected At least once per Measures 7 calendar days . Date and time of the inspection. and within 24 . Name of the person performing the inspection, hours of a rain Indication of whether the measures were operating

locations, dimensions and relative elevations | and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the (c) Ground cover is located and installed Initial and date a copy of the approved E&SC in accordance with the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications. Complete, date and sign an inspection report (d) The maintenance and repair requirements for all E&SC measures have been performed. (e) Corrective actions have been taken Initial and date a copy of the approved E&SC to E&SC measures. plan or complete, date and sign an inspection report to indicate the completion of the corrective action. 2. Additional Documentation to be Kept on Site

In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

(a) This General Permit as well as the Certificate of Coverage, after it is received.

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

(b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

PART II, SECTION G, ITEM (4)

DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

(a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items, (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit,

(c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include

properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems, (d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above,

(e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and (f) Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

SELF-INSPECTION, RECORDKEEPING AND REPORTING SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION C: REPORTING

SELF INSPECTION REQUIREMENTS

ACTIVITIES NCG010000.

GENERAL CONTRACTOR.

MEASURES DEVIATE FROM THE PLANS.

1. SELF-INSPECTIONS WILL BE PERFORMED IN ACCORDANCE WITH THE NPDES GENERAL PERMIT FOR CONSTRUCTION

3. THE DIMENSIONS OF THE BASINS SHALL BE CHECKED AND COMPARED TO THE DIMENSIONS ON THE APPROVED

2. ALL TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES, INCLUDING SEDIMENTATION CONTROL BASINS,

SEDIMENTATION TRAPS. SEDIMENTATION PONDS, ROCK DAMS, TEMPORARY DIVERSIONS, TEMPORARY SLOPE DRAINS,

ROCK CHECK DAMS, SEDIMENT FENCE OR BARRIERS, ALL FORMS OF INLET PROTECTION, STORM DRAINAGE FACILITIES,

ENERGY DISSIPATERS, STABILIZATION METHODS OF OPEN CHANNELS, AND GROUND COVER SHALL BE INSPECTED BY THE

SEDIMENTATION AND EROSION CONTROL PLAN. NOTIFY BENESCH IF THE DIMENSIONS OF ANY OF THE EROSION CONTROL

REPRESENTATIVE COMPLETING THE INSPECTIONS MAY MAKE NOTATIONS ON THE COPY OF THE APPROVED EROSION AND

4. A "SELF-INSPECTION REPORT FORM FOR LAND DISTURBING ACTIVITY" (AS REQUIRED BY NCGS 113A-54.1) IS AVAILABLE ON

SEDIMENTATION CONTROL PLAN THAT IS KEPT ON THE PROJECT SITE. DOCUMENTATION SHALL BE ACCOMPLISHED BY

SEDIMENTATION CONTROL PLAN OR BY COMPLETING, DATING AND SIGNING AN INSPECTION REPORT THAT LISTS EACH

THE NCDEQ WEBSITE OR PROVIDED WITHIN THE PROJECT MANUAL. ALTERNATIVELY THE OWNER OR DESIGNATED

INITIALING AND DATING EACH MEASURE OR PRACTICE SHOWN ON A COPY OF THE APPROVED EROSION AND

5. THE SELF-INSPECTION REPORT IS TO BE COMPLETED AFTER EACH PHASE OF THE APPROVED EROSION AND

DOCUMENTATION AND/OR REPORTS OF INSPECTIONS MUST BE MADE AVAILABLE ON THE SITE.

SEDIMENTATION CONTROL PLAN IS COMPLETE. THESE PHASES APPLY FOR THIS PROJECT:

5.6. ESTABLISHMENT OF PERMANENT GROUND COVER SUFFICIENT TO RESTRAIN EROSION.

ALL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CHECKED FOR STABILITY AND

ONCE EVERY WEEK. ANY NEEDED REPAIRS WILL BE MADE IMMEDIATELY TO MAINTAIN ALL

2. SEDIMENT WILL BE REMOVED FROM THE TEMPORARY SEDIMENT TRAPS WHEN STORAGE

3. SEDIMENT WILL BE REMOVED FROM BEHIND THE SILT FENCE WHEN IT BECOMES ABOUT 0.5

4. THE SEDIMENT FENCE WILL BE REPAIRED AS NECESSARY TO MAINTAIN A BARRIER. THE

OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL, BUT IN NO CASE LESS THAN

CAPACITY HAS BEEN APPROXIMATELY 50% FILLED. GRAVEL WILL BE CLEANED OR REPLACED

ENGINEER MAY DIRECT THAT ADDITIONAL SILT FENCING OR EROSION CONTROL MATTING BE

THE DETAILS INCLUDED IN THESE PLANS UNLESS OTHERWISE DIRECTED BY THE ENGINEER IN

1. PROVIDE 25' EASEMENT AS SHOWN ON THE APPROVED PLAN FOR MAINTENANCE AND ACCESS

4. PROVIDE AND MAINTAIN SUPER SILT FENCE AROUND STOCKPILE FOR POTENTIAL SEDIMENT LOSS.

3. THE APPROVED PLAN SHALL PROVIDE FOR THE USE OF STAGED SEEDING AND MULCHING ON A

4. ESTABLISH AND MAINTAIN A VEGETATIVE BUFFER AT THE TOE OF THE SLOPE (WHERE PRACTICAL).

SEEDING OR COVERING STOCKPILES WITH TARPS OR MULCH IS REQUIRED AND WILL REDUCE EROSION PROBLEMS. TARPS SHOULD BE KEYED IN AT THE TOP OF THE SLOPE TO KEEP WATER FROM RUNNING

IF A STOCKPILE IS TO REMAIN FOR FUTURE USE AFTER THE PROJECT IS COMPLETE (BUILDERS, ETC.), THE

FINANCIAL RESPONSIBLE PARTY MUST NOTIFY WAKE COUNTY OF A NEW RESPONSIBLE PARTY FOR THAT

5. ALL EROSION AND SEDIMENT CONTROL DEVICES SHALL BE INSTALLED IN ACCORDANCE WITH

6. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED ONCE THE ENTIRE

5.1. INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROL MEASURES;

5.2. CLEARING AND GRUBBING OF EXISTING GROUND COVER;

WHEN THE SEDIMENT POOL NO LONGER DRAINS PROPERLY.

INSTALLED AT ANY TIME PRIOR TO FINAL ACCEPTANCE.

2. STOCKPILE HEIGHT SHALL NOT EXCEED 10 FEET.

3. STOCKPILE SLOPES SHALL BE 2:1 OR FLATTER.

STOCKPILE MAINTENANCE

CONTINUAL BASIS WHILE THE STOCKPILE IS IN USE.

UNDERNEATH THE PLASTIC.

5.4. INSTALLATION OF STORM DRAINAGE FACILITIES:

MAINTENANCE PLAN:

PRACTICES AS DESIGN.

FEET DEEP AT THE FENCE.

SITE IS STABILIZED

STOCKPILE NOTES

5.5. COMPLETION OF CONSTRUCTION OR DEVELOPMENT;

5.3. COMPLETION OF ANY PHASE OF GRADING OF SLOPES OR FILLS;

MEASURE, PRACTICE OR DEVICE SHOWN ON THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN. ALL

1. Occurrences that Must be Reported Permittees shall report the following occurrences:

(a) Visible sediment deposition in a stream or wetland.

(b) Oil spills if: They are 25 gallons or more,

environment[40

They are less than 25 gallons but cannot be cleaned up within 24 hours,

 They cause sheen on surface waters (regardless of volume), or They are within 100 feet of surface waters (regardless of volume).

(c) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA

(Ref: 40 CFR 302.4) or G.S. 143-215.85.

(d) Anticipated bypasses and unanticipated bypasses.

(e) Noncompliance with the conditions of this permit that may endanger health or the

2. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.

other requirements listed below. Occurrences outside normal business hours may also be Reporting Timeframes (After Discovery) and Other Requirements (a) Visible sediment • Within 24 hours, an oral or electronic notification. deposition in a Within 7 calendar days, a report that contains a description of the stream or wetland sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. If the stream is named on the NC 303(d) list as impaired for sedimentrelated causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions. (b) Oil spills and Within 24 hours, an oral or electronic notification. The notification release of shall include information about the date, time, nature, volume and hazardous location of the spill or release. 1(b)-(c) above c) Anticipated A report at least ten days before the date of the bypass, if possible bypasses [40 CFR The report shall include an evaluation of the anticipated quality and 122.41(m)(3)] effect of the bypass. (d) Unanticipated Within 24 hours, an oral or electronic notification. bypasses [40 CFR • Within 7 calendar days, a report that includes an evaluation of the 122.41(m)(3)] quality and effect of the bypass (e) Noncompliance • Within 24 hours, an oral or electronic notification. with the conditions • Within 7 calendar days, a report that contains a description of the of this permit that noncompliance, and its causes: the period of noncompliance. may endanger including exact dates and times, and if the noncompliance has not health or the been corrected, the anticipated time noncompliance is expected to

continue; and steps taken or planned to reduce, eliminate, and

Division staff may waive the requirement for a written report on a

prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6).

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT Implementing the details and specifications on this plan sheet will result in the construction

activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

Required Ground Stabilization Timeframes				
Si	te Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations	
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None	
(b)	High Quality Water (HQW) Zones	7	None	
(c)	Slopes steeper than 3:1	7	If slopes are 10' or less in length and ar not steeper than 2:1, 14 days are allowed	
(d)	Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4: -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed	
(e)	Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zo -10 days for Falls Lake Watershed unle there is zero slope	
roui ract	nd stabilization shall be icable but in no case l	oe converted to perma longer than 90 calenda	ction activities, any areas with temporar inent ground stabilization as soon as ar days after the last land disturbing e maintained in a manner to render the	

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the echniques in the table below:

Permanent Stabilization • Temporary grass seed covered with straw or | • Permanent grass seed covered with straw or other mulches and tackifiers • Geotextile fabrics such as permanent soil Rolled erosion control products with or reinforcement matting

without temporary grass seed Hydroseeding Appropriately applied straw or other mulch Shrubs or other permanent plantings covered Plastic sheeting with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or

retaining walls

Rolled erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS Select flocculants that are appropriate for the soils being exposed during

construction, selecting from the NC DWR List of Approved PAMS/Flocculants. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures. Apply flocculants at the concentrations specified in the NC DWR List of Approved *PAMS/Flocculants* and in accordance with the manufacturer's instructions.

Provide ponding area for containment of treated Stormwater before discharging Store flocculants in leak-proof containers that are kept under storm-resistant cover

or surrounded by secondary containment structures.

QUIPMENT AND VEHICLE MAINTENANCE

Maintain vehicles and equipment to prevent discharge of fluids. Provide drip pans under any stored equipment. Identify leaks and repair as soon as feasible, or remove leaking equipment from the

Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible). Remove leaking vehicles and construction equipment from service until the problem

Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products

to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE Never bury or burn waste. Place litter and debris in approved waste containers. Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes. Locate waste containers at least 50 feet away from storm drain inlets and surface

waters unless no other alternatives are reasonably available. Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland. Cover waste containers at the end of each workday and before storm events or

provide secondary containment. Repair or replace damaged waste containers. Anchor all lightweight items in waste containers during times of high winds. Empty waste containers as needed to prevent overflow. Clean up immediately if

containers overflow. Dispose waste off-site at an approved disposal facility. 9. On business days, clean up and dispose of waste in designated waste containers.

waters unless no other alternatives are reasonably available.

PAINT AND OTHER LIQUID WASTE Do not dump paint and other liquid waste into storm drains, streams or wetlands. 2. Locate paint washouts at least 50 feet away from storm drain inlets and surface

Contain liquid wastes in a controlled area. Containment must be labeled, sized and placed appropriately for the needs of site. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot

Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace

offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags. Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas. Monitor portable toilets for leaking and properly dispose of any leaked material.

EARTHEN STOCKPILE MANAGEMENT Show stockpile locations on plans. Locate earthen-material stockpile areas at least

with properly operating unit

50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably

Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile. Provide stable stone access point when feasible.

Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated

erosion on disturbed soils for temporary or permanent control needs.

OTES: ACTUAL LOCATION DETERMINED IN FIELD 2. THE CONCRETE WASHOUT STRUCTURES SHALL BE MAINTAINED WHEN THE LIQUID AND/OR SOLID REACHES 75% OF THE STRUCTURES CAPACITY. 3.CONCRETE WASHOUT STRUCTURE NEEDS TO BE CLEARY MARKED WITH SIGNAGE NOTING DEVICE.

CONCRETE WASHOUTS

. Do not discharge concrete or cement slurry from the site. 2. Dispose of, or recycle settled, hardened concrete residue in accordance with local

and state solid waste regulations and at an approved facility. Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within

lot perimeter silt fence. Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two

types of temporary concrete washouts provided on this detail. Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.

Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.

Locate washouts in an easily accessible area, on level ground and install a stone

entrance pad in front of the washout. Additional controls may be required by the approving authority.

Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.

Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary

products, follow manufacturer's instructions. 10. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

HERBICIDES. PESTICIDES AND RODENTICIDES

Store and apply herbicides, pesticides and rodenticides in accordance with label

Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.

Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately. Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE

Create designated hazardous waste collection areas on-site.

Place hazardous waste containers under cover or in secondary containment. Do not store hazardous chemicals, drums or bagged materials directly on the ground

Sheet No:

Project No: 1725-500672.00

Revisions:

Sheet Title:

EROSION

CONTROL

NOTES AND

SEQUENCE

Seals:

Corp. NC License: F-1320

| EFFECTIVE: 04/01/19

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

EFFECTIVE: 04/01






Corp. NC License: F-1320

Project No: 1725-500672.00 11.20.2025 Revisions:

Sheet Title: **OVERALL EROSION CONTROL PLAN**

C301



MATCHLINE SEE CONTINUATION THIS SHEET
OUTLET (TYP)

Alfred Benesch & Company
Casso Perimeter Pointe Parkway, Suite 350
Charlotte, NC 28208



Seals:



Corp. NC License: F-1320

PARK

1800 WEST GANNON AVENUE

Project No: 1725-500672.00
Date: 11.20.2025

Revisions:

_____ Sheet Title:


EROSION CONTROL PLAN PHASE 1

Sheet No:

Call before you dig

SCALE: 1"=30'

C302



MATCHLINE SEE CONTINUATION THIS SHEET





Corp. NC License: F-1320


Project No: 1725-500672.00 11.20.2025 **Revisions:**

Sheet Title:

EROSION CONTROL PLAN PHASE 2

Sheet No: C302-I

SCALE: 1"=30'



Alfred Benesch & Company
Alfred Parkway, Suite 350
Charlotte, NC 28208
www.benesch.com

Seals:



Corp. NC License: F-1320

LER PARK
INON AVENUE

Project No: 1725-500672.00

Date: 11.20.2025


Revisions:

Sheet Title:

EROSION CONTROL PLAN FINAL PHASE

Sheet No:

C303



Alfred Benesch & Company 2359 Perimeter Pointe Parkway, Suite 350



Seals:



Comp. NC License, F. 12

Corp. NC License: F-1320

1800 WEST GANNON AVENUE


Project No: 1725-500672.00
Date: 11.20.2025

Revisions:

_____ Sheet Title:

OVERALL GRADING PLAN

Sheet No:



DEPTHER BENESCH & Company

Alfred Benesch & Company
2359 Perimeter Pointe Parkway, Suite 350
Charlotte NC 28208



Seals:



Corp. NC License: F-1320

IVER PARK

I GANNON AVENUE


Project No: 1725-500672.00
Date: 11.20.2025


sions:

Sheet Title:

GRADING PLAN ENLARGEMENT

Sheet No:









Seals:


Corp. NC License: F-1320



Sheet Title:

DRIVEWAY PROFILE





Project No: 1725-500672.00

Date:

Revisions:


11.20.2025

Seals:

Corp. NC License: F-1320

OVERALL UTILITY **PLAN**

C400



WATER METER



Corp. NC License: F-1320


Project No: 1725-500672.00 Revisions:

Sheet Title:

ENLARGED UTILITY **PLAN**

Sheet No: C401

Know what's **below. Call** before you dig.










Corp. NC License: F-1320

Project No: 1725-500672.00 11.20.2025 Date: Revisions:


Sheet Title:

RESTROOM AND SHELTER **DETAILS**

Sheet No: C500







Seals:



Corp. NC License: F-1320

Project No: 1725-500672.00 11.20.2025 Revisions:

Sheet Title:

SITE **CONSTRUCTION DETAILS**

Project No: 1725-500672.00 11.20.2025

Revisions:

Effective Date: 9/1/202

In accordance with the 2013 Design Manual Updates

SC250 OR 9

RIPRAP S150

Provide transverse(contraction) joints to control cracking at approximately 20-fe


 Install expansion joints at intervals not to exceed 100 feet. 4. Rock riprap linings should be installed per the standards and specifications outlined on following sheets. 5 Place filters, bedding's, and foundation drains to line and grade in the manner specified. Place filter and bedding materials immediately after slope preparation. every 3 feet along the overlap. required, spread the layers so there is minimal mixing.

6. For synthetic filter fabrics, overlap the downstream edge by at least 12 inches with the upstream edge which is buried a minimum 12 inches in a trench. Space anchor pins Spread granular materials in a uniform layer. When more than one gradation is

where concentrated flow enters. or bank failures. Make any repairs immediately.

➤ FILTER LAYER, GRAVEL OR FABRIC RIPRAP AND PAVED CHANNELS

RIPRAP CHANNELS



4" Sch 40 coupling connection to 3" Head (distance from center of inlet to water surface). 3" Inlet extension.

3" SKIMMER

25% OF SURFACE AREA PERSPECTIVE VIEW CONSTRUCTION SPECIFICATION 1. GRADE THE BASIN SO THAT THE BOTTOM IS LEVEL FRONT TO BACK AND SIDE TO SIDE.

FIRST CHAMBER —

SECOND CHAMBER -

25% OF SURFACE AREA

– INLET ZONE –

25% OF SURFACE AREA

25% OF SURFACE AREA

- COIR EROSION

ANCHOR MATERIAL IN 4"

WITH COMPACTED FILL

BAFFLE DETAIL

WIDE BY 8" DEEP TRENCH

FABRIC

2. INSTALL POSTS ACROSS THE WIDTH OF THE SEDIMENT TRAP, SEDIMENT BASIN AND/OR SKIMMER BASIN AS SHOWN. 3. STEEL POSTS SHOULD BE DRIVEN TO A DEPTH OF 24 INCHES, SPACED A MAXIMUM OF 4 FEET APART, AND INSTALLED UP THE SIDES OF THE BASIN AS WELL. THE TOP OF THE FABRIC SHOULD BE 6 INCHES HIGHER THAN THE INVERT OF THE SPILLWAY. TOPS OF BAFFLES SHOULD BE 2 INCHES LOWER THAN THE TOP OF THE BERMS.

4. BAFFLE MATERIAL SHALL BE 700 G/M2 COIR EROSION FABRIC

TEMPORARY POROUS BAFFLE

5. INSTALL AT LEAST THREE ROWS OF BAFFLES BETWEEN THE INLET AND OUTLET DISCHARGE POINT. BASINS LESS THAN 20 FEET IN LENGTH MAY USE 2 BAFFLES THAT DIVIDES THE BASIN IN THIRDS. 6. ADD A SUPPORT WIRE OR ROPE ACROSS THE TOP OF THE MEASURE TO PREVENT SAGGING. 7. WRAP BAFFLE MATERIAL OVER THE TOP WIRE. ATTACH FABRIC TO A ROPE AND A SUPPORT STRUCTURE WITH ZIP TIES, WIRE, OR STAPLES. USE 3 TIES PER POST ALL WITHIN TOP 8" OF

8. THE BOTTOM AND SIDES OF THE FABRIC SHOULD BE ANCHORED IN A TRENCH 8" DEEP. IN LIEU OF EXCAVATING A TRENCH, THE FABRIC MAY BE INSTALLED WITH A PIECE OF EQUIPMENT SPECIFICALLY DESIGNED TO SLICE THE GROUND WITH A DISC

9. DO NOT SPLICE THE FABRIC, BUT USE A CONTINUOUS PIECE ACROSS THE BASIN.

MAINTENANCE INSPECT BAFFLES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.

 BE SURE TO MAINTAIN ACCESS TO THE BAFFLES. SHOULD THE FABRIC OF A BAFFLE COLLAPSE, TEAR, DECOMPOSE, OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY.

 REMOVE SEDIMENT DEPOSITS WHEN IT REACHES HALF FULL TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE BAFFLES. TAKE CARE TO AVOID DAMAGING THE BAFFLES DURING CLEANOUT. SEDIMENT DEPTH SHOULD NEVER EXCEED HALF THE DESIGNED STORAGE DEPTH.

> **TACKING RATES** NCDEQ STANDARD 6.14

 Select material based on site and practice requirements, availability of material, labor and equipment on complete grading, install sediment control practices, and prepare the seedbed. Apply seed before mulching except when seed is applied as part of a hydroseeder slurry containing wood fiber mulch or a hydroseeder slurry is applied over straw.
 APPLICATION OF ORGANIC MULCH

 Spread mulch uniformly by hand, or with a mulch blower.
 When spreading straw mulch by hand, divide the area to be mulched into sections of approximately 1,000 ft², and place 70-90 lb. of straw(1 1/2 to 2 bales) in each section to facilitate uniform distribution.
 After Spreading, no more than 25% of the ground surface should be visible.
 In bydrosecting onegrations a green dive added to the slurry, assures a uniform application. unweathered; avoid weeds. nitrogen/ton. Apply with mulch blower, chip handle, or by hand. Not for use in 4.In hydroseeding operations a green dye, added to the slurry, assures a uniform application. ANCHORING ORGANIC MULCH Wood Chips 5-6 tons Straw mulch must be anchored immediately after spreading
 A tractor-drawn implement designed to bunch mulch into the 2. A tractor-drawn implement designed to punch mulch into the soil or a mulch anchoring tool provides maximum erosion control with straw. A regular farm disk, weighted and set nearly straight, may substitute, but will not do a job comparable to the mulch anchoring tool. The disk should not be sharp enough to cut the straw. These methods are limited to slopes no steeper than 3:1, where equipment can operate safely.
3. Application of liquid mulch binders and tackifiers should be heaviest at the edges of areas and at crests of ridges and banks, to resist winds. Binder should be applied uniformly to the rest of the area. Binders may be applied after mulch is spread, or may be sprayed into the mulch as it is being blown onto the soil. Applying straw and binder together is the most effective method.
4. Emulsified asphalt should be applied at 0.10 gallons per square yard (10 gall1,000 ft²). Heavier applications cause straw to "perch" over rills. Use Rapid setting (RS or CRS) designated asphalt in traffic areas to prevent uncured asphalt from being picked up on shoes and causing damage to russ clothes etc. cellulose. May be Wood Fiber 0.5-1 tons 35 cubic yards or hammer-milled, chip handler, or by hand. Do or chips. not use asphalt tack.

Cut or shredded in 4-6 inch lengths.

Out or shredded in 4-6 inch lengths. shoes and causing damage to rugs, clothes, etc.

5. Synthetic binders may be used as recommended by the manufacturer. Corn Stalks 4-6 tons 6. Lightweight plastic, cotton, jute, wire or paper nets may be stapled over the mulch according to the m For small areas where other methods cannot be used, peg and twine anchoring can be used. Drive 8-10 inch wooden pegs to within a inches of the soil surface, every 4 feet in all directions. Stakes can be driven before or after straw is spread. Secure mulch by 1-3 tons seed-bearing stems O. Nye Grain may be used to a licitor initiat in rain plantings, and German white in spining, broadcast at 15 bradie before applying indic CHEMICAL MULCHES
 May be effective for soil stabilization if used between May 1 and June 15, or Sept. 15 and Oct. 15, provided that they are used on slopes no steeper than 4:1, and that proper seedbed preparation has been accomplished, including surface roughening where required. Jute net Cover area woven of single when used with organic when used with organic
2. Chemical mulches cannot be used to bind other mulches, or with wood fiber in a hydroseeded slurry at any time. Follow the Fiberglass net Cover area Excelsior (wood fiber net) Cover area Continuous fibers ufacturer's recommendations for application. Withstands waterflow. FIBERGLASS ROVING

1. Spread roving uniformly over the area at a rate of 0.25 to 0.35 lb/yd². Anchor with asphalt immediately after application, at a rate of 0.25-0.35 gal/yd² Fiberglass roving

0.5-1 tons

Continuous fibers of drawn glass bound together ejector. Tack with emulsified . As a channel lining, and at other sites of concentrated flow, the roving mat must be further anchored to prevent undermining. may be secured with stakes placed at intervals no greater than 10 feet along the drainageway, and randomly throughout its width, ut not more than 10 feet apart.

Is an option to staking, the roving can be buried to a depth of 5 inches at the upgrade end and at intervals of 50 feet along the length gal/1,000 sq. ft. Chemical Stabilizers Aquatain Aerospray Not beneficial to plant growth

Dry, unchopped,

1-2 tons

oats; spread by hand or

4" SKIMMER

ests alone generally provide little moisture conservation benefits and only limited erosion protection. Therefore, typically use in conjunction with an organic mulch such as straw.

2. Except when wood fiber slurry is used, netting should always be installed **over** the mulch. Wood fiber may be sprayed on top of an *Refer to Practice No. 6.30, Grass Lined Channels in the NC DEQ E&SC Planning and Design Manual 3. Mats, including "excelsior" (wood fiber) blankets, are considered protective mulches and may be used alone. **MULCHING**

Effective Date: 9/1/2023 In accordance with the 2013

SWALE ID TYPE BOTTOM DEPTH

V-DITCH

V-DITCH

V-DITCH

V-DITCH

V-DITCH

V-DITCH

V-DITCH 0 1.3 2

TRIANGULAR "V" CHANNEL CROSS SECTION

PARABOLIC CHANNEL CROSS SECTION

FRAPEZOIDAL CHANNEL CROSS SECTION

GRASS LINED CHANNELS

14A

SKIMMER CONSTRUCTION SPECIFICATIONS

BEFORE REPOSITIONING THE SKIMMER.

MAINTENANCE

NOTES:

1. Select material based on site and practice requirements, availability of material, labor and equipment.

THROUGH THE DAM AFTER THE EMBANKMENT IS COMPLETE.

1. SHAPE THE BASIN TO THE SPECIFIED DIMENSIONS. PREVENT THE SKIMMING DEVICE FROM SETTLING INTO

3. ASSEMBLE THE SKIMMER FOLLOWING THE MANUFACTURES INSTRUCTIONS, OR AS DESIGNED.

TAKEN IN THE WINTER TO PREVENT THE SKIMMER FROM PLUGGING WITH ICE.

PLACE THE BARREL (TYPICALLY 4-INCH LAYERS AND COMPACT IT UNDER AND AROUND THE PIPE OR AT LEAST THE SAME DENSITY AS THE ADJACENT EMBANKMENT CARE MUST BE TAKEN NOT TO RAISE THE PIPE

FROM THE FIRM CONTACT WITH ITS FOUNDATION WHEN COMPACTING UNDER THE PIPE HAUNCHES. PLACE A

MINIMUM DEPTH OF 2 FEET OF COMPACTED BACKFILL OVER THE PIPE SPILLWAY BEFORE CROSSING IT WITH

CONSTRUCTION EQUIPMENT. IN NO CASE SHOULD THE PIPE CONDUIT BE INSTALLED BY CUTTING A TRENCH

THE BARREL PIPE. ATTACH THE FLEXIBLE JOINT TO THE BARREL PIPE AND POSITION THE SKIMMER OVER

THE EXCAVATED PIT OR SUPPORT. BE SURE TO ATTACH A ROPE TO THE SKIMMER AND ANCHOR IT TO THE

4. LAY THE ASSEMBLED SKIMMER ON THE BOTTOM OF THE BASIN WITH THE FLEXIBLE JOINT AT THE INLET OF

1. IF THE SKIMMER IS CLOGGED WITH TRASH AND THERE IS WATER IN THE BASIN, USUALLY JERKING ON THE

ROPE WILL MAKE THE SKIMMER BOB UP AND DOWN AND DISLODGE THE DEBRIS AND RESTORE FLOW. IF

THIS DOES NOT WORK, PULL THE SKIMMER OVER TO THE SIDE OF THE BASIN AND REMOVE THE DEBRIS.

ALSO CHECK THE ORIFICE INSIDE THE SKIMMER TO SEE IT IF IS CLOGGED; IF SO REMOVE THE DEBRIS.


2. IF THE SKIMMER ARM OR BARREL PIPE IS CLOGGED, THE ORIFICE CAN BE REMOVED AND THE OBSTRUCTION


CLEARED WITH A PLUMBER'S SNAKE OR BY FLUSHING WITH WATER. BE SURE AND REPLACE THE ORIFICE

3. FREEZING WEATHER CAN RESULT IN ICE FORMING IN THE BASIN. SOME SPECIAL PRECAUTIONS SHOULD BE

SIDE OF THE BASIN. THIS WILL BE USED TO PULL THE SKIMMER TO THE SIDE FOR MAINTENANCE.

THE MUD BY EXCAVATING A SHALLOW PIT UNDER THE SKIMMER OR PROVIDING A LOW SUPPORT UNDER THE





NCDEQ STD. 6.65

1. LOCATE WASHOUT STRUCTURE A MINIMUM OF 50 FEET AWAY FROM OPEN CHANNELS, STORM DRAIN INLETS, SENSITIVE AREAS, WETLANDS, BUFFERS AND WATER COURSES AND AWAY FROM CONSTRUCTION TRAFFIC.

2. SIZE WASHOUT STRUCTURE FOR VOLUME NECESSARY TO CONTAIN WASH WATER AND SOLIDS AND MAINTAIN AT LEAST 4 INCHES OF FREEBOARD. TYPICAL DIMENSIONS ARE 10 FEET X 10 FEET X 3 FEET DEEP. 3. PREPARE SOIL BASE FREE OF ROCKS OR OTHER DEBRIS THAT MAY CAUSE TEARS OR HOLES IN THE LINER. FOR LINER, USE 10 MIL OR THICKER UV RESISTANT, IMPERMEABLE SHEETING, FREE OF HOLES AND TEARS OR OTHER DEFECTS THAT COMPROMISE IMPERMEABILITY OF THE MATERIAL.

4. PROVIDE A SIGN FOR THE WASHOUT IN CLOSE PROXIMITY TO THE FACILITY. 5. KEEP CONCRETE WASHOUT STRUCTURE WATER TIGHT. REPLACE IMPERMEABLE LINER IF DAMAGED (E.G., RIPPED OR PUNCTURED). EMPTY OR REPLACE WASHOUT STRUCTURE THAT IS 75 PERCENT FULL, AND DISPOSE OF ACCUMULATED MATERIAL PROPERLY. DO NOT REUSE PLASTIC LINER. WET-VACUUM STORED LIQUIDS THAT HAVE NOT EVAPORATED AND DISPOSE OF IN AN APPROVED MANNER. PRIOR TO FORECASTED RAINSTORMS, REMOVE LIQUIDS OR COVER STRUCTURE TO PREVENT OVERFLOWS. REMOVE HARDENED SOLIDS, WHOLE OR BROKEN UF FOR DISPOSAL OR RECYCLING. MAINTAIN RUNOFF DIVERSION AROUND EXCAVATED WASHOUT STRUCTURE UNTIL

CONCRETE WASHOUT STATION

PAGE:

Effective Date: 9/1/2023

In accordance with the 2013

Design Manual Updates

(TYP.)

*SEE EROSION CONTROL PLAN

FOR METHOD

OF DISCHARGE

EARTH BERM -

(SEE EROSION

CONTROL PLAN)

1' FREEBOARD AT ALL TIMES

SPILLWAY ABOVE BAFFLES

1. Clear, grub and strip the area under the embankment of all vegetation and root mat. Remove all surface soil

to the designated disposal area. Place temporary sediment control measures below basin as needed.

3. Place the barrel on a firm, smooth foundation of impervious soil. Do not use pervious material such as sand,

4. Place a minimum depth of 2 feet compacted backfill over the pipe spillway before crossing with construction

5. Ensure that the flow length to basin width ratio is at least 2:1 to improve trapping efficiency. Length is measured

Assemble the skimmer following manufacturers instructions or as designed and lay on the bottom of the basin

with the flexible joint at the inlet of the barrel pipe. Attach the flexible joint to the barrel pipe and position the

skimmer over the excavated pit or support. Be sure to attach a rope and anchor it to the side of the basin. This

Install the spillway in undisturbed soil to the greatest extent possible. The spillway should be lined with laminated

plastic or impermeable geotextile fabric. The fabric must be wide and long enough to cover the bottom and sides and extend onto the top of the dam for anchoring in a trench. The edges may be secured with 8-inch staples or

Filter fabric must be long enough to extend down the slope and exit onto stable ground. The width of the fabric

outlet protection to divert sediment-laden water to the upper end of the pool area to improve basin trap efficiency.

9. The upper section(s) should overlap the lower section(s) so that water cannot flow under the fabric. Secure the

10. Discharge water into the basin in a manner to prevent erosion. Use temporary slope drains or diversions with

1. Inspect all measures at least weekly and after each rainfall of 1.0 inch or greater. Make necessary repairs

Excavate the sediment from the entire basin, not just around the skimmer or within the first cell.

Make sure any vegetation growing in the bottom of the basin does not hold down the skimmer.

flushing with clean water. Be sure to replace the orifice before repositioning the skimmer.

Stabilize the emergency spillway embankment and all other disturbed areas above the crest of the principal

Remove sediment and restore the basin to its original dimensions when sediment accumulates to one-half the

height of the first baffle. Pull the skimmer to one side so that the sediment underneath can be excavated.

Repair baffles if they are damaged. Re-anchor the baffles if water is flowing underneath or around them.

If the skimmer arm or barrel pipe is clogged, remove orifice and clear debris with a plumber's snake or by

Check fabric lined spillway for damage and make any required repairs with fabric that spans the full width of the

spillway. Check the embankment, spillways, and outlet for erosion damage, and inspect the embankment for

compact it under and around the pipe to at least the same density as the adjacent embankment.

at the elevation of the principal spillway.

will be used to pull the skimmer to the side for maintenance.

upper edge and sides of the fabric in a trench with staples or pins.

Ensure the skimmer is not clogged with trash or debris.

must be one piece, not joined or spliced; otherwise water can get under the fabric.

2. Place the fill in lifts not to exceed 9 inches, and machine compact it. Over fill the embankment 6 inches to allow


gravel, or crushed stone as backfill around the pipe. Place the fill around the pipe spillway in 4-inch layers and

containing high amounts of organic matter and stockpile or dispose of it properly. Haul all objectionable material

EMERGENCY

SPILLWAY

6" MIN INVERT ELEVATION OF EMERGENCY



STORAGE ZONE


MAINTENANCE REQUIREMENTS . INSPECT ROCK PIPE INLET PROTECTION AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (1/2INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE SEDIMENT STORAGE AREA TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ONE—HALF THE DESIGN DEPTH OF THE TRAP. PLACE THE SEDIMENT THAT IS REMOVED IN THE DESIGNATED DISPOSAL AREA AND REPLACE THE CONTAMINATED PART OF THE GRAVEL FACING. 2. CHECK THE STRUCTURE FOR DAMAGE. ANY RIPRAP DISPLACED FROM THE STONE HORSESHOE MUST BE REPLACED IMMEDIATELY

TEMPORARY FILTER BERM BASIN


- SEDIMENT STORAGE AREA VOLUME REQUIRED=XX SF. — FINISHED GRADE TOP OF **EMBANKMENT SECTION**

CONSTRUCTION SPECFICATIONS 1. CLEAR THE AREA OF ALL DEBRIS THAT MIGHT HINDER EXCAVATION AND DISPOSAL OF SPOIL. 2. INSTALL THE CLASS B OR CLASS I RIPRAP IN A SEMI-CIRCLE AROUND THE PIPE INLET. THE STONE SHOULD BE BUILT UP HIGHER ON EACH END WHERE IT TIES INTO THE EMBANKMENT. THE MINIMUM CREST WIDTH OF THE RIPRAP SHOULD BE 3 FEET, WITH A MINIMUM BOTTOM WIDTH OF 11 FEET. THE MINIMUM HEIGHT SHOULD BE 2 FEET, BUT ALSO 1 FOOT LOWER THAN THE SHOULDER OF THE EMBANKMENT OR DIVERSIONS 3. A 1 FOOT THICK LAYER OF NC DOT #5 OR #57 STONE SHOULD BE PLACED ON THE OUTSIDE SLOPE OF THE RIPRAP 4. THE SEDIMENT STORAGE AREA SHOULD BE EXCAVATED AROUND THE OUTSIDE OF THE STONE HORSESHOE 18 INCHES BELOW NATURAL GRADE 5. WHEN THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, FILL DEPRESSION AND ESTABLISH FINAL GRADING ELEVATIONS, COMPACT AREA PROPERLY, AND STABILIZE WITH GROUND COVER.

3. AFTER ALL THE SEDIMENT-PRODUCING AREAS HAVE BEEN PERMANENTLY STABILIZED, REMOVE THE STRUCTURE AND ALL THE UNSTABLE SEDIMENT. SMOOTH THE AREA TO BLEND WITH THE ADJOINING AREAS AND PROVIDE PERMANENT GROUND COVER



EROSION CONTROL PRODUCTS NCDEQ STD. 6.17



TEMPORARY SLOPE DRAIN

NCDEQ STD. 6.30 Channel Lining Thickness Rock Riprap 1.5 times maximum stone Flagstone 4 inches including mortar V-SHAPED RIPRAP CHANNEL — DESIGN TOP WIDTH — SUBGRADE EXCAVATION FILTER LAYER, GRAVEL OR FABRIC TRAPEZOIDAL RIPRAP CHANNEL DESIGN TOP WIDTH —— FILTER LAYER, GRAVEL 7 PARABOLIC-SHAPED RIPRAP CHANNEL — DESIGN TOP WIDTH — DESIĠN DEPTH

 Clear the foundation area of trees, stumps, roots, loose rock, and other 2. Excavate the cross section to the lines and grades of the foundation of the liner as shown on the plans. Bring over-excavated areas to grade by increasing the thickness of the liner or by backfilling with moist soil compacted to the density of the surrounding Concrete linings: • Place concrete linings to the thickness shown on the plans and finish them in a workmanlike manner. • Take adequate precautions to protect freshly placed concrete from extreme temperatures to ensure proper curing. Ensure that subgrade is moist when concrete is poured. Install foundation drains or weep holes where needed to protect against uplift and

V-DITCH

TRAPEZOID V-DITCH

TRAPEZOID 2

TRAPEZOID 2

TRAPEZOID

V-DITCH

TRAPEZOID

SC250 OR 6"

RIPRAP

X-Section Area (A) = Zd^2

Top Width (T) = 2dz

X-Section Area (A) = $\frac{2}{3}$ Td

Top Width (T) = b + 2dz

GRASS-LINED CHANNELS

X-Section Area (A) = bd + Zd² Maintenance

Top Width (T) = $\frac{1.5 \text{ A}}{d}$

TRAPEZOID

TRAPEZOID 2 2

flatter for safety.

establishment period.

necessary repairs.

1. At a minimum, grass-lined channels should carry peak

runoff from the 10-year storm without eroding. Increase the

capacity according to the potential damage if flood hazard

If design velocity of the channel to be vegetated by seeding

exceeds 2 feet per second, a temporary channel liner is

channels along roadways should have side slopes of 6:1 or

material from the foundation area, and dispose of properly.

3. Channel side slopes should be 3:1 or flatter to aid in the

4. Remove all trees, brush, stumps, and other objectionable

6. Remove and properly dispose of all excess soil so that the

The procedure used to establish grass in the channel wil

sufficient to withstand anticipated velocities during the

During the establishment period, check grass-lined channels

After grass is established, periodically check the channel.

3. Check the channel outlet and all road crossings for bank

5. Keep grass in a healthy, vigorous condition at all times.

4. Remove all significant sediment accumulations to maintain

stability and evidence of piping or scour holes.

check after heavy rainfall events and immediately make any

lepend upon the severity of the conditions and selection of

pecies. Protect the channel with mulch or a temporary liner

Excavate the channel, and shape it to neat lines and

seedbed preparations and sod buildup.

surface water may enter the channel freely.

8. Filter material should consist of a least 3 inches of material on all sides of the drain pipe. The drain pipe conduit should be a minimum of 4 inches in diameter. 9. Perform all channel construction to keep erosion and water pollution to a minimum. Immediately vegetate all disturbed areas or otherwise protect them against soil erosion

1 Inspect channels at least weekly and after each rainfall of 1.0 inch or greater and make repairs promptly. Give special attention to the outlet and inlet sections and other points Carefully check stability at road crossings, looking for indication of piping, scour holes, 3. Maintain all vegetation adjacent to the channel in a healthy, vigorous condition. In accordance with the 2013

Design Manual Updates

Sheet No:

Sheet Title:

DETAILS

CONSTRUCTION

SITE

4' MAX. NCDOT #5 OR #57 ---WASHED STONE 19-GUAGE HARDWARE CLOTH 1/4" MESH OPENINGS) NCDOT #5 OR #57 WASHED STONE FIGURE 6.5IA HARDWARE CLOTH AND **GRAVEL INLET PROTECTION PLAN** . UNIFORMLY GRADE A SHALLOW DEPRESSION APPROACHING INLET. 2. DRIVE 5-FOOT STEEL POSTS 2 FEET INTO THE GROUND SURROUNDING THE INLET. SPACE POST EVENLY

CONSTRUCTION SPECIFICATIONS

FILTER BAG FOR DEWATERING

AROUND THE PERIMETER OF THE INLET, A MAXIUM OF 4 FEET APART. SURROUND THE POSTS WITH WIRE MESH HARDWARE CLOTH. SECURE THE WIRE MESH TO THE STEEL POSTS AT THE TOP, MIDDLE, AND BOTTOM. PLACING A 2-FOOT FLAP OF WIRE MESH UNDER THE GRAVEL FOR ANCHORING IS RECOMMENDED. 4. PLACE CLEAN GRAVEL (NCDOT#5 OR #57 STONE) ON A 2:1 SLOPE WITH A HEIGHT OF 16 INCHES

AROUND THE WIRE, AND SMOOTH TO AN EVEN GRADE. ONCE THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE ACCUMULATED SEDIMENT, AND ESTABLISH FINAL GRADING ELEVATIONS. 6. COMPACT THE AREA PROPERLY AND STABILIZED IT WITH GROUNDCOVER.

<u>MAINTENANCE</u>

DATE

PVC ELBOW

PVC END ∼

PVC END ~

CAP

PVC /

INFLOW -

AVERAGE WIDTH (W) = 🕹

IDRAINAGE IDENUDED

(AC.) (AC.)

|BASIN| AREA | AREA |

* AREA OF BASIN WATER SURFACE AT TOP

OF PRINCIPAL SPILLWAY ELEVATION

BASIN VOLUME

TEMPORARY SKIMMER BASIN

STRUCTURE

CAP

PERSPECTIVE VIEW

WATER SURFACE

40 PVC PIPE

FRONT VIEW

ARM ASSEMBLY

HOLES IN

FLEXIBLE -

END VIEW

HOSE

UNDERSIDE

"C" ENCLOSURE

ENTRY UNIT

PVC VENT PIPE

BOTTOM SURFACE

STRUCTURE

DEWATERING

WOOD STAKE OR METAL

POST FOR RETRIEVAL

ROPE TIE-OFF

SKIMMER SEDIMENT BASIN

(FT.) (FEET) (FEET) (FEET) (FEET) (FEET) Ø (IN.)

─ ROPE

SKIMMER

DEVICE

(BELOW SKIMMER)

DEPTH |

└ STONE PAD

DATA BLOCK

1 | 3.3 | 2.1 | 11.3 | 5940 | 8034 | 4911 | 5068 | 2 | 3 | 4.5 | 120 | 1.5 | 58 | 4 | 1

| 2 | 1.5 | 1 |5.95 | 2700 | 3860 | 2588 | 2600 | 2 | 3 |4.5 | 89 | 1.5 | 35 | 3 | 0.75

SURFACE AREA

|REQUIRED | PROVIDE | REQUIRED | PROVIDE |

|(CU. FT.)|(CU. FT.)|(SQ. FT.)|(SQ. FT.)

DEWATERING

ZONE

FILTER

SEDIMEN

STORAGE ZONE

FABRIC

INSPECT INLETS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (1/2 INCH OR GREATER) RAINFALL EVENT. CLEAR THE MESH WIRE OF ANY DEBRIS OR OTHER OBJECTS TO PROVIDE ADEQUATE FLOW FOR SUBSEQUENT RAINS. TAKE CARE NOT TO DAMAGE OR UNDERCUT THE WIRE MESH DURING SEDIMENT REMOVAL. REPLACE STONE AS NEEDED.

<u>REFERENCES</u> INLET PROTECTION

6.52, BLOCK AND GRAVEL INLET PROTECTION 6.54, ROCK DOUGHNUT INLET PROTECTION

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATION FOR ROADS AND STRUCTURES


HARDWARE CLOTH AND GRAVEL INLET PROTECTION

- 1. A STABILIZED ENTRANCE PAD OF 2"-3" COURSE AGGREGATE SHALL BE LOCATED WHERE TRAFFIC WILL ENTER OR LEAVE THE CONSTRUCTION SITE ONTO A PUBLIC STREET. . FILTER FABRIC OR COMPACTED CRUSHER RUN STONE MAY BE USED AS A BASE FOR THE
- CONSTRUCTION ENTRANCE. 3. IF CONDITIONS AT THE SITE ARE SUCH THAT MOST OF THE MUD AND SEDIMENT ARE NOT REMOVED BY VEHICLES TRAVELING OVER THE GRAVEL, THE TIRES SHALL BE WASHED. WASHING SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS IN A SEDIMENT
- RAP OR OTHER SUITABLE DISPOSAL AREA. A WASH RACK MAY ALSO BE USED. 4. SOIL STABILIZATION FABRIC (AS SPECIFIED BY THE DESIGNER) SHALL BE USED.

MAINTENANCE NOTES:

MAINTAIN THE GRAVEL PAD IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. THIS MAY REQUIRE PERIODIC TOPDRESSING WITH 2-INCH STONE. AFTER EACH RAINFALL, INSPECT ANY STRUCTURE USED TO TRAP SEDIMENT AND CLEAN IT OUT AS NECESSARY. IMMEDIATELY REMOVE ALL OBJECTIONABLE MATERIALS SPILLED, WASHED, OR TRACKED ONTO PUBLIC ROADWAYS.

CONSTRUCTION ENTRANCE



1. DIG AN 8" TRENCH AND PLACE THE POSTS ON 10'

- USE A TENSION BAR AND 3 CLAMPS TO SECURE THE MESH TO THE FIRST POST. PLACE MESH IN TRENCH AND ON THE UPHILL SIDE OF POSTS.
- STRETCH THE MESH TIGHTLY AND ATTACH TO TERMINAL POST USING A TENSION BAR AND BANDS 4. ATTACH MESH TO EACH POSTS WITH WIRE TIES, 3
- MESH. ATTACH THE MESH TO THE TENSION WIRE USING HOG RINGS 5' ON CENTER. 6. ATTACH THE SILT FENCE FABRIC TO THE MESH
- USING PLASTIC WIRE TIES 2' ON CENTER TOP AND

FENCE POSTS MAINTENANCE NOTES:

1. FILTER BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS NEEDED SHALL BE MADE IMMEDIATELY. 2. SHOULD THE FABRIC DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL


IS NECESSARY, THE FABRIC SHALL BE REPLACED

PROMPTI Y 3. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS REMOVED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED.

TEMPORARY SUPER SILT FENCE

TRENCH IN FABRIC

& MESH 8" MIN.




- DRAINAGE. THE FOUNDATION SHOULD BE EXCAVATED AT LEAST 2 INCHES BELOW THE CREST OF THE STORM DRAIN PLACE THE BOTTOM ROW OF BLOCKS AGAINST THE FDGE OF THE STORM DRAIN FOR LATERAL SUPPORT AND TO AVOID WASHOUTS WHEN OVERFLOW OCCURS. IF NEEDED, GIVE LATERAL SUPPORT TO SUBSEQUENT ROWS BY PLACING 2 X 4 WOOD STUDS THROUGH BLOCK OPENINGS. 2. CAREFULLY FIT HARDWARE CLOTH OR COMPARABLE WIRE MESH WITH $\frac{1}{2}$ INCH OPENINGS OVER ALL BLOCK
- OPENINGS TO HOLD GRAVEL IN PLACE. 3. USE CLEAN #57 STONE, ₹ TO ½ INCH IN DIAMETER, PLACED 2 INCHES BELOW THE TOP OF THE BLOCK ON A 2:1 SLOPE OR FLATTER AND SMOOTH IT TO AN EVEN GRADE.

MAINTENANCE NOTES:

1. INSPECT, CLEAN, AND PROPERLY MAINTAIN THE EXCAVATED BASIN AFTER EVERY STORM UNTIL THE CONTRIBUTING DRAINAGE AREA HAS BEEN PERMANENTLY STABILIZED. TO PROVIDE SATISFACTORY BASIN EFFICIENCY, REMOVE SEDIMENT WHEN THE VOLUME OF THE BASIN HAS BEEN REDUCED BY ONE-HALF. SPREAD ALL EXCAVATED MATERIAL EVENLY OVER THE SURROUNDING LAND AREA OR STOCKPILE AND STABILIZE

\ BLOCK AND GRAVEL DROP INLET PROTECTION



GENERAL NOTES:

- 1. FILTER FABRIC FENCE SHALL BE A MINIMUM OF 32" IN WIDTH AND SHALL HAVE A MINIMUM OF 6 LINE WIRES
- WITH 12" STAY SPACING. 2. WOVEN FILTER FABRIC BE USED WHERE SILT FENCE IS TO REMAIN FOR A PERIOD OF MORE THAN 30 DAYS. 3. STEEL POSTS SHALL BE 5'-0" IN HEIGHT AND BE OF
- THE SELF-FASTENER ANGLE STEEL TYPE. 4. WIRE FENCING SHALL BE AT LEAST #10 GAGE WITH A MINIMUM OF 6 LINE WIRES WITH 12" STAY SPACING. 5. TURN SILT FENCE UP SLOPE AT ENDS.
- 6. WIRE MESH SHALL BE MIN. 13 GAGE WITH MAXIMUM 12" 7. ORANGE SAFETY FENCE IS REQUIRED AT BACK OF SILT FENCE (WITHIN 5 FT.) WHEN GRADING IS ADJACENT TO SWIM BUFFERS OR WETLANDS (REFER TO SWIM BUFFER

MAINTENANCE NOTES:

GUIDELINES).

- 1. INSPECT SEDIMENT FENCES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.
- 2. SHOULD THE FABRIC OF A SEDIMENT FENCE COLLAPSE, TEAR, DECOMPOSE OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY. 3. REMOVE SEDIMENT DEPOSITS AS NECESSARY TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE FENCE. TAKE
- CARE TO AVOID UNDERMINING THE FENCE DURING CLEANOUT 4. REMOVE ALL FENCING MATERIALS AND UNSTABLE SEDIMENT DEPOSITS AND

BRING THE AREA TO GRADE AND STABILIZE IT AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

END OF FLARED

SECTION

END OF APRON

0% SLOPE

ELEVATION

GRADE

CONTROL MANUAL" DMAX = 1.5 X d50

T = 1.5 X DMAX

NOTE: MINIMUM

H=3 PIPE DIAMETER

SEEDING MIXTURE SPECIES

ANCHORING TOOL.

GERMAIN MILLET

SUBSTITUTED AT A RATE OF 50 LB/ACRE

SEEDING DATES
MOUNTAINS-MAY 15 - AUG. 15

COASTAL PLAIN-APR. 15 - AUG. 15

750 LB/ACRE 10-10-10 FERTILIZER.

AS A MULCH ANCHORING TOOL

IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.

PIEDMONT-MAY 1 - AUG. 15

RYE (GRAIN)

d50 (SEE FIG. 8.06 A&B "NC SEDIMENT AND EROSION"

COASTAL PLAIN AND PIEDMONT-AUG. 15 - DEC. 30

FOLLOW SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND

BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH

REPAIR AND RE-FERTILIZE DAMAGED AREAS IMMEDIATELY

NECESSARY TO EXTENT TEMPORARY COVER BEYOND JUNE 15,

OVERSEED WITH 50 LB/ACRE KOBE (PIEDMONT AND COSTAL PLAIN)

TEMPORARY SEEDING RECOMMENDATIONS FOR FALL

IN THE PIEDMONT AND MOUNTAINS, A SMALL-STEMMED SUDANGRASS MAY BE

FOLLOW SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND

APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR

A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED

REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED. REFERTILIZE. AND MULCH

TEMPORARY SEEDING RECOMMENDATIONS FOR SUMMER

TEMPORARY SEEDING SPECIFICATIONS

TOPDRESS WITH 50 LB/ACRE OF NITROGEN IN MARCH. IF

AGRICULTURAL LIMESTONE AND 1,000 LB/ACRE 10-10-10 FERTILIZER.


APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH

ASPHALT, NETTING, OR A MULCH ANCHORING TOOL, A DISK WITH

FILTER FABRIC APT

(IF NEEDED)

FILTER FABRIC



2. REFER TO THE NORTH CAROLINA DEPARTMENT OF

RIPRAP APRON DESIGN STANDARDS.

CULVERT HEIGHT

OR GREATER.

MAINTENANCE NOTES:

SEEDING MIXTURE

ANNUAL LESPEDEZA (KOBE IN

PIEDMONT AND COSTAL PLAIN,

IS NOT TO EXTEND BEYOND JUNE.

COASTAL PLAIN-DEC. 1 - APRIL 15

MOUNTAINS-ABOVE 2500 FEET: FEB. 15 - MAY 15

BELOW 2500 FEET: FEB. 1 - MAY 1

FOLLOW SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND

AGRICULTURAL LIMESTONE AND 750 LB/ACRE 10-10-10 FERTILIZER.

APPLY 4,000 LB/ACRE STRAW, ANCHOR STRAW BY TACKING WITH

ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH

REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED,

TEMPORARY SEEDING RECOMMENDATIONS

FOR LATE WINTER AND EARLY SPRING

REFERTILIZE, AND MULCH IMMEDIATELY FOLLOWING EROSION OR

KOREAN IN MOUNTAINS)

PIEDMONT-JAN, 1 - MAY 1

OTHER DAMAGE.

SPECIES

OR KOREAN (MOUNTAINS) LESPEDEZA IN LATE FEBRUARY OR EARLY

BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH

RYE (GRAIN)

RATE (LB/ACRE)

RATE (LB/ACRE)

AT THE DOWNSTREAM END.

ENVIRONMENT AND NATURAL RESOURCES' EROSION AND

3. RIPRAP SHOULD EXTEND UP BOTH SIDES OF THE APRON

4. THERE SHALL BE NO OVERFLOW FROM THE END OF THE

APRON TO THE SURFACE OF THE RECEIVING CHANNEL

SEDIMENT CONTROL PLANNING AND DESIGN MANUAL FOR

AND AROUND THE END OF THE PIPE OR CULVERT AT THE

AREA TO BE PAVED OR RIPRAPPED SHALL BE UNDERCUT SO

CHANNEL. THE APRON SHALL HAVE A CUTOFF OR TOE WALL

THAT THE INVERT OF THE APRON SHALL BE ATTHE SAME GRADE (FLUSH) WITH THE SURFACE OF THE RECEIVING

5. THE WIDTH OF THE END OF THE APRON SHALL BE EQUAL TO THE BOTTOM WIDTH OF THE RECEIVING CHANNEL.

6. ALL SUBGRADE FOR STRUCTURE TO BE COMPACTED TO 95%

7. THE PLACING OF FILL, EITHER LOOSE OR COMPACTED IN THE

8. NO BENDS OR CURVES IN THE HORIZONTAL ALIGNMENT OF

10. ANY DISTURBED AREA FROM END OF APRON TO RECIEVING

. RIPRAP SHOULD BE INSPECTED PERIODICALLY FOR

SCOUR OR DISLODGED STONES. CONTROL OF WEED AND

OMIT ANNUAL LESPEDEZA WHEN DURATION OF TEMPORARY COVER

RATE (LB/ACRE)

BRUSH GROWTH MAY BE NEEDED IN SOME LOCATIONS.

MAXIMUM TAPER TO RECEIVING CHANNEL 5:1

RECEIVING CHANNEL SHALL NOT BE ALLOWED.

9. FILTER FABRIC SHALL BE INSTALLED ON COMPACTED

SUBGRADE PRIOR TO PLACEMENT OF RIP RAP.

THE APRON WILL BE PERMITTED.

CHANNEL MUST BE STABILIZED.

DISCHARGE OUTLET AT A MAXIMUM SLOPE OF 2:1 AND A HEIGHT NOT LESS THAN TWO THIRDS THE PIPE DIAMETER OR

OVER THE DAM. ADD STONES TO DAMS AS NEEDED TO MAINTAIN DESIGN HEIGHT AND CROSS SECTION.


THE CANNEL BANKS.

OF THE CHECK DAM.

MAINTENANCE NOTES:

THE TOE ELEVATION OF THE UPPER DAM.

6.31, RIPRAP-LINE AND PAVED CHANNELS).



	OUTLE	r protec	CTION SUI	MMARY		
SOURCE	La (ft)	W1 (ft)	W2 (ft)	*T (in)	H (in)	d50 (in)
CULVERT 1	14	16	6	13.56	16	6
CULVERTS 2 & 3	6	6.67	2	13.56	5.33	6
CULVERT 4	6	7	3	13.56	8	6
CULVERT 5	8	8.67	2	13.56	5.33	6
CULVERT 8	6	7	3	13.56	8	6
CULVERT 9	14	15.5	4.5	13.56	12	6
CULVERT 10	8	9.25	3.75	13.56	10	6
CULVERT 11	6	7	3	13.56	8	6
CULVERT 12	12	13.50	4.50	13.56	12	6
SWALES 19 & 20	8	9	3	13.56	8	6
SWALE 17	6	7	3	13.56	8	6
SWALES 15 & 16	6	7	3	13.56	8	6
SWALE 22A	14	16	6	13.56	16	6
SWALE 22B	14	16	6	13.56	16	6
SWALES 5, 6, & 7	6	7	3	13.56	8	6

SLOPES (3:1 TO 2:1)

TALL FESCUE

TALL FESCUE &

ABRUZZI RYE

TALL FESCUE

HULLED COMMON

BERMUDA GRASS

TALL FESCUE AND

***BROWNTOP MILLET

SORGHUM-SUDAN

HYBRIDS

SLOPES (3:1 TO 2:1)

SERICEA LESPEDEZA

ADD TALL FESCUE

COMMON BERMUDA

***TALL FESCUE AND

***BROWNTOP MILLET

***OR SORGHUM-SUDAN

SERICEA LESPEDEZA

(UNHULLED-

FESĆUE

ADD ABRUZZI RYE

UNSCARIFIED) AND TALL

(SCARIFIED) AND

AUG 15 - NOV 1

APR 15 - JUN 30

MAR 1 - JUN 1

MAR 1 - JUN 30

JUN 1 - SEP 1

PLANTING RATE

300 LBS/ACRE

25 LBS/ACRE

300 LBS/ACRE

25 LBS/ACRE

120 LBS/ACRE

35 LBS/ACRE

30 LBS/ACRE

50 LBS/ACRE

120 LBS/ACRE

35 LBS/ACRE

30 LBS/ACRE

70 LBS/ACRE

120 LBS/ACRE

25 LBS/ACRE

SIZES PRESENTED IN SECTION 2 OF THE EROSION CONTROL

PLAN VIEW

L = THE DISTANCE SUCH THAT POINTS A AND B ARE EQUAL ELEVATIONS

12" OF NCDOT #5 OR #57 WASHED STONE

CLASS B RIPRAP -

1. PLACE STONE TO THE LINES AND DIMENSIONS SHOWN IN THE PLAN ON A FILTER FABRIC FOUNDATION.

KEE THE CENTER STONE SECTION AT LEAST 9 INCHES BELOW NATURAL GROUND LEVEL WHERE THE DAM ABUTS

3. EXTEND STONE AT LEAST 1.5 FEET BEYOND THE DITCH BANK TO KEEP WATER FROM CUTTING AROUND THE ENDS

4. SET SPACING BETWEEN DAMS TO ASSURE THAT THE ELEVATION AT THE TOP OF THE LOWER DAM IS THE SAME AS

INSPECT CHECK DAMS AND CHANNELS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT $(\frac{1}{2}$ INCH OR GREATER) RAINFALL

EDGES OF THE DAM. CORRECT ALL DAMAGE IMMEDIATELY. IF SIGNIFICANT EROSION OCCURS BETWEEN DAMS, ADDITIONAL

MEASURES CAN BE TAKEN AS, INSTALLING A PROTECTIVE RIP RAP LINER IN THAT PORTION OF THE CHANNEL. (PRACTICE

REMOVE SEDIMENT ACCUMULATED BEHIND THE DAMS AS NEEDED TO PREVENT DAMAGE TO CHANNEL VEGETATION. ALLOW

THE CHANNEL TO DRAIN THROUGH THE STONE CHECK DAM, AND PREVENT LARGE FLOWS FROM CARRYING SEDIMENT

EVENT AND REPAIR IMMEDIATELY. CLEAN OUT SEDIMENT STRAW, LIMBS, OR OTHER DEBRIST THAT COULD CLOG THE

ANTICIPATE SUBMERGENCE AND DEPOSITION ABOVE THE CHECK DAM AND EROSION FROM HIGH FLOWS AROUND THE

. PROTECT THE CHANNEL AFTER THE LOWEST CHECK DAM FROM HEAVY FLOW THAT COULD CAUSE EROSION.

7. ENSURE THAT OTHER AREAS OF THE CHANNEL, SUCH AS CULVERT ENTRANCES BELOW THE CHECK DAMS, ARE


FILTER -

CLOTH

MAKE SURE THAT THE CHANNEL REACH ABOVE THE MOST UPSTREAM DAM IS STABLE.

NOT SUBJECT TO DAMAGE OR BLOCKAGE FORM DISPLACED STONES.

PACKAGE.						
	OUTLE	r PROTEC	CTION SUI	MMARY		
SOURCE	La (ft)	W1 (ft)	W2 (ft)	*T (in)	H (in)	d50 (in)
CULVERT 1	14	16	6	13.56	16	6
CULVERTS 2 & 3	6	6.67	2	13.56	5.33	6
CULVERT 4	6	7	3	13.56	8	6
CULVERT 5	8	8.67	2	13.56	5.33	6
CULVERT 8	6	7	3	13.56	8	6
CULVERT 9	14	15.5	4.5	13.56	12	6
CULVERT 10	8	9.25	3.75	13.56	10	6
CULVERT 11	6	7	3	13.56	8	6
CULVERT 12	12	13.50	4.50	13.56	12	6
SWALES 19 & 20	8	9	3	13.56	8	6
SWALE 17	6	7	3	13.56	8	6
SWALES 15 & 16	6	7	3	13.56	8	6
SWALE 22A	14	16	6	13.56	16	6
SWALE 22B	14	16	6	13.56	16	6
SWALES 5, 6, & 7	6	7	3	13.56	8	6



3. ALL CONCRETE TO BE 4000 P.S.I COMPRESSIVE STRENGTH. 4. PROVIDE TONGUE OR SPIGOT JOINT AT INLET END SECTION.


2' MAX AT


CROSS-SECTION VIEW


CENTER

- 5. PROVIDE GROOVE OR BELL JOINT AT OUTLET END SECTION. 6. THE DIMENSIONS FOR END SECTIONS SHALL SUBSTANTIALLY AGREE WITH THE TABLE. MINOR VARIATIONS WILL BE PERMITTED BASED
- ON THE MANUFACTURER'S STANDARD FORMS AND TEMPLATES. 7. NOT TO BE USED IN NCDOT MAINTAINED RIGHT OF WAY.
- TABLE OF DIMENSIONS T A B C E L H:V WT. -1/4" 6" 2'-3" 3'-10" 2'-0" 6'-1" 3:1 730 -1/2" 9" 2'-3" 3'-10" 3'-0" 6'-1" 3:1 1190 3" 10" 3'-8" 2'-6" 4'-0" 6'-2" 3:1 1770 -1/2" 1'-0" 4'-6" 1'-8" 5'-0" 6'-2" 3:1 2380 48" 5" 2'-0" 6'-0" 2'-2" 7'-0" 8'-2" 3:1 5920 54" 5-1/2" 2'-3" 5'-6" 2'-10" 7'-6" 8'-4" 3:1 8810 60" 6" 2'-6" 5'-0" 3'-3" 8'-0" 8'-3" 3:1 11180 66" 6-1/2" 3'-0" 6'-0" 2'-3" 8'-6" 8'-3" 3:1 12530 72" 7" 3'-0" 6'-6" 1'-9" 9'-0" 8'-3" 3:1 13980









LAWN MULCH AFTER COMPLETION OF SEEDING OPERATIONS. SPREAD UNIFORMLY TO FORM A CONTINUOUS BLANKET NOT LESS THAN 1 1/2" LOOSE MEASUREMENT OVER SEEDED AREAS. ANCHOR MULCH BY SPRAYING WITH ASPHALT EMULSION AT THE RATE OF 10-13 GALLONS PER 1,000 S.F. TAKE PRECAUTIONS TO PREVENT DAMAGE OR STAINING OF CONSTRUCTION OR OTHER PLANTINGS ADJACENT TO MULCHED AREAS.


PROTECT SEEDED AREAS AGAINST EROSION BY SPREADING SPECIFIED

SEEDBED PREPARATION 1. CHISEL COMPACTED AREAS AND SPREAD TOPSOIL 3 INCHES DEEP OVER ADVERSE SOIL CONDITIONS, IF AVAILABLE. 2. RIP THE ENTIRE AREA TO 6 INCHES DEPTH.

- 3. REMOVE ALL LOOSE ROCK, ROOTS, AND OTHER OBSTRUCTIONS LEAVING SURFACE REASONABLY SMOOTH AND UNIFORM. 4. APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPERPHOSPHATE UNIFORMLY AND MIX WITH SOIL (SEE BELOW*). 120 LBS/ACRE 5. CONTINUE TILLAGE UNTIL A WELL-PULVERIZED, FIRM, REASONABLY UNIFORM SEEDBED IS PREPARED 4-6" DEEP.
 - WITH SEEDING EQUIPMENT OR CULTIPACK AFTER SEEDING. 7. MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH. 8. INSPECT ALL SEEDED AREAS AND MAKE NECESSARY REPAIR OR RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND SHOULD BE OVER 60% DAMAGED, REESTABLISH FOLLOWING ORIGINAL LIME, FERTILIZER AND SEEDING RATES. 9. CONSULT CONSERVATION INSPECTOR ON MAINTENANCE TREATMENT AND FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED.
 - * APPLY: AGRICULTURAL LIMESTONE 2 TONS/ACRE FERTILIZER - 1000 LBS/ACRE 10-10-10 SUPERPHOSPHATE - 500 LBS/ACRE 20% MULCH - 2 TONS/ACRE -SMALL GRAIN STRAW

ANCHOR - ASPHALT EMULSION





TEMPORARY STONE OPENING IN SILT FENCE

Project No: 1725-500672.00 Date: Revisions:

11.20.2025

Corp. NC License: F-1320

Sheet Title:

SITE **CONSTRUCTION DETAILS**

Sheet No:


Corp. NC License: F-1320

Project No: 1725-500672.00 11.20.2025 Date:

Revisions:


CONSTRUCTION DETAILS

C504




TRENCH BOTTOM DIMENSIONS & BACKFILLING REQUIREMENTS FOR PVC GRAVITY SEWER MAIN
N.T.S.

S-5




TYPICAL SANITARY SEWER LATERAL CONNECTION




REQUIREMENTS FOR DUCTILE IRON





1. BACKFILL TO 95% OF MAXIMUM DENSITY WHERE EXCAVATIONS CUT THROUGH PAVEMENTS, CURBS, DRIVEWAYS AND SIDEWALKS, AND UNDER OR ADJACENT TO STRUCTURES. 2. STONE TO BE SIZE $\frac{1}{2}$ " TO $1-\frac{1}{2}$ ", WELL TAMPED.

- 3. STONE IS REQUIRED TO 6" BELOW PIPE WHERE WET CONDITIONS OR ROCK IS ENCOUNTERED, ONLY AS DIRECTED. 4. HAND SHAPE TRENCH BOTTOM FOR LOWER QUADRANT OF PIPE AND
- 5. PROVIDE MINIMUM 3'-0" COVER OVER PIPE. 6. STONE TO $\frac{1}{2}$ PIPE DIA. NOT REQUIRED FOR C-900 PVC OR DUCTILE IRON PIPE.
- 5 UTILITY TRENCH
 N.T.S.



6 CLEANOUT N.T.S.

NOTES

1. SEE SPECIFICATIONS FOR OTHER REQUIREMENTS.

7 ASPHALT LAP JOINT N.T.S.

ASPHALT -

DRIVEWAY

— MILL AND PLACE 1.5"

ASPHALT PAVEMENT

EXISTING BASE

COURSE

- EXISTING SUBGRADE

S9.5C SURFACE

COURSE

PIPE CROWN

 PROVIDE BEDDING TO PIPE SPRING LINE

UNDISTURBED SOIL

LOOSELY PLACED BEDDING

MATERIAL ONLY, COMPACT

AFTER PIPE IS PLACED

DIRECTLY BENEATH THE

PIPE UNCOMPACTED.

SHALL BE CLASS I

LEAVING SECTION

BACKFILL MATERIAL SHALL BE #57 STONE, #67 STONE, ASTM

MAXIMUM COVER REQUIREMENTS SHALL BE ESTABLISHED BY

CALCULATIONS BASED UPON AASHTO LRFD BRIDGE DESIGN

MAXIMUM ALLOWABLE DIAMETER FOR HDPE AND PP IS 48".

IF WATER TABLE IS HIGHER THAN SUBGRADE OF TRENCH,

STRUCTURAL DESIGN ASSUMPTIONS REGARDING THE

FOUNDATION SUPPORT AND THAT THE ASSUMED

4A GEOTEXTILE,

SUPPORT WILL BE MET.

SPECIFICATIONS FOR THE PIPE MATERIALS SPECIFIED ON THE

STONE BACKFILL MATERIAL SHALL BE WRAPPED IN NCDOT TYPE

IT IS THE RESPONSIBILITY OF THE ENGINEER TO CONFIRM THE

GROUNDWATER CONDITIONS OF THE STRUCTURAL TRENCH

D2321 CLASS | MATERIAL, OR AASHTO A1 OR A3 MATERIAL.

THE ENGINEER OF RECORD THROUGH ENGINEERING


Corp. NC License: F-1320


Project No: 1725-500672.00 11.20.2025


Revisions:


SITE **CONSTRUCTION DETAILS**

C505












- WATER MAIN







NCDOT 5" MONOLITHIC CONCRETE ISLAND ON ASPHALT

TYPICAL SECTION A: HDPE AND PP

DIAMETER (In)

18

30

PIPE CROWN -

LOOSELY PLACED BEDDING -

DIRECTLY BENEATH THE

PIPE UNCOMPACTED.

SHALL BE CLASS I MATERIAL

ONLY, COMPACT AFTER PIPE

IS PLACED LEAVING SECTION

TYPICAL SECTION B: RCP

FINISHED GRADE

TAMPED IN 6" LIFTS

- SELECT BACKFILL

CLASS | OR |

COMPACTED TO

95% OR GREATER

MATERIAL

HIGH DENSITY POLYETHYLENE (HDPE)

AND POLYPROPLYENE

(PP) MIN COVER CROWN

TO FINISHED GRADE (ft)

2.0

2.0

2.0

2.0

BEDDING FOR STORMWATER PIPES

- CLASS I, II, OR III

COMPACTED,


BACKFILL

6" MIN









├── 7 5%" ── ┤

9 1/3"

7 %"-8 ½"

10 1/4"-11"-

<u>EXTENSION OF VALVE BOX</u>

─ SEE DETAIL W-18

FOR COVER DETAILS.

- STANDARD VALVE BOX

CONCRETE PAD —

WITH STONE

ALLOWED.

1. VALVE BOX NOT TO CONTACT WATER MAIN

3. FOR ALL VALVES OVER 10' DEEP, A VALVE

2. ALL TRAFFIC CASTINGS MUST BE CLASS 35 OR

STEM EXTENSION MUST BE USED TO BRING TO

A DEPTH OF NO MORE THAN 5', EXTENSION

4. TOTAL VALVE BOX WEIGHT: MINIMUM OF 85 LBS.

CITY OF RALEIGH

STANDARD DETAIL

VALVE BOX INSTALLATION

AND EXTENSION

W-17

CONCRETE PAD

2. CONTAINMENT RPZ/RPDA BACKFLOW ASSEMBLIES ARE TO BE INSTALLED WITHIN 50 LINEAR

PIPING FEET OF THE METER OR RIGHT-OF-WAY FOR FIRE SERVICE LINES AND MEET INSTALLATION REQUIREMENTS AS LISTED IN APPENDIX A: GUIDELINES AND REQUIREMENTS OF

3. NO VALVE IN THE EXISTING SYSTEM SHALL BE OPERATED WITHOUT FOLLOWING THE

PROCEDURE OUTLINED IN THE RALEIGH WATER PUBLIC UTILITY DESIGN MANUAL. THE

CONTRACTOR SHALL NOTIFY RALEIGH WATER'S DISTRIBUTION DIVISION AT 919-996-3245 TO

4. RESIDENTIAL LAWN IRRIGATION R.P. ASSEMBLIES THAT ARE REMOVED TO PREVENT FREEZING IN THE WINTER MONTHS MUST BE CAPPED OFF. ALL ABOVE GROUND ASSEMBLIES, EXCEPT RESIDENTIAL LAWN IRRIGATION ASSEMBLIES, MUST BE PROTECTED FROM FROST.

1. ENCLOSURE MUST BE ASSE 1060 APPROVED AND HAVE ADEQUATE DRAINAGE.

5. ALL CONTAINMENT BACKFLOW ASSEMBLIES MUST BE ASSE AND USC APPROVED.

THE CROSS CONNECTION AND HYDRANT METER PROGRAM.

6. STEEL RODS AND BOLTS SHALL BE 34" 316 STAINLESS STEEL.

REQUEST THE OPERATION OF ANY VALVE.

- THRUST BLOCKING TYP.

SEE DETAIL W-8

VALVES. NO PRECAST CONCRETE DOUGHNUT

MUST BE A MINIMUM OF 1" SOLID STOCK.

5. 2'x2'x6" CONCRETE PAD REQUIRED ON ALL

CASTING

VALVE

BOX COVER

VALVE

BOX

TOP SECTION TO BE

SLIDE SECTION

─USE 5" SOIL PIPE

- STAB-IN C.I. OR

- STANDARD VALVE

BOX BOTTOM

SECTION

D.I. PIPE GASKET

FOR EXTENSIONS

BACKFILL, TYP.

CONCRETE BLOCK AND BACKFILL



BARK WITH 5 PARTS

— COMPACT BACKFILL IN BOTTOM OF HOLE

SECTIONAL VIEW

2 Typical Shrub Planting N.T.S.

TOWN OF ZEBULON

| AVE)

Existing Buffer Photo A

N.T.S.

Project No: 1725-500672.00 11.20.2025 **Revisions:**

Corp. NC License: F-1320

POINT OF BEGINNING (P.O.

E:2193171.77' NAD83/2011

EXISTING BUFFER A

Know what's **below**. **Call** before you dig.

Little River Existing Aerial View
N.T.S.

SCALE: 1"=60'


Existing Buffer Photo B
N.T.S.

Sheet Title:

OVERALL LANDSCAPE PLAN

Sheet No:

C600



Alfred Benesch & Company 2359 Perimeter Pointe Parkway, Suite 350 Charlotte, NC 28208 www.benesch.com

Seals:



Corp. NC License: F-1320

Lorp. NC License. F-13

TTLE RIVER PARK 1800 WEST GANNON AVENUE

Project No: 1725-500672.00

Date: 11.20.2025

Revisions:

Sheet Title:

LANDSCAPE PLAN

Sheet No:

Satistics of the serimeter Pointe Parkway, Suite 350



Seals:

Corp. NC License: F-1320

TLE RIVER PAR 1800 WEST GANNON AVENUE

Project No: 1725-500672.00

Date: 11.20.2025

Revisions:

Sheet Title:

SITE LIGHTING PLAN

Sheet No: **C 7 0 0**

	LIGHTING FIXTURE SCHEDULE									
MARK	MANUF.	CATAL <i>O</i> G NUMBER	NO.	MP DATA TYPE	VOLTS	BAL NO.	LAST DATA TYPE	INPUT WATTS	MOUNTING	DESCRIPTION
Α	HE WILLIAMS	6DR-TL-L20/835- DIM-UNV-L-M-OF-WET/CC	1	LED	120/277	-	-	19	RECESSED	GENERAL - 6" WET LISTED RECESSED LED.

CATALOG NUMBERS AND MANUFACTURERS ARE TO INDICATE TYPE AND QUALITY OF FIXTURE DESIRED. SUBMIT CUTSHEETS OF THESE AND ALTERNATE MANUFACTURERS FOR ARCHITECT AND OWNER APPROVAL PRIOR TO PURCHASE OF ANY FIXTURES. INFORMATION ON ALTERNATE FIXTURES PROPOSED BY THE CONTRACTOR SHALL INCLUDE THE ADD/DEDUCT ASSOCIATED WITH ACCEPTANCE OF THAT FIXTURE (OR THE ALTERNATE PACKAGE AS A WHOLE).

LIGHTING SYSTEMS

		11111	4 0 1 0		•
ENERGY	CONS	SERVAT	ION CO	DE SEC	TION 405

LIGHTING POWER DENSITY CALCULATION COMPLIANCE	
INTERIOR LIGHTING POWER DENSITY CALCULATION PER TABLE 405.4.2.	SEE

THIS PROJECT IS CLASSIFIED AS -

LIGHTING FIXTURE SCHEDULE FOR FIXTURE INFORMATION. RESTROOM INTERIOR WATTAGE SPECIFIED VS. ALLOWED <u>140</u> VS. <u>229</u>

EXTERIOR LIGHTING POWER DENSITY CALCULATION PER TABLE 405.6.2. SEE LIGHTING FIXTURE SCHEDULE FOR FIXTURE INFORMATION. TRADABLE EXTERIOR WATTAGE SPECIFIED VS. ALLOWED ____171_ VS. <u>600</u>___

NONTRADABLE EXTERIOR WATTAGE SPECIFIED VS. ALLOWED NA VS. NA

DESIGNER STATEMENT:

TO THE BEST OF MY KNOWLEDGE AND BELIEF, THE DESIGN OF THIS BUILDING COMPLIES WITH THE LIGHTING SYSTEMS REQUIREMENTS OF THE INTERNATIONAL ENERGY CONSERVATION CODE, SECTION 505 AND ANY LOCAL AMENDMENTS THEREOF.

□ COMMERCIAL (SEE BELOW)

SIGNED: NAME: JAMES HOFFMAN III TITLE: ELECTRICAL ENGINEER

SECTION 406 COMPLIANCE - \square N/A ☐ 406.1.1 **□ 406.1.2 □ 406.1.3 □ 406.1.4 □ 406.1.5 □ 406.1.6**

ф SURFACE, RECESSED OR GROUND MOUNTED LIGHTING FIXTURE, SEE FIXTURE SCHEDULE FOR DETAILS. ELECTRIC UTILITY METER LOCATION. **ELECTRICAL ABBREVIATIONS** 18" DIMENSION INDICATES HEIGHT ABOVE FINISHED FLOOR AT WHICH CENTER OF DEVICE IS TO BE MOUNTED. AFF ABOVE FINISHED FLOOR. AFG ABOVE FINISHED GRADE. EC ELECTRICAL CONTRACTOR. FPN FUSE PER EQUIPMENT NAMEPLATE REQUIREMENTS. GC GENERAL CONTRACTOR. MC MECHANICAL CONTRACTOR. PC PLUMBING CONTRACTOR. WP INDICATES DEVICE TO HAVE WEATHERPROOF COVER. UON UNLESS OTHERWISE NOTED.

ELECTRICAL SYMBOL LEGEND

CIRCUIT CONDUCTORS CONCEALED IN FLOOR, WALL OR CEILING.

SINGLE POLE SWITCH, 20A, 120/277 VOLT, 48" A.F.F. TO CENTER.

"GFI" INDICATES GROUND FAULT CIRCUIT INTERRUPTER TYPE.

DUPLEX RECEPTACLE, 15 AMP, 120 VOLT, 18" A.F.F. TO CENTER. FOR SINGLE

"EWC" INDICATES MOUNT INSIDE ENCLOSURE OF ELECTRIC WATER COOLER.

240/120V PANEL, SURFACE OR RECESS MOUNTED, SEE SCHEDULE FOR DETAILS.

ARROWHEAD INDICATES HOMERUN TO PANEL NOTED.

RECEPTACLE ON A CIRCUIT, USE A 20A RECEPTACLE.

"WP" INDICATES WEATHERPROOF.

 \Rightarrow

GENERAL ELECTRICAL NOTES

- ALL ELECTRICAL WORK SHALL BE IN ACCORDANCE WITH THE 2020 EDITION OF THE NATIONAL ELECTRICAL CODE AND ALL LOCAL AND STATE CODES.
- 2. ALL MATERIAL, DEVICES, APPLIANCES, AND EQUIPMENT SHALL BE NEW AND SHALL CONFORM TO THE STANDARDS OF THE UNDERWRITER'S LABORATORIES, INC., AND THE NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION.
- 3. ALL ELECTRICAL PERMITS AND INSPECTION FEES SHALL BE OBTAINED AND PAID FOR BY THE ELECTRICAL CONTRACTOR. DRAWINGS ARE DIAGRAMMATIC ONLY AND INDICATE ONLY THE GENERAL ARRANGEMENT. SEE ARCHITECTURAL DRAWINGS FOR EXACT DIMENSIONS.
- 4. ELECTRICAL CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS FOR ONE YEAR EFFECTIVE THE DAY THE PROJECT IS ACCEPTED BY THE OWNER.
- 5. ELECTRICAL CONTRACTOR SHALL MAKE ALL ELECTRICAL POWER CONNECTIONS TO HVAC, PLUMBING AND OTHER EQUIPMENT AS REQUIRED.
- 6. A COMPLETE GROUNDING SYSTEM SHALL BE PROVIDED AND INSTALLED IN ACCORDANCE WITH
- ARTICLE 250 OF THE NEC, AND AS SHOWN ON THE DRAWINGS. 7. ALL CUTTING AND PATCHING OF WALLS AND FLOORS FOR ELECTRICAL EQUIPMENT SHALL BE THE
- 8. CONDUCTORS SHALL BE COPPER RATED AT NOT LESS THAN 600 VOLTS. MINIMUM SIZE SHALL BE #12 AWG UNLESS OTHERWISE NOTED ON THE DRAWINGS. ALL WIRE #8 AWG AND LARGER SHALL BE STRANDED. ALL CONDUCTORS #10 AND SMALLER SHALL BE SOLID, UNLESS OTHERWISE NOTED. ALUMINUM CONDUCTORS AND MINIMUM SIZE OF #14 SHALL BE USED IN

RESIDENTIAL UNITS. BRANCH CIRCUIT CONDUCTORS SHALL BE TYPE THHN OR THWN AS

- 9. USE SCHEDULE 40 PVC OUTDOORS WHERE NOT SUBJECT TO PHYSICAL DAMAGE OR BELOW FLOOR SLAB. MINIMUM CONDUIT SIZE TO BE 1/2". TYPE NM, MC AND AC CABLE MAY BE USED WHERE PERMISSIBLE BY NEC. FLEXIBLE CONDUIT SHALL BE USED FOR CONNECTIONS TO VIBRATING EQUIPMENT AND LUMINAIRES, BUT SHALL NOT EXCEED 6' IN LENGTH.
- 10. PROVIDE A PULLWIRE IN ALL EMPTY CONDUITS.

REQUIRED.

RESPONSIBILITY OF THE ELECTRICAL CONTRACTOR.


- II. PROVIDE A TYPED DIRECTORY IN ALL PANELBOARDS CLEARLY DESCRIBING THE LOCATION OF AND TYPE OF LOAD BEING SERVED FOR ALL CIRCUITS. PROVIDE ENGRAVED PHENOLIC NAMEPLATES FOR ALL PANELBOARDS AND DISCONNECT SWITCHES, WHITE LETTERS ON BLACK BACKGROUND.
- 12. FUSES 0 600 AMPS SHALL BE UL CLASS "RK-I" LOW PEAK DUAL ELEMENT TIME DELAY WITH 200,000 AMPERE INTERRUPTING RATING AS MANUFACTURED BY BUSSMANN, UNLESS NOTED
- 13. ALL TERMINALS/LUGS SHALL BE 60/75° RATED. ALL TERMINALS, SPLICING CONNECTORS, LUGS, ETC SHALL BE IDENTIFIED FOR USE WITH THE MATERIAL (CU/AL) OF THE CONDUCTOR AND SHALL BE PROPERLY INSTALLED.
- 14. VERIFY ALL REQUIREMENTS AND COORDINATE EXACT LOCATION OF INCOMING ELECTRICAL SERVICE WITH LOCAL POWER COMPANY PRIOR TO PROJECT START-UP. NOTIFY ENGINEER OF ANY CHANGES AS MAY BE REQUIRED.
- 15. E.C. TO VERIFY DEVICE PLATE COLOR AND MATERIAL WITH ARCHITECT PRIOR TO PURCHASE.
- 16. THE ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL ELECTRICAL EQUIPMENT FROM FOREIGN MATERIAL DURING CONSTRUCTION (PAINT, SPACKLE, ETC.).
- 17. WHERE A HOME RUN IS SHOWN THE CIRCUIT SHALL BE INSTALLED IN A DEDICATED CONDUIT, DO NOT COMBINE WITH OTHER CIRCUITS. WHERE A CIRCUIT HOMERUN IS NOT SHOWN, THE CONTRACTOR SHALL COMBINE CIRCUITS AS FOLLOWS: A MAXIMUM OF THREE 20A BRANCH CIRCUITS MAY BE COMBINED IN A COMMON HOMERUN WITH SEPARATE NEUTRALS FOR A MAXIMUM TOTAL OF SIX CURRENT CARRYING CONDUCTORS. ALL BRANCH CIRCUITS LARGER THAN 20A SHALL BE SEPARATELY HOMERUN TO THE PANEL.
- 18. RECEPTACLES IN COMMERCIAL AREAS SHALL BE SPECIFICATION GRADE EQUAL TO HUBBELL 5200/5300 SERIES; GROUND FAULT RECEPTACLES SHALL BE EQUAL TO HUBBELL GF-5362. LIGHTING SWITCHES SHALL BE SPECIFICATION GRADE EQUAL TO HUBBELL 1200 SERIES.
- 19. ALL EXTERIOR FIXTURES AND DEVICES SHALL BE RATED FOR OPERATION AT 0° F AND SHALL BE DAMP OR WET LABELED AS REQUIRED.
- 20. THE ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ALL ELECTRICAL EQUIPMENT, DEVICES, ETC. IN ACCORDANCE WITH LOCAL SEISMIC CODE REQUIREMENTS. PROVIDE SEISMIC RESTRAINTS, ACCESSORIES AND INSTALLATION DETAIL AS REQUIRED.
- 21. ALL QUESTIONS MUST BE SUBMITTED IN RFI FORMAT TO THE ARCHITECT AND MUST BE ADDRESSED BY THE APPROPRIATE DESIGNER OF RECORD PRIOR TO BECOMING A PROPOSED CHANGE ORDER.





ch

S

Φ








GANNON AVENUE NORTH CAROLINA 4 RIVE 1800 WEST ZEBULON,

PROJECT NO: 1725-500672.00 4/15/2025


REVISION SCHEDULE

REV NO REV DATE

ELECTRICAL LEGEND AND NOTES



GROUNDING ELECTRODES SHALL BE PROVIDED IN ACCORDANCE WITH NEC SECTION 250. ALL GROUNDING ELECTRODE CONDUCTORS SIZED AS INDICATED ON POWER RISER DIAGRAM. ALL METHODS OF CREATING THE GROUNDING SYSTEM MAY NOT BE REQUIRED OR



ZW-2415-E0-2 - ELECTRICAL SITE PLAN.dw

SURFACE

NEMA 3R

| | | - | - | 39 |

SPACE

SPACE

SPACE

3.8 | 2.4 | TOTAL CONNECTED kVA 6.2 DEMAND kVA: 6.4 PANEL RMS SYM. AMPS: SEE RISER DEMAND AMPS: 27

- / _ | 36 | -

- / _ | 40 | - |


1 SPACE

1 SPACE

1 SPACE

42 - - 1 SPACE

PANEL "A" LOAD SUMMARY									
OAD YPE		KVA CONN	DEM FACT	KVA DEM					
OADS ON 100AMP MCB									
LIGHTS		0.9	1.25	1.1					
RECEPTACLES	IST 10kVA	0.5	1.0	0.5					
	REMAINDER	_	0.5	-					
WATER HEATER		4.8	1.0	4.8					
TOTALS		6.2		6.4					
TOTAL AMPS @ 240V IØ	26.7								



- ATC CIRCUIT THROUGH 24-HR, 7-DAY, MULTI-POLE ASTRONOMICAL TIMECLOCK. LOCATE
- 3. GFI PROVIDE GFCI BREAKER FOR CIRCUIT. GFCI RECEPTACLES MAY BE USED IN LIEU OF GFCI BREAKERS SO LONG AS THE DEVICE(S) CONFORM TO NEC CODE REQUIREMENTS FOR GFCI PROTECTION.

PANEL "B" LOAD SUMMARY							
LOAD TYPE		KVA CONN	DEM FACT	KVA DEM			
LOADS ON 200AMP MCB							
LIGHTS		1.7	1.25	2.1			
RECEPTACLES	IST I0kVA	1.7	1.0	1.7			
	REMAINDER	_	0.5	_			
WATER HEATER		4.8	1.0	4.8			
EQUIPMENT		0.8	1.0	0.8			
TOTALS		9.0		9.4			
TOTAL AMPS @ 240V IØ	39.2						

1 PHASE 3 WIRE SURFACE MOUNTED NEMA 3R

PANEL SHALL BE SERVICE ENTRANCE RATED, EQUAL TO SIEMENS PI PANELBOARD.. TIMECLOCK ADJACENT TO PANEL.

PANEL "B" LOAD SUMMARY				
LOAD TYPE		KVA CONN	DEM FACT	KVA DEM
LOADS ON 200AMP MCB				
LIGHTS		1.7	1.25	2.1
RECEPTACLES	IST I0kVA	1.7	1.0	1.7
	REMAINDER	_	0.5	_
WATER HEATER		4.8	1.0	4.8
EQUIPMENT		0.8	1.0	0.8
TOTALS		9.0		9.4
TOTAL AMPS @ 240V IØ	39.2			

XFMR 50 kVA PROVIDED BY OTHERS PANEL 100A MCB 240/120V 240/120V 10,000AIC 22,000AIC GRADE NOTE 5 NOTE 1




RISER DIAGRAM NOTES:

PRIMARY BY

UTILITY

- I. SERVICE LATERAL CONDUCTORS TO METER PROVIDED AND INSTALLED BY UTILITY. COORDINATE FOR TRENCHING AND CONDUIT REQUIREMENTS.
- 2. METER BASE PROVIDED AND INSTALLED BY ELECTRICAL CONTRACTOR, TO UTILITY REQUIREMENTS. METER PROVIDED AND INSTALLED BY UTILITY. MOUNT METER AT THE MINIMUM HEIGHT ABOVE FINAL GRADE. COORDINATE REQUIREMENTS WITH UTILITY.
- 3. 3#250 KCM (AL), IN $2\frac{1}{2}$ " CONDUIT.
- 4. 3#3 (AL), IN I" CONDUIT.
- 5. GROUNDING ELECTRODE CONDUCTOR SHALL BE #8 (CU) BONDED TO BUILDING STEEL (IF ANY), SLAB REINFORCING BARS (CONCRETE ENCASED ELECTRODE) AND DRIVEN GROUND ROD, SEE 1/E001.



GENERAL NOTES: (THIS SHEET)

I. FAINT ITEMS ARE PROVIDED BY OTHERS.

LIGHTHOUSE ENGINEERING, PA No. C-2714

OF AUTHORITY

OF AU

benesch & COMPANY

PROJECT NO: 1725-500672.00

REVISION SCHEDULE

REV NO REV DATE

ELECTRICAL FLOOR PLAN AND RISER