


Y:\North Carolina\TXC\05\1725-500672-00_JobInfo_1725-500672-00_CD\1725-500672-00_EROSION CONTROL PLAN.dwg
V:\North Carolina\TXC\05\1725-500672-00_JobInfo_1725-500672-00_CD\1725-500672-00_EROSION CONTROL PLAN.dwg





LEGEND			
	EXISTING SIGN		EXISTING CURB AND GUTTER
	EXISTING IRON PIN		PROPOSED CURB AND GUTTER
	EXISTING LIGHT POLE		PROPERTY LINE
	EXISTING UTILITY POLE		EXISTING FENCE
	RIGHT-OF-WAY		EXISTING UNDERGROUND ELECTRIC LINE
	ACCESSIBLE SPACE		EXISTING OVERHEAD UTILITY LINE
	EXISTING TREE TO REMAIN		EXISTING UNDERGROUND TELEPHONE LINE
	EXISTING FIRE HYDRANT		EXISTING FIBER OPTIC LINE
	EXISTING WATER VALVE		EXISTING SANITARY SEWER LINE
	EXISTING WATER METER		EXISTING GAS LINE
	EXISTING SEWER MANHOLE		EXISTING CONTOUR LINE
	EXISTING STORM MANHOLE		PROPOSED CONTOUR LINE
	PROPOSED STORM MANHOLE		PROPOSED DRAINAGE DITCH
	PROPOSED FLARED END SECTION		EXISTING STORM DRAINAGE PIPE
	EXISTING DRAINAGE STRUCTURE		PROPOSED STORM DRAINAGE PIPE
	PROPOSED DRAINAGE STRUCTURE		PROPOSED ROOF DRAIN PIPE
	EXISTING SPOT ELEVATION		EXISTING TREE LINE
	PROPOSED SPOT ELEVATION		PROPOSED TREE LINE
	EXISTING CLEANOUT		EXISTING GAS VALVE
	EXISTING DOWNSPOUT		EXISTING GAS METER
	WETLANDS EXTENT		ZONE "Ae" (100 YEAR FLOODPLAIN)
	TEMPORARY SILT SACK		ZONE "X" (FUTURE 100 YEAR FLOODPLAIN)
	TEMPORARY INLET PROTECTION		STREAM CENTER LINE
	TEMPORARY ROCK CHECK DAM		TEMPORARY SILT FENCE
	TEMPORARY FILTER BERM BASIN		TEMPORARY SILT FENCE AND TREE PROTECTION
	TEMPORARY FILTER BAG WITH FLOATING INTAKE TO SKIMMER CELL		TEMPORARY TREE PROTECTION
	TEMPORARY DIVERSION SWALE		STONE OPENING IN TEMPORARY SILT FENCE
	PERMANENT SWALE		SUPER SILT FENCE
	PROPOSED CHANNEL MATTING		PROPOSED LIMIT OF DISTURBANCE
			PROPOSED RIPRAP APRON
			FLOOD PRONE SOIL LIMITS


- GENERAL NOTES**
- SEE GRADING PLAN SHEET C304 FOR PIPE INVERTS AND SIZING.
 - SEE SWALE SCHEDULE ON SHEET C502 FOR SIZES AND LINING.
 - SEE RIPRAP APRON DETAIL ON SHEET C503 FOR SIZING.

- NCDEQ REQUIRED NOTES**
- STOCKPILES, LAYDOWN OR WASTE AREAS, CONCRETE WASHOUTS, PORTABLE TOILETS, AND FUELS MUST BE LOCATED AT LEAST 50 FEET AWAY FROM ANY OPEN WATER CONVEYANCES, SUCH AS BASINS, DITCHES, STORM DRAIN INLETS, ETC. THE LOCATION OF THESE ACTIVITIES MAY BE FIELD ADJUSTED IF THE DISTANCE REQUIREMENTS ARE MET.
 - NO LAND DISTURBING ACTIVITIES, INCLUDING TIMBERING OR DEMOLITION ACTIVITIES, ARE ALLOWED WITHOUT FIRST OBTAINING A SEDIMENT AND EROSION CONTROL PLAN APPROVAL AND CERTIFICATE OF COVERAGE.

- CONSTRUCTION SEQUENCE**
- EROSION AND SEDIMENT CONTROL (E&S) PERMIT AND A CERTIFICATION OF COVERAGE (COC) MUST BE OBTAINED BEFORE ANY LAND DISTURBING ACTIVITIES (INCLUDING TIMBERING AND DEMOLITION) OCCUR. COC CAN BE OBTAINED BY FILLING OUT THE e-NOI FORM AT <https://www.deq.nc.gov/NC001/deq.nc.gov> ONCE THE PLANS HAVE BEEN APPROVED. A COPY OF THE E&S PERMIT, THE COC, AND A HARD COPY OF THE PLAN MUST BE KEPT ON SITE IN A PERMITS BOX AND ACCESSIBLE DURING INSPECTION.
 - PER NPDES REQUIREMENTS, A RAIN GAUGE, SELF-INSPECTIONS RECORDS, PERMIT, CERTIFICATION OF COVERAGE, AND E&S PLAN ARE REQUIRED TO BE MAINTAINED ON SITE AND ACCESSIBLE DURING INSPECTION. IT IS RECOMMENDED THAT THESE ITEMS BE PLACED IN A PERMITS BOX AT THE BEGINNING OR ENTRANCE OF PROJECT.
 - THE CONTRACTOR SHALL CONDUCT SELF-INSPECTIONS OF THE EROSION AND SEDIMENTATION CONTROL MEASURES AND COMPLETE THE FOLLOWING COMBINED SELF-INSPECTION FORM FOUND ON THE DEMAR WEBSITE: <https://deq.nc.gov/about/divisions/energy-mineral-lands-resources/erosion-sediment-control/forms/deq.nc.gov>. TWELVE MONTHS OF COMPLETE INSPECTION FORMS SHALL BE KEPT ON-SITE AND AVAILABLE FOR INSPECTION AT ALL TIMES. IT IS RECOMMENDED A COPY BE KEPT IN A PERMITS BOX.
 - SELF-INSPECTIONS FOR EROSION AND SEDIMENTATION CONTROL MEASURES ARE TO BE PERFORMED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF EVERY RAIN EVENT OF EQUAL TO OR GREATER THAN 1 INCH. ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN MEASURES AS DESIGNED. ALL ESC MEASURES SHALL BE MAINTAINED AS SPECIFIED IN THE CONSTRUCTION DETAILS ON THIS PLAN. A RAIN GAUGE SHALL BE INSTALLED AT THE PROJECT SITE FOR MONITORING.
 - CONTACT NCDEQ EROSION CONTROL INSPECTOR TO INFORM THEM THAT CONSTRUCTION IS READY TO BEGIN.
 - SCHEDULE AN ON-SITE PRE-CONSTRUCTION CONFERENCE WITH THE NCDEQ EROSION CONTROL INSPECTOR, WAKE COUNTY, CONTRACTOR, AND BENESCH TO DISCUSS EROSION CONTROL MEASURES.
 - INSTALL GRAVEL CONSTRUCTION ENTRANCE, TEMPORARY DIVERSIONS SWALES, TREE PROTECTION, AND SILT FENCE AS SHOWN ON THE APPROVED PLAN. CLEAR ONLY AS NECESSARY TO INSTALL THESE DEVICES. SEED TEMPORARY DIVERSIONS AND BERMS IMMEDIATELY AFTER CONSTRUCTION.
 - INSTALL TEMPORARY SKIMMER SEDIMENT BASINS 1 AND 2 AND DIVERSION SWALES DRAINING TO THEM.
 - INSTALL TEMPORARY DEWATERING DEVICE (SILT BAG) NEAR TEMPORARY SKIMMER SEDIMENT BASINS. CONTRACTOR WILL CONTINUOUSLY MONITOR AND MAINTAINED DEVICE DURING OPERATION. SEE MANUFACTURER FOR SPECIFIC MAINTENANCE REQUIREMENTS.
 - CONTACT NCDEQ EROSION CONTROL INSPECTOR FOR APPROVAL TO MOVE INTO NEXT PHASE. AND OBTAIN A CERTIFICATE OF COMPLIANCE.
 - BEGIN CLEARING AND GRUBBING. ROUGH GRADE SITE.
 - KEEP ALL EROSION AND SEDIMENTATION CONTROL DEVICES IN WORKING CONDITION AS WORK PROGRESS. INSPECT AND AMEND ANY DAMAGED DEVICES AS SPECIFIED IN THE DETAILS.



Y:\North Carolina\TXC\505\1725-500672-00_Zebulon_Little_River_Park_Erosion_Control_Plan.dwg
Y:\North Carolina\TXC\505\1725-500672-00_Zebulon_Little_River_Park_Erosion_Control_Plan.dwg




LEGEND			
	EXISTING SIGN		EXISTING CURB AND GUTTER
	EXISTING IRON PIN		PROPOSED CURB AND GUTTER
	EXISTING LIGHT POLE		PROPERTY LINE
	EXISTING UTILITY POLE		EXISTING FENCE
	RIGHT-OF-WAY		EXISTING UNDERGROUND ELECTRIC LINE
	ACCESSIBLE SPACE		EXISTING OVERHEAD UTILITY LINE
	EXISTING TREE TO REMAIN		EXISTING UNDERGROUND TELEPHONE LINE
	EXISTING FIRE HYDRANT		EXISTING FIBER OPTIC LINE
	EXISTING WATER VALVE		EXISTING SANITARY SEWER LINE
	EXISTING WATER METER		EXISTING WATER LINE
	EXISTING SEWER MANHOLE		EXISTING GAS LINE
	EXISTING STORM MANHOLE		EXISTING CONTOUR LINE
	PROPOSED STORM MANHOLE		PROPOSED CONTOUR LINE
	PROPOSED FLARED END SECTION		PROPOSED DRAINAGE DITCH
	EXISTING DRAINAGE STRUCTURE		EXISTING STORM DRAINAGE PIPE
	PROPOSED DRAINAGE STRUCTURE		PROPOSED STORM DRAINAGE PIPE
	EXISTING SPOT ELEVATION		PROPOSED ROOF DRAIN PIPE
	PROPOSED SPOT ELEVATION		EXISTING TREE LINE
	EXISTING CLEANOUT		PROPOSED TREE LINE
	EXISTING DOWNSPOUT		EXISTING GAS VALVE
	WETLANDS EXTENT		EXISTING GAS METER
	TEMPORARY SILT SACK		ZONE "AE" (100 YEAR FLOODPLAIN)
	TEMPORARY INLET PROTECTION		ZONE "X" (FUTURE 100 YEAR FLOODPLAIN)
	TEMPORARY ROCK CHECK DAM		STREAM CENTER LINE
	TEMPORARY FILTER BERM BASIN		TEMPORARY SILT FENCE
	TEMPORARY FILTER BAG WITH FLOATING INTAKE TO SKIMMER CELL		TEMPORARY SILT FENCE AND TREE PROTECTION
	TEMPORARY DIVERSION SWALE		TEMPORARY TREE PROTECTION
	PERMANENT SWALE		STONE OPENING IN TEMPORARY SILT FENCE
			SUPER SILT FENCE
			PROPOSED LIMIT OF DISTURBANCE
			PROPOSED RIPRAP APRON
			FLOOD PRONE SOIL LIMITS

- ### GENERAL NOTES
- SEE GRADING PLAN SHEET C304 FOR PIPE INVERTS AND SIZING.
 - SEE SWALE SCHEDULE ON SHEET C502 FOR SIZES AND LINING.
 - SEE RIPRAP APRON DETAIL ON SHEET C503 FOR SIZING.

- ### NCDEQ REQUIRED NOTES
- STOCKPILES, LAYDOWN OR WASTE AREAS, CONCRETE WASHOUTS, PORTABLE TOILETS, AND FUELS MUST BE LOCATED AT LEAST 50 FEET AWAY FROM ANY OPEN WATER CONVEYANCES, SUCH AS BASINS, DITCHES, STORM DRAIN INLETS, ETC. THE LOCATION OF THESE ACTIVITIES MAY BE FIELD ADJUSTED IF THE DISTANCE REQUIREMENTS ARE MET.
 - NO LAND DISTURBING ACTIVITIES, INCLUDING TIMBERING OR DEMOLITION ACTIVITIES, ARE ALLOWED WITHOUT FIRST OBTAINING A SEDIMENT AND EROSION CONTROL PLAN APPROVAL AND CERTIFICATE OF COVERAGE.

- ### CONSTRUCTION SEQUENCE
- KEEP ALL EROSION AND SEDIMENTATION CONTROL DEVICES IN WORKING CONDITION AS WORK PROGRESS. INSPECT AND AMEND ANY DAMAGED DEVICES AS SPECIFIED IN THE DETAILS.
 - INSTALL STORM SEWER AND PROTECT INLETS WITH BLOCK AND GRAVEL INLET CONTROLS AS SHOWN ON THE PLAN. BEGIN BULK OF CONSTRUCTION, WATER AND SEWER CONNECTION, BUILDING, ETC.
 - STABILIZE SITE AS AREAS ARE BROUGHT UP TO FINISH GRADE WITH VEGETATION, PAVING, DITCH LININGS, ETC. SEED AND MULCH DENUDDED AREAS PER GROUND STABILIZATION TIME FRAMES.
 - STABILIZE ALL NEW DENUDDED AREAS WITH TEMPORARY HYDRO-SEEDING. SEE SEEDING SCHEDULE FOR SEED TYPE, DATES, AND RATES FOR DISTURBED AREAS WITH GRADED SLOPES FLATTER THAN 3:1. SEE EROSION CONTROL BLANKET NOTE (SHEET C300) FOR SEEDING ON DISTURBED AREAS WITH GRADED SLOPES AT 3:1 OR STEEPER.
 - SEEDING AND MATTING SHALL BE COMPLETED ON UPSTREAM AREAS SLOPES PRIOR TO REMOVING AND BACKFILLING TEMPORARY SEDIMENT BASINS. BOTH BASINS SHALL REMAIN IN PLACE UNTIL REMOVAL IS APPROVED BY NCDEQ INSPECTOR.
 - COMPLETE ALL CONSTRUCTION WITHIN PROJECT LIMITS. CONTINUE TO STABILIZE ALL OPEN AREAS WITHIN STABILIZATION REQUIREMENTS WHERE LAND-DISTURBING ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED.
 - ALL EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE N.C. EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL, U.S. DEPT. OF AGRICULTURE, AND THE SOS EROSION CONTROL ORDINANCE.
 - THE CONTRACTOR SHALL DILIGENTLY AND CONTINUOUSLY MAINTAIN ALL EROSION CONTROL DEVICES AND STRUCTURES TO MINIMIZE EROSION.
 - THE CONTRACTOR SHALL CONDUCT SELF-INSPECTIONS OF THE EROSION AND SEDIMENTATION CONTROL MEASURES AND COMPLETE THE FOLLOWING COMBINED SELF-INSPECTION FORM FOUND ON THE DEMLR WEBSITE: <https://dem.nc.gov/about/divisions/erosion-sediment-control/forms/ldet-nc.pdf>. TWELVE MONTHS OF COMPLETE INSPECTION FORMS SHALL BE KEPT ON-SITE AND AVAILABLE FOR INSPECTION AT ALL TIMES. IT IS RECOMMENDED A COPY BE KEPT IN A PERMITS BOX.
 - SELF-INSPECTIONS FOR EROSION AND SEDIMENTATION CONTROL MEASURES ARE TO BE PERFORMED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND EVERY EIGHT HOURS OF EVERY RAIN EVENT OF EQUAL TO OR GREATER THAN 1 INCH ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN MEASURES AS DESIGNED. ALL ESC MEASURES SHALL BE MAINTAINED AS SPECIFIED IN THE CONSTRUCTION DETAILS ON THIS PLAN. A RAIN GAUGE SHALL BE INSTALLED AT THE PROJECT SITE FOR MONITORING.



Alfred Benesch & Company
2355 Perimeter Forum
Charlotte, NC 28208
www.benesch.com
P 704.521.9880

Seals:

Corp. NC License: F-1320

LITTLE RIVER PARK


1800 WEST GANNON AVENUE
ZEBULON, NORTH CAROLINA

Project No: 1725-500672.00
Date: 11.20.2025
Revisions:
Addendum #1 12.08.25

Sheet Title:
**EROSION CONTROL PLAN
PHASE 2**

Sheet No:
C302-1

4. SCHEDULE A SITE MEETING WITH THE ENVIRONMENTAL CONSULTANT TO DETERMINE IF A BASIN CAN BE REMOVED. INSTALL SILT FENCING OR OTHER TEMPORARY EROSION CONTROL MEASURES AS NEEDED PRIOR TO REMOVAL OF THE BASIN.
5. CONTACT NCDOE – RALEIGH REGIONAL OFFICE (919) 791-4200 TO DETERMINE THE DIVISION OF PERMITS AND LAND RESOURCES CENTER CONTACT PERSON TO RECEIVE DOWATERING NOTIFICATIONS. AT LEAST 10 DAYS PRIOR TO BEGINNING DOWATERING ACTIVITY, SEND EMAIL TO NCDOE-DEMNR CONTACT PERSON AND COPY ENVIRONMENTAL CONSULTANT THAT MEET YOU ONSITE. THE EMAIL SHOULD INCLUDE THE FOLLOWING INFORMATION: WAKE COUNTY PROJECT NAME, NUMBER, AND LOCATION (CITY/TOWN), ENVIRONMENTAL CONSULTANT NAME, AND ADDRESS THE FOLLOWING: A) REASON FOR CONVERSION, B) BASIN #, C) DOWATERING METHOD, AND D) ALL OTHER INFORMATION FROM PART II, SECTION G, ITEM 4 OF THE NCDOT. (KEEP EMAIL FOR YOUR NPDES MONITORING DOCUMENTATION)
6. AFTER RECEIVING POSITIVE CONFIRMATION FROM NCDOE-DEMNR THAT YOU MAY REMOVE THE BASIN OR ON DAY 11, WHICHEVER IS SOONER, REMOVE BASINS) AND ASSOCIATED TEMPORARY DOWATERING DEVICES. IF PRESS AND/OR SAND SPREADERS ARE REQUIRED, THEY MUST BE PROVIDED. PERFORM THIS OPERATION AT THIS TIME. INSTALL ALL OTHER HARDSCAPES WITHIN BASIN LOCATIONS. FINE GRADE AREA IN PREPARATION FOR SEEDING.
7. PERFORM SEEDBED PREPARATION, SEED, MULCH AND ANCHOR ANY RESULTING BARE AREAS IMMEDIATELY.
8. PERFORM SOD/PLANT PLAN
9. INSTALL VELOCITY DISSIPATORS AND/OR LEVEL SPREADERS AS REQUIRED ON THE EROSION CONTROL PLAN
10. WHEN SITE IS FULLY STABILIZED, CALL ENVIRONMENTAL CONSULTANT FOR APPROVAL OF REMOVING REMAINING TEMPORARY EROSION CONTROL MEASURES AND ADVISE ON WHEN SITE CAN BE ISSUED A CERTIFICATE OF COMPLETION. NOTE: A MEETING SHOULD ALSO BE SCHEDULED WITH THE ENVIRONMENTAL CONSULTANT TO DETERMINE IF THE BASIN CAN BE CONVERTED FOR STORMWATER USE. SOME MUNICIPALITIES MAY ALSO REQUIRE THIS.




1. SEE GRADING PLAN SHEET C304 FOR PIPE INVERTS AND SIZING.
2. SEE SWALE SCHEDULE ON SHEET C502 FOR SIZES AND LINING.
3. SEE RIPRAP APRON DETAIL ON SHEET C503 FOR SIZING.

1. STOCKPILES, LAYDOWN OR WASTE AREAS, CONCRETE WASHOUTS, PORTABLE TOILETS, AND FUELS MUST BE LOCATED AT LEAST 50 FEET AWAY FROM ANY OPEN WATER CONVEYANCES, SUCH AS BASINS, DITCHES, STORM DRAIN INLETS, ETC. THE LOCATION OF THESE ACTIVITIES MAY BE FIELD ADJUSTED IF THE DISTANCE REQUIREMENTS ARE MET.
2. NO LAND DISTURBING ACTIVITIES, INCLUDING TIMBERING OR DEMOLITION ACTIVITIES, ARE ALLOWED WITHOUT FIRST OBTAINING A SEDIMENT AND EROSION CONTROL PLAN APPROVAL AND CERTIFICATE OF COVERAGE.


1. COMPLETE ALL CONSTRUCTION/THROW PROJECT LIMITS CONTINUE TO STABILIZE ALL OPEN AREAS WITHIN STABILIZATION REQUIREMENTS WHERE LAND-DISTURBING ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED.
2. WHEN CONSTRUCTION IS COMPLETE AND ALL AREAS ARE STABILIZED COMPLETELY, CONTACT NDEQ INSPECTOR FOR AN INSPECTION.
3. WHEN PERMISSION IS GRANTED BY NDEQ INSPECTOR, REMOVE TEMPORARY DIVERSIONS, SEDIMENT BASINS (SEE BELOW FOR BASIN REMOVAL SEQUENCE), ALL REMAINING PERMANENT EROSION CONTROL DEVICES, SUCH AS VELOCITY DISSIPATORS, SHOULD NOW BE IN PLACE AND MONITORING.
4. EROSION CONTROL MEASURES DIRECTLY AFFECTED BY THIS CONTRACT SHALL BE MAINTAINED/REMOVED UNDER THIS CONTRACT. DEVICES SHALL BE MAINTAINED TO MAX. 50% CAPACITY UNTIL AREAS THEY SERVE ARE FULLY STABILIZED.
5. PROVIDE PERMANENT GRASSING FOR ALL DISTURBED AREAS.
6. CONTACT NDEQ FOR PERMISSION TO REMOVE REMAINING TEMPORARY EROSION CONTROL DEVICES.
7. REMOVE ALL EROSION CONTROL DEVICES, SPREAD AND SEED ACCUMULATED SEDIMENT.
8. ALL EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE N.C. EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL, U.S. DEPT. OF AGRICULTURE, AND THE SCS EROSION CONTROL ORDINANCE.
9. THE CONTRACTOR SHALL DILIGENTLY AND CONTINUOUSLY MAINTAINED ALL EROSION CONTROL DEVICES AND STRUCTURES TO MINIMIZE EROSION.
10. WHEN THE PROJECT IS COMPLETE, THE PERMITTEE SHALL CONTACT DEMLR TO CLOSE OUT THE EASC PLAN.
11. PER THE NPDES PERMIT, GROUND STABILIZATION WILL BE APPLIED WITHIN 14 CALENDAR DAYS FROM LAST LAND DISTURBING ACTIVITY, FOR STEEP SLOPES, THAT AREA MUST BE STABILIZED WITHIN 7 CALENDAR DAYS. HOWEVER, NPDES GROUNDCOVER REQUIREMENTS TAKE PRECEDENCE.
12. PERMANENT GROUNDCOVER SHALL BE ESTABLISHED IN 90 CALENDAR DAYS. HOWEVER, NPDES GROUNDCOVER REQUIREMENTS TAKE PRECEDENCE.
13. THE CONTRACTOR SHALL CONDUCT SELF-INSPECTIONS OF THE EROSION AND SEDIMENTATION CONTROL MEASURES AND COMPLETE THE FOLLOWING COMBINED SELF-INSPECTION FORM FOUND ON THE DEMLR WEBSITE: <https://dep.nc.gov/about/divisions/energy-mineral-land-resources/erosion-sediment-control/forms> [dep.nc.gov]. TWELVE MONTHS OF COMPLETE INSPECTION FORMS SHALL BE KEPT ON-SITE AND AVAILABLE FOR INSPECTION AT ALL TIMES. IT IS RECOMMENDED A COPY BE KEPT IN A PERMITS BOX.
14. SELF-INSPECTIONS FOR EROSION AND SEDIMENTATION CONTROL MEASURES ARE TO BE PERFORMED AT LEAST ONE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF EVERY RAIN EVENT OF EQUAL TO OR GREATER THAN 1 INCH, ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN MEASURES AS DESIGNED. ALL ESC MEASURES SHALL BE MAINTAINED AS SPECIFIED IN THE CONSTRUCTION DETAILS ON THIS PLAN. A RAIN GAUGE SHALL BE INSTALLED AT THE PROJECT SITE FOR MONITORING.




Y:\North Carolina\TXS\051715-500672-00_Zebulon_Little_River_Park_Grading_Plan.dwg
Y:\North Carolina\TXS\051715-500672-00_Zebulon_Little_River_Park_Grading_Plan.dwg




V:\North Carolina\TXC\051715-500672-00_Zebulon_Utility_Plan.dwg 1715-500672-00-UTILITY PLAN.dwg







1 INSTALLATION OF D/W PIPE IN STREET SECTION N.T.S.




2 R7-8 HANDICAP SIGN N.T.S.




3 STANDARD SIGN INSTALLATION N.T.S.




4 STANDARD TREE PROTECTION N.T.S.



5 CONCRETE WHEELSTOP DETAIL N.T.S.




6 GRAVEL TRAIL N.T.S.




- NOTES:
- SEE SPECIFICATIONS FOR OTHER REQUIREMENTS.
 - HEAVY DUTY PAVEMENT AREAS INDICATED TO RECEIVE A NEW SURFACE/BINDER COURSE ON THE EXISTING BASE COURSE (OVERLAY) SHALL USE 2 1/2" OF 1-19.0B INTERMEDIATE COURSE AND 1" OF 9.5B SURFACE COURSE.
 - ASPHALT MIX SHALL NOT CONTAIN MORE THAN 30% RECYCLED ASPHALT PRODUCT (RAP).


7 ASPHALT PAVING SECTION N.T.S.




9 ASPHALT TRAIL OVER EXISTING GRAVEL TRAIL N.T.S.




10 CONCRETE SIDEWALK N.T.S.




11 PAINTED CROSSWALK N.T.S.




12 PAINTED DIRECTIONAL ARROWS N.T.S.




13 ACCESSIBLE PARKING / SIGNAGE / STRIPING N.T.S.





14 CONCRETE STEPS WITH HANDRAIL N.T.S.



15 SPLIT RAIL FENCE N.T.S.




16 TEMPORARY PROJECT SIGN N.T.S.




1 TEMPORARY SKIMMER BASIN

NCDEQ STD. 6.64




4 FILTER BAG FOR DEWATERING

N.T.S.





8 HARDWARE CLOTH AND GRAVEL INLET PROTECTION

NCDEQ STD. 6.51




9 TEMPORARY FILTER BERM BASIN

NCDEQ STD. 6.55




2 TEMPORARY POROUS BAFFLE

NCDEQ STD. 6.65





5 CONCRETE WASHOUT STATION

N.T.S.




9 TEMPORARY FILTER BERM BASIN

NCDEQ STD. 6.55




3A TACKING RATES

NCDEQ STANDARD 6.14





5 EROSION CONTROL PRODUCTS

NCDEQ STD. 6.17




9 TEMPORARY SLOPE DRAIN

NCDEQ STD. 6.32




3 MULCHING

NCDEQ STANDARD 6.14






5 GRASS-LINED CHANNELS

NCDEQ STD. 6.30




7 GRASS LINED SWALES

NCDEQ STD. 6.30




7 RIPRAP CHANNELS

NCDEQ STD. 6.31



7 RIPRAP CHANNELS

NCDEQ STD. 6.31



7 RIPRAP CHANNELS

NCDEQ STD. 6.31




NOTES:

1. A STABILIZED ENTRANCE PAD OF 2"-3" COURSE AGGREGATE SHALL BE LOCATED WHERE TRAFFIC WILL ENTER OR LEAVE THE CONSTRUCTION SITE ONTO A PUBLIC STREET.
2. FILTER FABRIC OR COMPACTED CRUSHER RUN STONE MAY BE USED AS A BASE FOR THE CONSTRUCTION ENTRANCE.
3. IF CONDITIONS AT THE SITE ARE SUCH THAT MOST OF THE MUD AND SEDIMENT ARE NOT REMOVED BY VEHICLES TRAVELING OVER THE GRAVEL, THE TIRES SHALL BE WASHED. WASHING SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS IN A SEDIMENT TRAP OR OTHER SUITABLE DISPOSAL AREA. A WASH RACK MAY ALSO BE USED.
4. SOIL STABILIZATION FABRIC (AS SPECIFIED BY THE DESIGNER) SHALL BE USED.

MAINTENANCE NOTES:

MAINTAIN THE GRAVEL PAD IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. THIS MAY REQUIRE PERIODIC TOPDRESSING WITH 2-INCH STONE. AFTER EACH RAINFALL, INSPECT ANY STRUCTURE USED TO TRAP SEDIMENT AND CLEAN IT OUT AS NECESSARY. IMMEDIATELY REMOVE ALL OBJECTIONABLE MATERIALS SPILLED, WASHED, OR TRACKED ONTO PUBLIC ROADWAYS.

1 CONSTRUCTION ENTRANCE
N.T.S.




NOTES:

1. DIG AN 8" TRENCH AND PLACE THE POSTS ON 10' CENTERS.
2. USE A TENSION BAR AND 3 CLAMPS TO SECURE THE MESH TO THE FIRST POST. PLACE MESH IN TRENCH AND ON THE UPHILL SIDE OF POSTS.
3. STRETCH THE MESH TIGHTLY AND ATTACH TO TERMINAL POST USING A TENSION BAR AND BANDS PER POST.
4. ATTACH MESH TO EACH POSTS WITH WIRE TIES, 3 PER POST.
5. RUN TENSION WIRE AT TOP AND BOTTOM OF THE MESH. ATTACH THE MESH TO THE TENSION WIRE USING HOOD RINGS 5' ON CENTER.
6. ATTACH THE SILT FENCE FABRIC TO THE MESH USING PLASTIC WIRE TIES 2' ON CENTER TOP AND BOTTOM.

MAINTENANCE NOTES:

1. FILTER BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS NEEDED SHALL BE MADE IMMEDIATELY.
2. SHOULD THE FABRIC DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL IS NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.
3. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT, ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS REMOVED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED.

5 TEMPORARY SUPER SILT FENCE
N.T.S.




CONSTRUCTION SPECIFICATIONS:

1. LAY ONE BLOCK ON EACH SIDE OF THE STRUCTURE ON ITS SIDE IN THE BOTTOM ROW TO ALLOW POOL DRAINAGE. THE FOUNDATION SHOULD BE EXCAVATED AT LEAST 2 INCHES BELOW THE CREST OF THE STORM DRAIN. PLACE THE BOTTOM ROW OF BLOCKS AGAINST THE EDGE OF THE STORM DRAIN FOR LATERAL SUPPORT AND TO AVOID WASHOUTS WHEN OVERFLOW OCCURS. IF NEEDED, GIVE LATERAL SUPPORT TO SUBSEQUENT ROWS BY PLACING 2 X 4 WOOD STUDS THROUGH BLOCK OPENINGS.
2. CAREFULLY FIT HARDWARE CLOTH OR COMPARABLE WIRE MESH WITH 1/2 INCH OPENINGS OVER ALL BLOCK OPENINGS TO HOLD GRAVEL IN PLACE.
3. USE CLEAN #57 STONE, 3 TO 1/2 INCH IN DIAMETER, PLACED 2 INCHES BELOW THE TOP OF THE BLOCK ON A 2:1 SLOPE OR FLATTER AND SMOOTH IT TO AN EVEN GRADE.

MAINTENANCE NOTES:

1. INSPECT, CLEAN, AND PROPERLY MAINTAIN THE EXCAVATED BASIN AFTER EVERY STORM UNTIL THE CONTRIBUTING DRAINAGE AREA HAS BEEN PERMANENTLY STABILIZED.
2. TO PROVIDE SATISFACTORY BASIN EFFICIENCY, REMOVE SEDIMENT WHEN THE VOLUME OF THE BASIN HAS BEEN REDUCED BY ONE-HALF. SPREAD ALL EXCAVATED MATERIAL EVENLY OVER THE SURROUNDING LAND AREA OR STOCKPILE AND STABILIZE APPROPRIATELY.

8 BLOCK AND GRAVEL DROP INLET PROTECTION
N.T.S.



GENERAL NOTES:

1. FILTER FABRIC FENCE SHALL BE A MINIMUM OF 32" IN WIDTH AND SHALL HAVE A MINIMUM OF 6 LINE WIRES WITH 12" STAY SPACING.
2. WOVEN FILTER FABRIC BE USED WHERE SILT FENCE IS TO REMAIN FOR A PERIOD OF MORE THAN 30 DAYS.
3. STEEL POSTS SHALL BE 5'-0" IN HEIGHT AND BE OF THE SELF-FASTENER ANGLE STEEL TYPE.
4. WIRE FENCING SHALL BE AT LEAST #10 GAGE WITH A MINIMUM OF 6 LINE WIRES WITH 12" STAY SPACING.
5. TURN SILT FENCE UP SLOPE AT ENDS.
6. WIRE MESH SHALL BE MIN. 13 GAGE WITH MAXIMUM 12" OPENINGS.
7. ORANGE SAFETY FENCE IS REQUIRED AT BACK OF SILT FENCE (WITHIN 5 FT.) WHEN GRADING IS ADJACENT TO SWIM BUFFERS OR WETLANDS (REFER TO SWIM BUFFER GUIDELINES).

MAINTENANCE NOTES:

1. INSPECT SEDIMENT FENCES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.
2. SHOULD THE FABRIC OF A SEDIMENT FENCE COLLAPSE, TEAR, DECOMPOSE OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY.
3. REMOVE SEDIMENT DEPOSITS AS NECESSARY TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE FENCE. TAKE CARE TO AVOID UNDERMINING THE FENCE DURING CLEANOUT.
4. REMOVE ALL FENCING MATERIALS AND UNSTABLE SEDIMENT DEPOSITS AND BRING THE AREA TO GRADE AND STABILIZE IT AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

2 SILT FENCE
N.T.S.


NOTES:

1. PLACE STONE TO THE LINES AND DIMENSIONS SHOWN IN THE PLAN ON A FILTER FABRIC FOUNDATION.
2. KEEP THE CENTER STONE SECTION AT LEAST 9 INCHES BELOW NATURAL GROUND LEVEL WHERE THE DAM ABUTS THE CHANNEL BANKS.
3. EXTEND STONE AT LEAST 1.5 FEET BEYOND THE DITCH BANK TO KEEP WATER FROM CUTTING AROUND THE ENDS OF THE CHECK DAM.
4. SET SPACING BETWEEN DAMS TO ASSURE THAT THE ELEVATION AT THE TOP OF THE LOWER DAM IS THE SAME AS THE TOE ELEVATION OF THE UPPER DAM.
5. PROTECT THE CHANNEL AROUND THE LOWEST CHECK DAM FROM HEAVY FLOW THAT COULD CAUSE EROSION.
6. MAKE SURE THAT THE CHANNEL REACH ABOVE THE MOST UPSTREAM DAM IS STABLE.
7. ENSURE THAT OTHER AREAS OF THE CHANNEL, SUCH AS CULVERT ENTRANCES BELOW THE CHECK DAMS, ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FORM DISPLACED STONES.

MAINTENANCE NOTES:

1. INSPECT CHECK DAMS AND CHANNELS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (1/2 INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. CLEAN OUT SEDIMENT, STRAW, LIMBS, OR OTHER DEBRIS THAT COULD CLOG THE CHANNEL WHEN NEEDED.
2. ANTICIPATE SUBMERGENCE AND DEPOSITION ABOVE THE CHECK DAM AND EROSION FROM HIGH FLOWS AROUND THE EDGES OF THE DAM. CORRECT ALL DAMAGE IMMEDIATELY. IF SIGNIFICANT EROSION OCCURS BETWEEN DAMS, ADDITIONAL MEASURES CAN BE TAKEN AS, INSTALLING A PROTECTIVE RIP RAP LINER IN THAT PORTION OF THE CHANNEL. (PRACTICE 6.31, RIPRAP-LINE AND PAVED CHANNELS).
3. REMOVE SEDIMENT ACCUMULATED BEHIND THE DAMS AS NEEDED TO PREVENT DAMAGE TO CHANNEL VEGETATION. ALLOW THE CHANNEL TO DRAIN THROUGH THE STONE CHECK DAM, AND PREVENT LARGE FLOWS FROM CARRYING SEDIMENT OVER THE DAM. ADD STONES TO DAMS AS NEEDED TO MAINTAIN DESIGN HEIGHT AND CROSS SECTION.

3 CHECK DAM
N.T.S.



NOTES:

1. CLASS OR MEDIAN SIZE OF RIPRAP AND LENGTH, WIDTH AND DEPTH OF APRON TO BE DESIGNED BY THE ENGINEER.
2. REFER TO THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES' EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL FOR RIPRAP APRON DESIGN STANDARDS.
3. RIPRAP SHOULD EXTEND UP BOTH SIDES OF THE APRON AND AROUND THE END OF THE PIPE OR CULVERT AT THE DISCHARGE OUTLET AT A MAXIMUM SLOPE OF 2:1 AND A HEIGHT NOT LESS THAN TWO THIRDS THE PIPE DIAMETER OR CULVERT HEIGHT.
4. THERE SHALL BE NO OVERFLOW FROM THE END OF THE APRON TO THE SURFACE OF THE RECEIVING CHANNEL. THE AREA TO BE PAVED OR RIPRAPPED SHALL BE UNDERCUT SO THAT THE INVERT OF THE APRON SHALL BE AT THE SAME GRADE (FLUSH) WITH THE SURFACE OF THE RECEIVING CHANNEL. THE APRON SHALL HAVE A CUTOFF OR TIE WALL AT THE DOWNSTREAM END.
5. THE WIDTH OF THE END OF THE APRON SHALL BE EQUAL TO THE BOTTOM WIDTH OF THE RECEIVING CHANNEL. MAXIMUM TAPER TO RECEIVING CHANNEL 5:1.
6. ALL SUBGRADE FOR STRUCTURE TO BE COMPACTED TO 95% OR GREATER.
7. THE PLACING OF FILL, EITHER LOOSE OR COMPACTED IN THE RECEIVING CHANNEL SHALL NOT BE ALLOWED.
8. NO BENDS OR CURVES IN THE HORIZONTAL ALIGNMENT OF THE APRON WILL BE PERMITTED.
9. FILTER FABRIC SHALL BE INSTALLED ON COMPACTED SUBGRADE PRIOR TO PLACEMENT OF RIP RAP.
10. ANY DISTURBED AREA FROM END OF APRON TO RECEIVING CHANNEL MUST BE STABILIZED.

MAINTENANCE NOTES:

1. RIPRAP SHOULD BE INSPECTED PERIODICALLY FOR SCOUR OR DISLODGED STONES. CONTROL OF WEED AND BRUSH GROWTH MAY BE NEEDED IN SOME LOCATIONS.

* d50 (SEE FIG. 8.06 A&B "NC SEDIMENT AND EROSION CONTROL MANUAL")
MAX = 1.5 X d50
T = 1.5 X DMAX

6 RIPRAP APRON
N.T.S.

SEEDING MIXTURE SPECIES	RATE (LB/ACRE)
RYE (GRASS)	120
SEEDING DATES	
MOUNTAINS-AUG. 15 - DEC. 30	
COASTAL PLAIN AND PIEDMONT-AUG. 15 - DEC. 30	
SOIL AMENDMENTS	
FOLLOW SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND 1,000 LB/ACRE 10-10-10 FERTILIZER.	
MULCH	
APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.	
MAINTENANCE	
REPAIR AND RE-FERTILIZE DAMAGED AREAS IMMEDIATELY. TOPDRESS WITH 50 LB/ACRE OF NITROGEN IN MARCH. IF NECESSARY TO EXTEND TEMPORARY COVER BEYOND JUNE 15, OVERSEED WITH 50 LB/ACRE KOBE (PIEDMONT AND COASTAL PLAIN) OR KOREAN (MOUNTAINS) LESPEDEZA IN LATE FEBRUARY OR EARLY MARCH.	


TEMPORARY SEEDING RECOMMENDATIONS FOR FALL

SEEDING MIXTURE SPECIES	RATE (LB/ACRE)
GERMAIN MILLET	40
IN THE PIEDMONT AND MOUNTAINS, A SMALL-STEMMED SUDANGRASS MAY BE SUBSTITUTED AT A RATE OF 50 LB/ACRE.	
SEEDING DATES	
MOUNTAINS-MAY 15 - AUG. 15	
PIEDMONT-MAY 1 - AUG. 15	
COASTAL PLAIN-APRIL 15 - AUG. 15	
SOIL AMENDMENTS	
FOLLOW SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND 750 LB/ACRE 10-10-10 FERTILIZER.	
MULCH	
APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.	
MAINTENANCE	
REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE, AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.	

TEMPORARY SEEDING RECOMMENDATIONS FOR SUMMER



SEEDING MIXTURE SPECIES	RATE (LB/ACRE)
RYE (GRASS)	120
ANNUAL LESPEDEZA (KOBE IN PIEDMONT AND COASTAL PLAIN, KOREAN IN MOUNTAINS)	50
OMIT ANNUAL LESPEDEZA WHEN DURATION OF TEMPORARY COVER IS NOT TO EXTEND BEYOND JUNE.	
SEEDING DATES	
MOUNTAINS-ABOVE 2500 FEET: FEB. 15 - MAY 15	
BELOW 2500 FEET: FEB. 1 - MAY 1	
PIEDMONT-JAN. 1 - MAY 1	
COASTAL PLAIN-DEC. 1 - APRIL 15	
SOIL AMENDMENTS	
FOLLOW SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND 750 LB/ACRE 10-10-10 FERTILIZER.	
MULCH	
APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.	
MAINTENANCE	
REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE, AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.	

TEMPORARY SEEDING RECOMMENDATIONS FOR LATE WINTER AND EARLY SPRING



10 PRE-CAST STORM MANHOLE
N.T.S.



D	T	A	B	C	E	L	HV	WT.
12"	2'-1/4"	4"	2'-3"	4'-0"	2'-0"	6'-1"	3:1	730
15"	2'-1/4"	6"	2'-3"	3'-10"	2'-0"	6'-1"	3:1	730
18"	2'-1/2"	9"	2'-3"	3'-10"	3'-0"	6'-1"	3:1	1190
24"	3"	10"	3'-8"	2'-6"	4'-0"	6'-2"	3:1	1770
30"	3'-1/2"	1'-0"	4'-8"	1'-8"	3'-0"	6'-2"	3:1	2380
36"	4"	1'-3"	5'-3"	2'-11"	6'-0"	8'-2"	3:1	5320
42"	4'-1/2"	1'-9"	5'-3"	2'-11"	6'-6"	8'-2"	3:1	5920
48"	5'	2'-0"	6'-3"	2'-2"	7'-0"	8'-2"	3:1	7470
54"	5'-1/2"	2'-3"	5'-6"	2'-10"	7'-6"	8'-4"	3:1	8810
60"	6"	2'-6"	5'-0"	3'-3"	8'-0"	8'-3"	3:1	11180
66"	6'-1/2"	3'-0"	6'-0"	2'-3"	8'-6"	8'-3"	3:1	12530
72"	7"	3'-0"	6'-6"	1'-9"	9'-0"	8'-3"	3:1	13680



GENERAL NOTES:



1. SEE CURRENT NCDOT STANDARD 310.01 FOR DETAILS.
2. REINFORCEMENT SHALL CONFORM TO THE REQUIREMENTS OF REINFORCED CONCRETE PIPE OF LIKE DIAMETER PER ASHOTO M170, TABLE 2, WALL B.
3. ALL CONCRETE TO BE 4000 P.S.I. COMPRESSIVE STRENGTH.
4. PROVIDE TONGUE OR SPIGOT JOINT AT INLET END SECTION.
5. PROVIDE GROOVE OR BELL JOINT AT OUTLET END SECTION.
6. THE DIMENSIONS FOR END SECTIONS SHALL SUBSTANTIALLY AGREE WITH THE TABLE. MINOR VARIATIONS WILL BE PERMITTED BASED ON THE MANUFACTURER'S STANDARD FORMS AND TEMPLATES.
7. NOT TO BE USED IN NCDOT MAINTAINED RIGHT OF WAY.

4 FLARED END SECTION
N.T.S.



7 15" AREA DRAIN
N.T.S.

*ALL GRATES SHALL BE PEDESTRIAN RATED/APPROVED






SECTION X-X

SECTION Y-Y

DIMENSIONS AND QUANTITIES									
DIMENSIONS OF BOX & PIPE			CONC.	TOTAL BRICK MASONRY		DEDUCTIONS			
PIPE SIZE	SPAN A	WIDTH B	HEIGHT C	PER FT. BRICK	PER FT. COPING	MIN. PER ONE PIPE	MIN. PER ONE PIPE	MIN. PER ONE PIPE	MIN. PER ONE PIPE
SIZE	A	B	H (MIN.)	C.U. YDS.	C.U. YDS.	C.M.	C.M.	R.C.	R.C.
12"	3'-0"	2'-0"	2'-8"	0.267	0.313	0.037	0.871	0.020	0.032
15"	3'-0"	3'-0"	3'-0"	0.267	0.313	0.037	0.976	0.031	0.047
18"	3'-0"	3'-0"	3'-0"	0.267	0.313	0.037	1.108	0.044	0.065
24"	3'-0"	2'-0"	4'-0"	0.267	0.313	0.037	1.289	0.078	0.113

4.1 DROP INLET
N.T.S.



* (1) ADAPTORS CAN BE MOUNTED ON ANY ANGLE 0° TO 359° TO DETERMINE MINIMUM ANGLE BETWEEN ADAPTORS SEE PLAN.

* (2) MAXIMUM RECOMMENDED OVERALL HEIGHT 10'

GENERAL NOTES:

1. SEDIMENT FILTER OUTLET AND HARDWARE CLOTH SHALL BE 18 INCHES HIGH BUT NOT TALLER THAN 18 INCHES.
2. HARDWARE CLOTH SHALL BE ANCHORED TO THE STEEL POSTS SECURELY USING APPROPRIATE ANCHORS. HARDWARE CLOTH SHALL BE KEPT IN A MINIMUM OF 12 INCHES IN LENGTH AND BACKFILLED PROPERLY AS SHOWN IN ABOVE DETAIL. HARDWARE CLOTH TO BE SAME AS STD. #6.62 (19 GAUGE, 1/4" SPACING).
3. POSTS SHALL BE NO MORE THAN 4 FEET APART.
4. SITE OUTLETS AT ANY POINT WHERE CONCENTRATED FLOWS ARE ANTICIPATED AND AT THE DIRECTION OF THE INSPECTOR.

MAINTENANCE NOTES:

1. FILTER OUTLETS SHALL BE INSPECTED BY THE FINANCIALLY RESPONSIBLE PARTY OR HIS AGENT IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS NEEDED SHALL BE MADE IMMEDIATELY.
2. THE STONE SHALL BE REPLACED PROMPTLY AFTER ANY EVENT THAT HAS CLOGGED OR REMOVED IT.
3. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN DEPOSITS REACH HALF THE HEIGHT OF THE BARRIER. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE OUTLET IS REMOVED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED.

11 TEMPORARY STONE OPENING IN SILT FENCE
N.T.S.

Seals:



Corp. NC License: F-1320

LITTLE RIVER PARK
1800 WEST GANNON AVENUE
ZEBULON, NORTH CAROLINA


Project No: 1725-500672.00
Date: 11.20.2025
Revisions:
Addendum #1 12.08.25

Sheet Title:
SITE CONSTRUCTION DETAILS


Sheet No:

C503


Y:\North Carolina\TXS-05\1725-500672-00_Zebulon_Little_River_Park_Doc\Drawings\1725-500672-00-DETAILS.dwg




4 **MANHOLE CONNECTION**
N.T.S.




5 **DROP MANHOLE FOR SANITARY SEWER**
N.T.S.




1 **TRENCH BOTTOM DIMENSIONS & BACKFILLING REQUIREMENTS FOR DUCTILE IRON**
N.T.S.




2 **TRENCH BOTTOM DIMENSIONS & BACKFILLING REQUIREMENTS FOR PVC GRAVITY SEWER MAIN**
N.T.S.



3 **TYPICAL SANITARY SEWER LATERAL CONNECTION**
N.T.S.



6 **CLEANOUT**
N.T.S.




7 **ASPHALT LAP JOINT**
N.T.S.

STREETSCAPE BUFFER REQUIREMENTS	
STREETSCAPE BUFFER	
SHALL MAINTAIN A MINIMUM WIDTH OF AT LEAST 15' FROM THE LOT LINE.	
STREETSCAPE BUFFERS SHALL NOT BE LOCATED WITHIN REQUIRED SIGHT DISTANCE TRIANGLE.	
STREETSCAPE BUFFERS SHALL BE CONFIGURED AS A TYPE 'C' SEMI-OPAQUE BUFFER EXCEPT THAT THE MINIMUM NUMBER OF REQUIRED SHRUBS IS REDUCED FROM 25 TO 20, AND THE ON-CENTER SPACING IS REDUCED TO 5'.	
PLANT MATERIAL REQUIREMENTS	
4 UNDERSTORY TREES PER 100 LF (MAXIMUM SPACING OF 16' O.C.)	
6 UNDERSTORY TREES PER 100 LF (MAXIMUM SPACING OF 16' O.C.)	
20 SHRUBS PER 100 LF MAXIMUM SPACING OF 5' O.C.	
(75% OF REQUIRED SHRUBS NEED TO BE EVERGREEN)	
LOCATION	WATER PLANT ROAD FRONTAGE (OVERHEAD POWER LINES PRESENT)
TOTAL LF	324 LF
BUFFER WIDTH	15'
REQUIRED CANOPY TREES	N/A (OVERHEAD POWER LINES PRESENT)
REQUIRED UNDERSTORY TREES	33 REQUIRED UNDERSTORY TREES
PROVIDED UNDERSTORY TREES	33 PROVIDED UNDERSTORY TREES
REQUIRED SHRUBS	65 REQUIRED SHRUBS
PROVIDED SHRUBS	67 PROVIDED SHRUBS

PARKING LOT REQUIREMENTS	
ALL PARKING LOTS SHALL BE SERVED BY:	
ONE CANOPY TREE FOR EVERY 12 OFF-STREET PARKING SPACES PROVIDED.	
REQUIRED CANOPY TREES MAY BE PLACED AROUND, IN, OR NEAR THE PARKING LOT PROVIDED THAT NO PARKING SPACE IS MORE THAN 50' FROM THE TRUNK OF A CANOPY TREE.	
REQUIRED CANOPY TREES SHALL BE DISTRIBUTED THROUGHOUT PARKING AREAS AND MAY BE LOCATED IN LANDSCAPE ISLANDS, BETWEEN ROWS OF PARKING, IN DRIVEWAY MEDIANS, AND WITHIN TEN FEET OF THE PERIMETER OF THE PARKING LOT.	
A SINGLE CONTINUOUS ROW OF EVERGREEN SHRUBS PLANTED NO GREATER THAN THREE FEET ON-CENTER AND WITHIN FIVE FEET OF THE PARKING LOT EDGE.	
PARKING SPACES	50 SPACES / 12 = 5 TREES
REQUIRED CANOPY TREES	5 REQUIRED CANOPY TREES
PROVIDED CANOPY TREES	5 PROVIDED CANOPY TREES


SITE LANDSCAPING REQUIREMENTS	
ONE CANOPY TREE FOR EVERY 2,000 SQUARE FEET OF LOT AREA FOR THE FIRST 20,000 SQUARE FEET OF A LOT.	
20,000 SF / 2,000 SF =	10 CANOPY TREES
REQUIRED CANOPY TREES	10 REQUIRED CANOPY TREES
PROVIDED CANOPY TREES	10 PROVIDED CANOPY TREES

PERIMETER BUFFER REQUIREMENTS	
PLANT MATERIAL REQUIREMENTS	
4 UNDERSTORY TREES PER 100 LF	
15 SHRUBS PER 100 LF (50% MINIMUM EVERGREEN SHRUBS)	
BUFFER LOCATION	EASTERN & NORTHERN PROPERTY BOUNDARY
BUFFER TYPE	TYPE 'A'
BUFFER LF	507 LF
BUFFER WIDTH	10' WIDE
TOTAL CANOPY TREES REQUIRED	NONE
TOTAL UNDERSTORY TREES REQUIRED	20 UNDERSTORY TREES REQUIRED
TOTAL UNDERSTORY TREES PROVIDED	20 UNDERSTORY TREES PROVIDED
TOTAL SHRUBS REQUIRED	75 SHRUBS REQUIRED
TOTAL SHRUBS PROVIDED	75 SHRUBS PROVIDED



PLANT SCHEDULE						
SYMBOL	CODE	QTY	BOTANICAL / COMMON NAME	ROOT	CAL.	REMARKS
CANOPY TREES						
	GI	7	Gleditsia triacanthos inermis 'Skycole' / Skyline® Honey Locust	B & B	2.5" Cal	
	NS	7	Nyssa sylvatica / Tupelo	B & B	2.5" Cal	
	QH	8	Quercus lyrata 'QLFTB' / Highbeam® Overcup Oak	B & B	2.5" Cal	
UNDERSTORY TREES						
	AG	18	Amelanchier x grandiflora 'Autumn Brilliance' / Autumn Brilliance Apple Serviceberry	B & B	1.5" Cal. min.	
	BD	16	Betula nigra 'Duraheat' / Duraheat River Birch	B & B	1.5" Cal. min.	Single Stem
	CV	10	Chionanthus virginicus / White Fringetree	B & B	1.5" Cal. min.	
	CV2	15	Crataegus viridis 'Winter King' / Winter King Hawthorn	B & B	1.5" Cal. min.	
SYMBOL	CODE	QTY	BOTANICAL / COMMON NAME	CONT	REMARKS	HEIGHT
SHRUBS						
	CW	18	Callicarpa americana 'Welch's Pink' / Welch's Pink American Beautyberry	3 gal		18" MIN.
	IS	10	Ilex glabra 'Shamrock' / Shamrock Inkberry Holly	3 gal		18" MIN.
	IV	31	Itea virginica 'Henry's Garnet' / Henry's Garnet Sweetspire	3 gal		18" MIN.
SHRUBS - EVERGREEN						
	IN2	20	Ilex vomitoria 'Nana' / Dwarf Yaupon Holly	3 gal		18" MIN.
	MT	57	Myrica cerifera 'Tom's Dwarf' / Tom's Dwarf Wax Myrtle	3 gal		18" MIN.
SYMBOL	CODE	QTY	BOTANICAL / COMMON NAME	CONT	REMARKS	SPACING
GROUND COVERS						
	PE2	107,635 sf	Pollinator meadow Mix / See Specs.	seed		
	SN	83,566 sf	Seeded lawn / See Specs.	seed		
	PE3	8,273 sf	Shade meadow Mix / See Specs.	seed		

LEGEND	
	SIGN
	EXISTING LIGHT POLE
	EXISTING UTILITY POLE
	ACCESSIBLE SPACE
	EXISTING FIRE HYDRANT
	EXISTING TREE TO REMAIN
	PROPOSED GROUND COVER
	PLANT LABEL
	PLANT QUANTITY
	EXISTING CURB AND GUTTER
	PROPOSED CURB AND GUTTER
	PROPERTY LINE
	EXISTING FENCE
	PROPOSED FENCE
	EXISTING UNDERGROUND ELECTRIC LINE
	UGE
	EXISTING OVERHEAD UTILITY LINE
	EXISTING TREE LINE
	PROPOSED TREE LINE AFTER CLEARING
	PROPOSED MULCH LINE
	PROPOSED STORM DRAINAGE PIPE
	PROPOSED FOUNDATION DRAIN
	SANITARY SEWER LINE
	WATER LINE



Seals:



Corp. NC License: F-1320

LITTLE RIVER PARK

1800 WEST GANNON AVENUE
ZEBULON, NORTH CAROLINA

Project No: 1725-500672.00
Date: 11.20.2025
Revisions:
Addendum #1 12.08.25

Sheet Title:
LANDSCAPE PLAN

Sheet No:
C601